



EXPANSION JOINT DETAILS

- NOTES :**
- 1 Fabric to cover entire construction joint. Caulk securely into grooves. Fabric and V-Strips to be placed at construction joints in mudwall of R.C.G. superstructures.
  - 2 Expansion material in joints is preformed joint filler.
  - 3 Copper flashing is to be lapped 2" and soldered, subject to approval.

CONSTRUCTION JOINT DETAIL

INDIANA DEPARTMENT OF TRANSPORTATION	
CONSTRUCTION & EXPANSION JOINT DETAILS	
MAY 2000	
STANDARD DRAWING NO. E 724-BJTS-05	
	/s/ Anthony L. Uremovich 11-15-99 DESIGN STANDARDS ENGINEER DATE
	/s/ Firooz Zandi 11-15-99 CHIEF HIGHWAY ENGINEER DATE
DESIGN STANDARDS ENGINEER	