



November 3, 2014

ROOT CAUSE ANALYSIS REPORT

Downtown Underground Network Event on August 13, 2014



- 1. Introductions & Overview
- 2. Root Cause Analysis Review
- 3. O'Neill Management Consultants Review
- 4. IPL Action Plan
- 5. Response to IURC Data Requests
- 6. Q&A



Kelly Huntington

President & CEO

Joe Bentley

Senior Vice President, Customer Operations

Mike Holtsclaw

Director, T&D Engineering

Jim Sadtler

Director, Transmission Field Operations

Kelly Millhouse

Director, Substations and AC Networks



Root Cause Analysis Review



IPL OPERATORS RESPONDED QUICKLY TO SAFELY RESOLVE EVENT WITHIN 15 MINUTES

Time	Occurrence
1:25p	 Conflicting 911 calls reporting smoke and loud banging noise from underground structure and smoke from manholes at 100 S Meridian Street
1:31p	- 1 st IFD units on scene
1:33p	- IPL Team Leader Field Service on scene
1:40p	 IPL Transmission Operations Control Center operator opens Gardner Lane UG 651 feeder breaker Event ends




IPL IMMEDIATELY CONDUCTED ITS INVESTIGATION AND INITIATED A ROOT CAUSE ANALYSIS PROCESS

- Evidence preservation began immediately
- Assembled In-house team
- Contacted Eaton Corporation the next day
- Gathered Data
 - YouTube Videos & Security Video
 - IFD information
 - Maintenance & Inspection Records
 - Network Protector Information
 - PI Historian data (Network SCADA & ECS SCADA)
- Analyzed Data
- Developed Conclusions & Action Plans




26 S MERIDIAN STREET 480-VOLT SPOT NETWORK VAULT





IPL'S ROOT CAUSE ANALYSIS IDENTIFIED THE TWO POSSIBLE EVENT SCENARIOS



PRIMARY SWITCH
COMPARTMENT
CLOSED-OPEN-GROUND



THE EVENT WAS COMPLETELY CONTAINED IN THE NETWORK PROTECTOR

 The Network Protector door remained closed which reduced damage to other vault equipment







O'Neill Management Consultants Review



IPL Action Plan



IPL HAS A THOROUGH PLAN TO OPTIMIZE DOWNTOWN NETWORK OPERATIONS

	Action Plan	Timing
1	Replace all 480-Volt Network Protectors	12/31/2018
2	Document Network Event Response Plan	3/31/2015
3	Meet with Indianapolis Fire Department	9/10/2014
4	Develop Mitigation Strategy	3/31/2015
5	Conduct Review of Gateway Vault Communications	3/31/2015
6	Enhance Network Protector Inspection Process	11/1/2014
7	Update Succession Plans	June 1st Annually
8	Conduct Staff Training	June 1st Annually
9	Enhance Audit Maintenance & Inspection Records Process	3/31/2015



- Replace <u>ALL</u> 480-Volt Network Protectors
 - Will replace all 480-Volt network protectors
 - 137 protectors in 44 vaults
 - Developed a five year program to replace approximately 30 per year
 - Estimated capital cost of \$15M
- Verify the location of all 58 pre-1985 Westinghouse CM-22 network protectors - <u>COMPLETE</u>
- Re-prioritize the replacement program sequence <u>COMPLETE</u>




- Complete change outs by <u>December 31, 2018</u>
- Timetable allows for minimizing customer outages during the change-out and reduces reliability risks for the downtown network
- Responsible Party: Director, Transmission Field Operations



IPL'S ROOT CAUSE ANALYSIS IDENTIFIED THE TWO POSSIBLE EVENT SCENARIOS

26 S Meridian Street 480-Volt Spot Network Vault





- Document a formal written Network Event Response and Test Plan including:
 - Identification of key personnel
 - Event notification
 - Incident command structure for handling network events
 - Identification of on-scene IPL incident commander
 - Annual tabletop drill of the plan
- Complete Plan by March 31, 2015
- Responsible Party: Director, T&D Engineering



- Schedule meeting with the Indianapolis Fire Department - <u>COMPLETE</u>
 - Review the response for a network event
 - Discuss coordination with IPL
 - Discuss lessons learned from August 13th event
 - Meeting was held on 9/10/14 and feedback will be incorporated in Network Event Response Plan (Recommendation #2)
- Meeting was held on <u>September 10, 2014</u>
- Responsible Party: Director, T&D Engineering



- Develop a mitigation strategy that limits severity and consequences of a network transformer or network protector failure
 - Better information at the substation level
- Complete Action Plan, including identification of major milestones for selected strategy by <u>March 31</u>, 2015
- Responsible Party: Director, Asset Management



- Conduct a review of all Gateway Vault circuits for communications stability and frequency of telemetry errors
 - Determine frequency of communication errors
 - Review response process for Network SCADA communication errors and who is notified
 - Review the routing of Blue Network SCADA communications cable in the vaults. Determine if there is a way to provide increased fire protection during an event.
- Complete Review and Develop Action Plan, including major milestones by <u>March 31, 2015</u>
- Responsible Party: Director, Transmission Field Operations



IPL ACTION PLAN | #6

- Enhance the network protector inspection process
 - Add visual inspection of the bottom area around the transformer bus in the network protector for debris or evidence of tracking on the bus support insulators <u>Added to tablet electronic inspection form</u>
 - Add visual inspection of the network protector bushing for signs of cracks or tracking - <u>Added to tablet</u> <u>electronic inspection form</u>



- Complete Changes to tablet software by <u>November 1,</u> 2014
- Responsible Party:
 Director, Asset
 Management



- Update Staffing Plans
 - Ensure no critical loss of institutional knowledge
 - Continue to monitor, update, and implement the Company's succession plan for key staff responsible for network operations and emergency response
 - Includes control room staff, first responders, engineering support, and those responsible for public and customer communications
- Complete by <u>June 1st</u> annually
- Responsible Party: Customer Operations Leadership



Staff Training

- Actively participate in industry forums and conferences where other companies that operate secondary network systems also participate
 - Example: 2015 Eaton Electrical Network Systems Conference
- Annual funding for travel and memberships is included in O&M budget
- Complete by <u>June 1st</u> annually
- Responsible Party: Customer Operations Leadership



- Network Inspection Process Audit
 - Implement process to verify inspection data from tablets is downloaded properly to on-line systems - <u>COMPLETE</u>
 - Implement periodic auditing of maintenance and inspection records for completeness
 - Conduct audit of back office process to improve and assure the retrieval and completeness of inspection and maintenance records in master database
- Complete Process Audit and develop Action Plan to address any gaps identified by <u>March 31, 2015</u>
- Responsible Party: Director, Asset Management



Responses to IURC Data Requests



IPL ENGAGES IN SUCCESSION PLANNING

Long-Term Succession Planning

- Downtown Network is supported by an organization of 72 people and IPL regularly reviews scheduled work activities to optimize this number
- The downtown network has an integrated web of leadership that is not dependent on any one individual
- IPL's Power Delivery Staffing Study analyzes specific workforce and future needs to help support the succession plan process
- IPL leverages this information to identify and develop individuals for all positions



IPL IS COMMITTED TO MAINTAINING A SKILLED WORKFORCE

- Multi-faceted approach to succession planning
 - Hiring the right people
 - Job rotations
 - On-the-job training
 - External formal training and conferences
 - System and Technical enhancements
 - Coaching and mentoring of young professionals



IPL HAS STRENGTHENED THE RIGOR OF POWER DELIVERY ASSET MANAGEMENT

- Asset Management Framework
 - Maintenance/Inspection and capital investment
 - Asset replacement programs for downtown network
 - Systematic approach using performance indicators
- Power Delivery Organization integrated with DP&L as part of the new Customer Operations Organization
 - Ensures continued high reliability provided in an efficient and effective manner
 - Provides additional people resources and increased opportunities to share best practices and knowledge



- IPL's downtown network system is safe and reliable
- IPL is committed to taking the necessary actions to assure the continued safe and reliable operation of its downtown network
- IPL continues to take actions to reduce the likelihood and impact of any future occurrences within its downtown network system



Questions





November 3, 2014

ROOT CAUSE ANALYSIS REPORT

Downtown Underground Network Event on August 13, 2014



Appendix




APPENDIX: POST EVENT UG 651 NETWORK PROTECTOR








Customer Operations Organization Attachment





Design Engineering Group Attachment




Legend
Green-Key Positions @ IPL
Yellow-Backup Positions @ IPL
Blue-Mutual Assistance/Supplemental to Key Positions located @ DPL


*Team Leader Major Underground Projects Engineering



IPL Major Underground Projects Engineering Group Attachment











IPL Substation and Network Field Operations Group Attachment



Legend
Green-Key Positions @ IPL
Yellow-Backup Positions @ IPL
Blue-Mutual Assistance/Supplemental to Key Positions located @ DPL



DPL Substations & AC Network Team Attachment





DPL Substations and AC Network Team Attachment (Continued)

