Pre-Cast Post Cross-section

Pre-cast Post
with Bracket

12" diameter minimum hole

Hole Depth minimum based on
height of sidewalls:
Up to 14 feet = 36" Deep
Up to 18 feet = 42" Deep
Above 18 feet = 48" Deep

Pin to prevent
uplift

12" diameter x 4" minimum
thick cement cookie or
equivalent engineered
support required