


STORAGE BUILDING

INDIANA DEPARTMENT OF NATURAL RESOURCES

MORaine NATURE PRESERVE

PROJECT NO. E160010



Certified by:

LOCATION MAP



DRAWINGS INDEX

- GENERAL**
G-1 DRAWINGS INDEX, LOCATION MAPS
- CIVIL ENGINEERING**
C-1 SITE PLAN
C-2 SITE GRADING PLAN & DRAINAGE PLAN
- STRUCTURAL / ARCHITECTURAL**
A-1 FOUNDATION PLAN, FLOOR PLAN, DESIGN DATA
A-2 WALL SECTION, DETAILS
A-3 WALL SECTIONS, DETAILS
A-4 SHEAR WALLS PLAN & ELEVATIONS, DETAILS
A-5 BUILDING ELEVATIONS, DOOR SCHEDULE, FINISH SCHEDULE
- PLUMBING / ELECTRICAL**
P-1 HOT & COLD WATER PLAN, ISOMETRIC
P-2 SANITARY PLAN, ISOMETRIC
E-1 LIGHTING PLAN, FIXTURES SCHEDULE
E-2 RECEPTACLE PLAN

PROJECT INFORMATION

BUILDING ADDRESS: Moraine Nature Preserve
275 E 650 N
Valparaiso, IN 46383

COUNTY: Porter

OCCUPANCY TYPE: S-2

CONSTRUCTION TYPE: TYPE V B
INDIANA BUILDING CODE 2014 EDITION

ZONING AUTHORITIES: N/A


BUILDING AREA:
Un-heated 1713 square feet
Semiheated 1047 square feet
TOTAL 2760 square feet

OCCUPANT LOAD: 2 people - part time.

BUILDING ENVELOPE for Semiheated part Climate Zone 5 A

ROOF: Attic - Batt Insulation R-38
Walls Above-Grade: Batt Insulation R-19
Walls Below-Grade: NR
Slab-On-Grade: Perimeter Rigid Insulation R-10 for 12"
Garage Door: Rigid Insulation R-14.8 - see Drawing A-5
Pedestrian Door: Rigid Insulation R-14.8 - See Drawing A-5
Windows: R-2.4 - See Drawing A-5

VICINITY MAP



STORAGE BUILDING
MORaine NATURE PRESERVE
DEPT. OF NATURAL RESOURCES
275 E 650 N
VALPARAISO, INDIANA 46383



STATE OF INDIANA
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF ENGINEERING
ROOM W209, INDIANA GOVERNMENT CENTER SOUTH
402 WEST WASHINGTON STREET
INDIANAPOLIS, INDIANA 46204
TEL: 317-232-4150, FAX: 317-231-285

Revisions:

Project Number: E160010
Requisition Number:
Designer: Drawing Date: 09-13-17
Drafter: Drawing Scale: AS NOTED
DNR Approval:
Client Approval:

File Number: 400-071
Drawing Number:

G-1
Sheet 1 of 12

Sources: Esri, HERE, DeLorme, USGS, Intermap, INCREMENT P, NRCan, Esri Japan, METI, Esri China (Hong Kong), Esri Korea, Esri (Thailand), MspnyIndia, NGCC, © OpenStreetMap contributors, and the GIS User Community