

Date: **January 16, 2025**

**Addendum No. 1  
To Specifications For  
Project No. **ENG2503724272****

**Description: Charlestown State Park Culvert Replacement Project**  
**Location: 3000 State Park Drive; Clark County Indiana**

FOR AGENCY: Department of Natural Resources

The information contained in this Addendum shall become a part of the basic plans and specifications the same as if original incorporated therein. The original plans and specifications shall remain in their entirety, except as modified by this Addendum. The items herein shall supersede information in the specifications and on the plans.

ITEM No. 1: Please change the completion date to May 1, 2026, not May 1, 2025.

ITEM No. 2: Please replace the Schedule of Values and Supplemental Unit Price Request Sheet with the enclosed.

END OF ADDENDUM

Schedule of Values  
 Charlestown State Park  
 Culvert Replacements

Indiana Department of Natural Resources  
 12/2/2024

Item No.	Item Description	Quantity	Units	Unit Price	Amount
105-0000A	Remediation Allowance	1	LS		
105-06845	Construction Engineering	1	LS		
110-01001	Mobilization and Demobilization	1	LS		
201-52370	Clearing Right of Way	1	LS		
203-02000	Excavation, Common	638	CYS		
203-02070	Borrow	191	CYS		
205-0000A	Erosion Control	1	LS		
207-09935	Subgrade Treatment, Type IC	529	SYS		
211-09265	Structure Backfill, Type 2	181	CYS		
214-12238	Geotextile for Pavement, Type 2A	27	SYS		
214-12239	Geotextile for Pavement, Type 2B	948	SYS		
301-12233	Compacted Aggregate, No. 8	10	CYS		
301-12234	Compacted Aggregate, No. 53	162	CYS		
304-12623	HMA Patching, Full Depth, Type B	220	TON		
306-08043	Milling, Transition	25	SYS		
401-10258	Joint Adhesive, Surface	356	LFT		
401-10259	Joint Adhesive, Intermediate	348	LFT		
401-11785	Liquid Asphalt Sealant	356	LFT		
402-0000A	HMA Surface, Type B (1-1/2")	46	TON		
402-0000B	HMA Intermediate, Type B (2-1/2")	73	TON		
402-0000C	HMA Base, Type B (6")	179	TON		
406-05520	Asphalt for Tack Coat	1	TON		
616-05688	Riprap, Class I	436	TON		
616-06405	Riprap, Revetment	347	TON		
616-12249	Geotextile For Riprap Type 2B	1273	SYS		
621-01004	Mobilization and Demobilization for Seeding	1	EA		
621-02770	Erosion Control Blanket	818	SYS		
621-06559	Mulched Seeding R	818	SYS		
715-05019A	CLV 96442 - Pipe, Type 1, Circular, Diameter 36 In.	65	LFT		
715-05019B	CLV 96358 - Pipe, Type 1, Circular, Diameter 36 In.	80	LFT		
715-05123	CLV-96352 - Pipe, Type 1, Circular, Diameter 24 In.	76	LFT		
715-05127	CLV 535 - Pipe, Type 1, Circular, Diameter 42 In.	64	LFT		
715-04632	Pipe End Section, Precast Concrete, Diameter 36 In.	2	EA		
715-04632A	Pipe End Section, Precast Concrete, Diameter 24 In.	1	EA		
715-11643	Pipe End Section, Precast Concrete w/ Energy Dissipator, Diameter 36 In.	2	EA		
715-11643	Pipe End Section, Precast Concrete w/ Energy Dissipator, Diameter 24 In.	1	EA		
715-11643	Pipe End Section, Precast Concrete w/ Energy Dissipator, Diameter 42 In.	1	EA		
801-06775	Maintaining Traffic	1	LS		
	Base Bid - Subtotal				
	Unit Price No.1 - CLV 96352, Pump Around	1	LS		
	Unit Price No.2 - CLV 96358, Pump Around	1	LS		
	Unit Price No.3 - CLV 535, Pump Around	1	LS		
	Unit Price No.4 - CLV 96442, Pump Around	1	LS		
	Alternate No. 1 - HMA Overlay	1	LS		
	Total				

CHARLESTOWN STATE PARK  
Culvert Replacement Project

**SUPPLEMENTAL UNIT PRICE**

The contractor agrees to accept the following unit prices to adjust the amount of the contract, if actual site conditions or later changes in the design require additional work. These unit prices shall be submitted with the lump sum bid.

1. PUMP AROUND AT CLV-96352

\$ \_\_\_\_\_ / LS

2. PUMP AROUND AT CLV-96358

\$ \_\_\_\_\_ / LS

3. PUMP AROUND AT CLV-535

\$ \_\_\_\_\_ / LS

4. PUMP AROUND AT CLV-96442

\$ \_\_\_\_\_ / LS

Name of bidder: \_\_\_\_\_

Date: \_\_\_\_\_