

**Schedule of Pay Items Letting Date November 10, 2020 Letting ID 201110**

Call: 111

Contract: R -39587-A

Section No.: 1 INTERSECTION IMPROVEMENT, ROUNDABOUT

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	5.00 EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0004	109-08360	CONTRACT LIENS	1.00 DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0012	202-02279	CURB AND GUTTER, REMOVE	1815.00 LFT
0013	202-52710	SIDEWALK CONCRETE, REMOVE	875.00 SYS
0014	203-02000	EXCAVATION, COMMON	3230.00 CYS
0015	205-12108	STORMWATER MANAGEMENT BUDGET	32080.00 DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0017	205-12618	SWQCP PREPARATION	1.00 LS
0018	207-08264	SUBGRADE TREATMENT, TYPE II	1985.00 SYS
0019	207-12498	SUBGRADE TREATMENT, TYPE ID	5591.00 SYS
0020	211-09264	STRUCTURE BACKFILL, TYPE 1	2238.00 CYS
0021	301-12234	COMPACTED AGGREGATE NO. 53	711.00 CYS
0022	302-07455	DENSE GRADED SUBBASE	122.00 CYS
0023	304-12625	HMA PATCHING FULL DEPTH TYPE C	9.00 TON
0024	306-08036	MILLING, ASPHALT, 2 IN.	263.00 SYS
0025	401-07345	QC/QA-HMA, 2, 70, SURFACE, 12.5 mm	486.00 TON
0026	401-07397	QC/QA-HMA, 2, 70, INTERMEDIATE, 19.0 mm	570.00 TON
0027	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	798.00 TON
0028	401-10258	JOINT ADHESIVE, SURFACE	1127.00 LFT
0029	401-10259	JOINT ADHESIVE, INTERMEDIATE	1127.00 LFT
0030	401-11785	LIQUID ASPHALT SEALANT	1127.00 LFT
0031	406-05520	ASPHALT FOR TACK COAT	3.00 TON

0032	502-06457	PCCP, 9 IN.	273.00	SYS
0033	503-05240	D-1 CONTRACTION JOINT	216.00	LFT
0034	604-05528	HMA FOR SIDEWALK	198.00	TON
0035	604-06070	SIDEWALK, CONCRETE	552.00	SYS
0036	604-08086	CURB RAMP, CONCRETE	302.00	SYS
0037	604-12083	DETECTABLE WARNING SURFACES	36.00	SYS
0038	604-95344	HAND RAIL, PEDESTRIAN	229.00	LFT
0039	605-06120	CURB, CONCRETE	656.00	LFT
0040	605-06140	CURB AND GUTTER, CONCRETE	2381.00	LFT
0041	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	233.00	LFT
0042	605-06255	CENTER CURB, D CONCRETE	11.00	SYS
0043	605-90726	CURB, CONCRETE, DEPRESSED	80.00	LFT
0044	605-96305	CURB AND GUTTER, CONCRETE DEPRESSED	100.00	LFT
0045	610-07487	HMA FOR APPROACHES, TYPE B	96.00	TON
0046	610-08446	PCCP FOR APPROACHES, 6 IN.	518.00	SYS
0047	611-06497	MAILBOX ASSEMBLY, SINGLE	5.00	EACH
0048	615-06490	RIGHT-OF-WAY MARKER	27.00	EACH
0049	615-06505	MONUMENT, B	22.00	EACH
0050	616-06405	RIPRAP, REVETMENT	17.00	TON
0051	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	10.00	SYS
0052	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0053	621-06545	FERTILIZER	1.00	TON
0054	621-06554	SEED MIXTURE U	140.00	LBS
0055	621-06565	MULCHING MATERIAL	2.00	TON
0056	621-06567	WATER	4.00	kGAL
0057	621-06575	SODDING, NURSERY	777.00	SYS
0058	622-05650	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 IN. TO 2.5 IN.	20.00	EACH
0059	628-09402	FIELD OFFICE, B	9.00	MOS
0060	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0061	628-11977	COMPUTER SYSTEM	2.00	EACH
0062	629-12029	PLANT GROWTH LAYER	4155.00	SYS
0063	715-01898	WATER MAIN, DUCTILE IRON, 10 IN.	200.00	LFT
0064	715-04596	WATER SERVICE	2.00	EACH
0065	715-04995	LINE STOP	4.00	EACH
0066	715-04995	LINE STOP	2.00	EACH
0067	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	2768.00	LFT
0068	715-05121	PIPE, TYPE 1, CIRCULAR, 18 IN.	5.00	LFT

0069	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	1523.00	LFT
0070	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	528.00	LFT
0071	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	50.00	LFT
0072	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	273.00	LFT
0073	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	100.00	LFT
0074	715-05161	PIPE, TYPE 2, CIRCULAR, 48 IN.	669.00	LFT
0075	715-05409	PIPE, SANITARY SEWER, 10 IN.	10.00	LFT
0076	715-09064	VIDEO INSPECTION FOR PIPE	3158.00	LFT
0077	715-09475	STORMWATER QUALITY STRUCTURE	1.00	EACH
0078	715-09883	VALVE WITH BOX	2.00	EACH
0079	715-09883	VALVE WITH BOX	1.00	EACH
0080	715-46010	PIPE END SECTION, DIAMETER 18 IN.	1.00	EACH
0081	715-46020	PIPE END SECTION, DIAMETER 24 IN.	1.00	EACH
0082	715-91742	WATER METER RELOCATE	1.00	EACH
0083	715-94780	WATER MAIN, DUCTILE IRON, 6 IN.	15.00	LFT
0084	715-96669	WATER MAIN, DUCTILE IRON, 16 IN.	65.00	LFT
0085	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	2768.00	LFT
0086	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	3077.00	SYS
0087	718-52610	AGGREGATE FOR UNDERDRAINS	312.00	CYS
0088	720-44000	CASTING, ADJUST TO GRADE	1.00	EACH
0089	720-45030	INLET, E7	5.00	EACH
0090	720-45410	MANHOLE, C4	12.00	EACH
0091	720-45510	MANHOLE, C4 MODIFIED	1.00	EACH
0092	720-45605	STRUCTURE, MANHOLE, RECONSTRUCTED	2.00	LFT
0093	720-92884	MANHOLE, K4 MODIFIED	4.00	EACH
0094	720-93501	MANHOLE, L4	1.00	EACH
0095	720-94612	MANHOLE, K4	3.00	EACH
0096	720-95422	MANHOLE, J4	1.00	EACH
0097	720-98174	INLET, B15	16.00	EACH
0098	720-98555	INLET, C15	21.00	EACH
0099	720-98869	MANHOLE, L4 MODIFIED	1.00	EACH
0100	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00	EACH
0101	801-06625	DETOUR ROUTE MARKER ASSEMBLY	86.00	EACH
0102	801-06640	CONSTRUCTION SIGN, A	28.00	EACH
0103	801-06645	CONSTRUCTION SIGN, B	15.00	EACH
0104	801-06775	MAINTAINING TRAFFIC	1.00	LS
0105	801-07118	BARRICADE, III-A	160.00	LFT

0106	801-07119	BARRICADE, III-B	96.00	LFT
0107	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	301.00	LFT
0108	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	132.00	LFT
0109	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	148.00	SFT
0110	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	152.00	SFT
0111	807-02191	HANDHOLE LIGHTING	5.00	EACH
0112	807-03950	LUMINAIRE ORNAMENTAL	12.00	EACH
0113	807-03951	LIGHT POLE ORNAMENTAL	12.00	EACH
0114	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	176.00	LFT
0115	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	1235.00	LFT
0116	807-11981	LIGHTING FOUNDATION, CONCRETE WITH GROUNDING 36 IN. DIA X 96 IN.	12.00	EACH
0117	807-86810	SERVICE POINT, II	1.00	EACH
0118	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	672.00	LFT
0119	807-86910	CONNECTOR KIT, UNFUSED	12.00	EACH
0120	807-86915	CONNECTOR KIT, FUSED	12.00	EACH
0121	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	32.00	EACH
0122	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	8.00	EACH
0123	807-86930	INSULATION LINK, NON-WATERPROOFED	16.00	EACH
0124	807-86935	INSULATION LINK, WATERPROOFED	20.00	EACH
0125	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	320.00	LFT
0126	808-11691	LINE, THERMOPLASTIC, DOTTED, WHITE, 12 IN.	42.00	LFT
0127	808-12032	GROOVING FOR PAVEMENT MARKINGS	2260.00	LFT
0128	808-12148	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 36 IN.	62.00	LFT
0129	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	118.00	LFT
0130	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2100.00	LFT
0131	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	8.00	EACH
0132	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	20.00	EACH

Call: 121

Contract: R -39733-A

Section No.: 1 INTERSECTION IMPROVEMENT WITH ADDED TURN LANES

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	3.00 EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	3.00 EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0005	109-08360	CONTRACT LIENS	1.00 DOL
0006	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0007	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0008	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0013	202-02240	PAVEMENT REMOVAL	1451.00 SYS
0014	202-02278	CURB, CONCRETE, REMOVE	2031.00 LFT
0015	202-91385	INLET, REMOVE	19.00 EACH
0016	202-93047	MANHOLE, REMOVE	12.00 EACH
0017	202-96133	PIPE, REMOVE	1736.00 LFT
0018	203-02000	EXCAVATION, COMMON	705.00 CYS
0019	205-12108	STORMWATER MANAGEMENT BUDGET	12000.00 DOL
0020	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0021	205-12618	SWQCP PREPARATION	1.00 LS
0022	207-08264	SUBGRADE TREATMENT, TYPE II	1227.00 SYS
0023	207-09935	SUBGRADE TREATMENT, TYPE IC	549.00 SYS
0024	207-12498	SUBGRADE TREATMENT, TYPE ID	2390.00 SYS
0025	211-02050	B BORROW	35.00 CYS
0026	211-09264	STRUCTURE BACKFILL, TYPE 1	2711.00 CYS
0027	214-11796	GEOGRID, TYPE IB	335.00 SYS
0028	302-07455	DENSE GRADED SUBBASE	193.00 CYS
0029	303-08210	COMPACTED AGGREGATE NO. 53 TEMPORARY FOR DRIVEWAYS	400.00 TON
0030	306-11872	MILLING, PROFILE	3361.00 SYS
0031	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	358.00 TON

0032	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	874.00 TON
0033	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	626.00 TON
0034	401-10258	JOINT ADHESIVE, SURFACE	3061.00 LFT
0035	401-10259	JOINT ADHESIVE, INTERMEDIATE	3061.00 LFT
0036	401-11785	LIQUID ASPHALT SEALANT	3061.00 LFT
0037	406-05520	ASPHALT FOR TACK COAT	2.00 TON
0038	605-06140	CURB AND GUTTER, CONCRETE	1684.00 LFT
0039	610-08446	PCCP FOR APPROACHES, 6 IN.	828.00 SYS
0040	610-09108	PCCP FOR APPROACHES, 9 IN.	400.00 SYS
0041	611-06497	MAILBOX ASSEMBLY, SINGLE	20.00 EACH
0042	615-06490	RIGHT-OF-WAY MARKER	2.00 EACH
0043	615-06505	MONUMENT, B	2.00 EACH
0044	621-06570	TOPSOIL	248.00 CYS
0045	621-06575	SODDING, NURSERY	2976.00 SYS
0046	628-09402	FIELD OFFICE, B	12.00 MOS
0047	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	690.00 LFT
0048	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	237.00 LFT
0049	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	1928.00 LFT
0050	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	710.00 LFT
0051	715-05422	PIPE, SLOTTED DRAIN, 12 IN.	457.00 LFT
0052	715-08306	HMA FOR STRUCTURE INSTALLATION, TYPE C	362.00 TON
0053	715-09064	VIDEO INSPECTION FOR PIPE	3565.00 LFT
0054	715-11896	WATER SERVICE CONNECTION	5.00 EACH
0055	715-11896	WATER SERVICE CONNECTION	2.00 EACH
0056	715-46000	PIPE END SECTION, DIAMETER 12 IN.	2.00 EACH
0057	715-46030	PIPE END SECTION, DIAMETER 30 IN.	1.00 EACH
0058	715-93403	WATER SERVICE CONNECTION, 0.75 IN.	3.00 EACH
0059	720-02442	PIPE PLUG EXISTING	7.00 EACH
0060	720-03757	MANHOLE, C15	1.00 EACH
0061	720-04721	MANHOLE, K	1.00 EACH
0062	720-44025	CASTING, 4, FURNISH AND ADJUST TO GRADE	1.00 EACH
0063	720-45260	PIPE CATCH BASIN, 12 IN.	2.00 EACH
0064	720-45410	MANHOLE, C4	9.00 EACH
0065	720-45415	MANHOLE, D4	7.00 EACH
0066	720-98174	INLET, B15	1.00 EACH
0067	720-98555	INLET, C15	5.00 EACH
0068	720-99416	CATCH BASIN, B15	1.00 EACH

0069	720-99417	CATCH BASIN, C15	10.00 EACH
0070	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	6615.00 LFT
0071	801-06640	CONSTRUCTION SIGN, A	29.00 EACH
0072	801-06775	MAINTAINING TRAFFIC	1.00 LS
0073	801-07119	BARRICADE, III-B	96.00 LFT
0074	802-03126	SIGN OVERHEAD RELOCATE	1.00 EACH
0075	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	122.00 LFT
0076	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	43.00 SFT
0077	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	73.00 SFT
0078	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	26.00 SFT
0079	802-91122	SIGN GROUND MOUNTED RESET	5.00 EACH
0080	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.00 EACH
0081	805-01579	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00 LS
0082	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	1.00 EACH
0083	805-01842	HANDHOLE SIGNAL TYPE 1	2.00 EACH
0084	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	285.00 LFT
0085	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00 LS
0086	805-78109	CONTROLLER AND CABINET, SECONDARY MENU DRIVEN, 8 PHASE	1.00 EACH
0087	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	13.00 EACH
0088	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	2.00 EACH
0089	805-78415	SPAN, CATENARY, AND TETHER	2.00 EACH
0090	805-78420	DISCONNECT HANGER	2.00 EACH
0091	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	548.00 LFT
0092	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	775.00 LFT
0093	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	850.00 LFT
0094	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	2660.00 LFT
0095	805-78785	SIGNAL DETECTOR HOUSING	1.00 EACH
0096	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	186.00 LFT
0097	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	1.00 EACH
0098	805-92504	LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	1.00 EACH
0099	808-06609	PAVEMENT MESSAGE MARKING	2.00 EACH
0100	808-06609	PAVEMENT MESSAGE MARKING	1.00 EACH
0101	808-06609	PAVEMENT MESSAGE MARKING	1.00 EACH
0102	808-06609	PAVEMENT MESSAGE MARKING	2.00 EACH
0103	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	735.00 LFT
0104	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	3800.00 LFT
0105	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	2750.00 LFT

0106	808-06716	LINE, REMOVE	1150.00	LFT
0107	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	36.00	LFT
0108	808-12032	GROOVING FOR PAVEMENT MARKINGS	5175.00	LFT
0109	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	640.00	LFT
0110	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	83.00	LFT



Call: 131

Contract: R -39734-A

Section No.: 1          VERTICAL SIGHT CORRECTION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	5.00 EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0004	109-08360	CONTRACT LIENS	1.00 DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0012	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00 LS
0013	202-03135	REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	1212.00 SFT
0014	202-52710	SIDEWALK CONCRETE, REMOVE	6.00 SYS
0015	202-96133	PIPE, REMOVE	534.00 LFT
0016	203-02000	EXCAVATION, COMMON	4571.00 CYS
0017	203-51223	EXCAVATION, WATERWAY	21.00 CYS
0018	205-11626	PUMP AROUND	1.00 EACH
0019	205-12108	STORMWATER MANAGEMENT BUDGET	23100.00 DOL
0020	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0021	205-12618	SWQCP PREPARATION	1.00 LS
0022	206-51235	COFFERDAM	1.00 LS
0023	207-08264	SUBGRADE TREATMENT, TYPE II	1517.00 SYS
0024	207-09935	SUBGRADE TREATMENT, TYPE IC	5222.00 SYS
0025	211-09265	STRUCTURE BACKFILL, TYPE 2	141.00 CYS
0026	211-09268	STRUCTURE BACKFILL, TYPE 5	197.00 CYS
0027	301-12232	COMPACTED AGGREGATE NO. 5	21.00 CYS
0028	302-07455	DENSE GRADED SUBBASE	42.30 CYS
0029	303-01180	COMPACTED AGGREGATE NO. 53	761.00 TON
0030	303-08210	COMPACTED AGGREGATE NO. 53 TEMPORARY FOR DRIVEWAYS	55.00 TON
0031	401-06264	PROFILOGRAPH, HMA	1.00 LS

0032	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	307.00 TON
0033	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	510.00 TON
0034	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	1635.00 TON
0035	401-10258	JOINT ADHESIVE, SURFACE	3239.00 LFT
0036	401-10259	JOINT ADHESIVE, INTERMEDIATE	3239.00 LFT
0037	401-11785	LIQUID ASPHALT SEALANT	3239.00 LFT
0038	406-05520	ASPHALT FOR TACK COAT	4.00 TON
0039	601-02241	GUARDRAIL, REMOVE	238.00 LFT
0040	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	250.00 LFT
0041	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	1.00 EACH
0042	601-12293	GUARDRAIL, MGS, STRUCTURE, TOP-MOUNTED POST	6.00 EACH
0043	601-12404	MODIFIED MGS W-BEAM POST	10.00 EACH
0044	601-94689	GUARDRAIL, END TREATMENT, OS	3.00 EACH
0045	604-06070	SIDEWALK, CONCRETE	7.00 SYS
0046	605-06121	CURB, CONCRETE B	174.00 LFT
0047	605-06145	CURB AND GUTTER, B, CONCRETE	543.00 LFT
0048	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	614.00 LFT
0049	610-07487	HMA FOR APPROACHES, TYPE B	278.00 TON
0050	610-08446	PCCP FOR APPROACHES, 6 IN.	253.00 SYS
0051	611-06497	MAILBOX ASSEMBLY, SINGLE	3.00 EACH
0052	615-06490	RIGHT-OF-WAY MARKER	14.00 EACH
0053	615-06505	MONUMENT, B	5.00 EACH
0054	616-05688	RIPRAP, CLASS 1	6.00 TON
0055	616-06405	RIPRAP, REVETMENT	243.00 TON
0056	616-09997	DITCH DETENTION CHECK	2.00 EACH
0057	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	605.00 SYS
0058	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 EACH
0059	621-06545	FERTILIZER	1.00 TON
0060	621-06553	SEED MIXTURE R	256.00 LBS
0061	621-06565	MULCHING MATERIAL	3.00 TON
0062	621-06567	WATER	14.00 KGAL
0063	621-06574	SODDING	860.00 SYS
0064	621-06575	SODDING, NURSERY	525.00 SYS
0065	628-09403	FIELD OFFICE, C	18.00 MOS
0066	702-04325	TEMPORARY SHORING	1.00 LS
0067	714-11183	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 10 FT. X 6 FT.	78.00 LFT
0068	715-05032	PIPE, TYPE 2, CIRCULAR, 15 IN.	50.00 LFT

0069	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	121.00	LFT
0070	715-05168	PIPE, TYPE 3, CIRCULAR, 12 IN.	27.00	LFT
0071	715-05177	PIPE, TYPE 3, CIRCULAR, 36 IN.	20.00	LFT
0072	715-05229	PIPE, TYPE 1, DEFORMED, MIN. AREA 1.8 SFT	100.00	LFT
0073	715-09064	VIDEO INSPECTION FOR PIPE	171.00	LFT
0074	715-46000	PIPE END SECTION, DIAMETER 12 IN.	3.00	EACH
0075	715-46005	PIPE END SECTION, DIAMETER 15 IN.	1.00	EACH
0076	715-46040	PIPE END SECTION, DIAMETER 36 IN.	1.00	EACH
0077	715-46055	PIPE END SECTION, MIN. AREA 1.8 SFT	2.00	EACH
0078	719-05440	PIPE, DRAIN. TILE TERMINAL SECTION, 8 IN.	10.00	LFT
0079	720-02442	PIPE PLUG EXISTING	2.00	EACH
0080	720-09079	INLET, HAS MODIFIED	5.00	EACH
0081	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0082	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	5865.00	LFT
0083	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	48.00	LFT
0084	801-06640	CONSTRUCTION SIGN, A	30.00	EACH
0085	801-06645	CONSTRUCTION SIGN, B	6.00	EACH
0086	801-06775	MAINTAINING TRAFFIC	1.00	LS
0087	801-07118	BARRICADE, III-A	80.00	LFT
0088	801-07119	BARRICADE, III-B	32.00	LFT
0089	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	1150.00	LFT
0090	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	430.00	LFT
0091	801-12081	PORTABLE SIGNAL	1.00	LS
0092	801-12482	DRIVEWAY ASSISTANCE DEVICE	2.00	EACH
0093	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	70.20	LFT
0094	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	11.00	EACH
0095	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	35.75	SFT
0096	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	6.67	SFT
0097	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	3642.00	LFT
0098	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	2985.00	LFT
0099	808-06716	LINE, REMOVE	1968.00	LFT
0100	808-06723	PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW	2.00	EACH
0101	808-06724	PAVEMENT MESSAGE MARKING, PAINT, ONLY	1.00	EACH
0102	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	94.00	LFT
0103	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	36.00	EACH
0104	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	13.00	EACH

Call: 161

Contract: R -39920-A

Section No.: 1 SLIDE CORRECTION

Line			
Item No	Item Code	Description	Quantity Unit
0001	104-05404	DESIGN/BUILD	1.00 LS
0002	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0003	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0004	109-08360	CONTRACT LIENS	1.00 DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0012	202-02272	PAVED SIDE DITCH, REMOVE	90.00 LFT
0013	203-02000	EXCAVATION, COMMON	440.00 CYS
0014	205-11626	PUMP AROUND	1.00 EACH
0015	205-12108	STORMWATER MANAGEMENT BUDGET	6000.00 DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0017	205-12618	SWQCP PREPARATION	1.00 LS
0018	207-09935	SUBGRADE TREATMENT, TYPE IC	293.00 SYS
0019	301-12234	COMPACTED AGGREGATE NO. 53	16.00 CYS
0020	303-01180	COMPACTED AGGREGATE NO. 53	154.00 TON
0021	304-07494	WIDENING WITH HMA, TYPE C	73.00 TON
0022	306-08034	MILLING, ASPHALT, 1 1/2 IN.	2072.00 SYS
0023	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	185.00 TON
0024	401-10258	JOINT ADHESIVE, SURFACE	2050.00 LFT
0025	401-10259	JOINT ADHESIVE, INTERMEDIATE	352.00 LFT
0026	401-11785	LIQUID ASPHALT SEALANT	2402.00 LFT
0027	406-05520	ASPHALT FOR TACK COAT	1.00 TON
0028	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.00 TON
0029	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	250.00 LFT
0030	601-94689	GUARDRAIL, END TREATMENT, OS	2.00 EACH
0031	616-05689	RIPRAP, CLASS 2	60.00 TON

0032	616-06405	RIPRAP, REVETMENT	136.00	TON
0033	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	327.00	SYS
0034	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0035	621-06559	MULCHED SEEDING R	595.00	SYS
0036	628-09402	FIELD OFFICE, B	9.00	MOS
0037	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0038	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.00	EACH
0039	801-03291	CONSTRUCTION SIGN, D	6.00	EACH
0040	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4951.00	LFT
0041	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	1001.00	LFT
0042	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	24.00	LFT
0043	801-06640	CONSTRUCTION SIGN, A	26.00	EACH
0044	801-06645	CONSTRUCTION SIGN, B	6.00	EACH
0045	801-06775	MAINTAINING TRAFFIC	1.00	LS
0046	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	475.00	LFT
0047	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	200.00	LFT
0048	801-12081	PORTABLE SIGNAL	1.00	LS
0049	801-12482	DRIVEWAY ASSISTANCE DEVICE	6.00	EACH
0050	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	170.00	LFT
0051	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1350.00	LFT
0052	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	675.00	LFT
0053	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	17.00	EACH
0054	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	17.00	EACH

Call: 171

Contract: R -40646-A

Section No.: 1 BIKE AND PEDESTRIAN FACILITIES

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	5.00 EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	5.00 EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0005	109-08360	CONTRACT LIENS	1.00 DOL
0006	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0007	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0008	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0012	201-02255	TREE 18 IN., REMOVE	6.00 EACH
0013	201-02260	TREE 30 IN., REMOVE	3.00 EACH
0014	201-02265	TREE 48 IN., REMOVE	4.00 EACH
0015	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0016	202-02240	PAVEMENT REMOVAL	1670.00 SYS
0017	202-91922	STUMP, REMOVE	1.00 EACH
0018	203-02000	EXCAVATION, COMMON	2600.00 CYS
0019	203-02070	BORROW	250.00 CYS
0020	205-12108	STORMWATER MANAGEMENT BUDGET	4500.00 DOL
0021	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0022	205-12618	SWQCP PREPARATION	1.00 LS
0023	207-08266	SUBGRADE TREATMENT, TYPE III	4050.00 SYS
0024	207-09935	SUBGRADE TREATMENT, TYPE IC	5762.00 SYS
0025	211-09264	STRUCTURE BACKFILL, TYPE 1	520.00 CYS
0026	303-01180	COMPACTED AGGREGATE NO. 53	2300.00 TON
0027	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	446.00 TON
0028	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	968.00 TON
0029	401-10258	JOINT ADHESIVE, SURFACE	1925.00 LFT
0030	401-10259	JOINT ADHESIVE, INTERMEDIATE	1925.00 LFT
0031	401-11785	LIQUID ASPHALT SEALANT	1925.00 LFT

0032	406-05520	ASPHALT FOR TACK COAT	4.00 TON
0033	604-05528	HMA FOR SIDEWALK	565.00 TON
0034	604-06070	SIDEWALK, CONCRETE	974.00 SYS
0035	604-08086	CURB RAMP, CONCRETE	288.00 SYS
0036	604-12083	DETECTABLE WARNING SURFACES	42.00 SYS
0037	605-06120	CURB, CONCRETE	4380.00 LFT
0038	616-03096	RIVER ROCK	190.00 TON
0039	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00 EACH
0040	621-06545	FERTILIZER	1.00 TON
0041	621-06554	SEED MIXTURE U	58.00 LBS
0042	621-06565	MULCHING MATERIAL	1.00 TON
0043	621-06567	WATER	23.00 kGAL
0044	621-06570	TOPSOIL	79.00 CYS
0045	621-06575	SODDING, NURSERY	939.00 SYS
0046	628-09402	FIELD OFFICE, B	12.00 MOS
0047	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0048	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	40.00 LFT
0049	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	110.00 LFT
0050	715-05052	PIPE, TYPE 4, CIRCULAR, 12 IN.	1360.00 LFT
0051	715-05147	PIPE, TYPE 2, CIRCULAR, 8 IN.	20.00 LFT
0052	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	375.00 LFT
0053	715-05408	PIPE, SANITARY SEWER, 8 IN.	100.00 LFT
0054	715-05711	PIPE, SANITARY SEWER, 6 IN.	100.00 LFT
0055	715-08250	PIPE DUCTILE IRON 12 IN.	200.00 LFT
0056	715-09064	VIDEO INSPECTION FOR PIPE	2105.00 LFT
0057	715-40000	PIPE, SANITARY SEWER, 4 IN.	100.00 LFT
0058	718-12308	GEOTEXTILE FOR UNDERDRAIN, TYPE 2B	2865.00 SYS
0059	718-52610	AGGREGATE FOR UNDERDRAINS	725.00 CYS
0060	720-01894	CASTING, FURNISH AND ADJUST TO GRADE	6.00 EACH
0061	720-44000	CASTING, ADJUST TO GRADE	6.00 EACH
0062	720-45005	INLET, A2	13.00 EACH
0063	720-45055	INLET, M10	19.00 EACH
0064	720-45205	CATCH BASIN, A2	3.00 EACH
0065	720-45605	STRUCTURE, MANHOLE, RECONSTRUCTED	26.00 LFT
0066	801-04308	ROAD CLOSURE SIGN ASSEMBLY	1.00 EACH
0067	801-06625	DETOUR ROUTE MARKER ASSEMBLY	9.00 EACH
0068	801-06640	CONSTRUCTION SIGN, A	19.00 EACH

0069	801-06645	CONSTRUCTION SIGN, B	13.00 EACH
0070	801-06775	MAINTAINING TRAFFIC	1.00 LS
0071	801-07118	BARRICADE, III-A	140.00 LFT
0072	801-07119	BARRICADE, III-B	80.00 LFT
0073	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	655.00 LFT
0074	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	342.00 SFT
0075	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	45.00 SFT
0076	802-91122	SIGN GROUND MOUNTED RESET	3.00 EACH
0077	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	2.00 EACH
0078	805-01842	HANDHOLE SIGNAL TYPE 1	2.00 EACH
0079	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	200.00 LFT
0080	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	2.00 EACH
0081	805-02445	CONTROLLER AND CABINET, P1	1.00 EACH
0082	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	4.00 EACH
0083	805-78370	PEDESTRIAN PUSH BUTTON, NON-APS	2.00 EACH
0084	805-78415	SPAN, CATENARY, AND TETHER	1.00 EACH
0085	805-78420	DISCONNECT HANGER	1.00 EACH
0086	805-78445	SIGNAL SERVICE	2.00 EACH
0087	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	175.00 LFT
0088	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	360.00 LFT
0089	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	550.00 LFT
0090	805-78925	CONTROLLER CABINET FOUNDATION, P1	1.00 EACH
0091	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	2.00 EACH
0092	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	500.00 LFT
0093	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	180.00 LFT
0094	808-99077	LINE, PREFORMED PLASTIC, SOLID, WHITE, 24 IN.	200.00 LFT



Call: 181

Contract: R -41080-A

Section No.: 1

SMALL STRUCTURE REPLACEMENT

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0012	202-51330	PRESENT STRUCTURE, REMOVE	1.00 LS
0013	202-51330	PRESENT STRUCTURE, REMOVE	1.00 LS
0014	202-93741	GUARDRAIL, END TREATMENT, REMOVE	7.00 EACH
0015	202-98488	PIPE END SECTION, REMOVE	1.00 EACH
0016	203-02000	EXCAVATION, COMMON	425.00 CYS
0017	203-02070	BORROW	150.00 CYS
0018	203-08607	LINEAR GRADING	747.00 LFT
0019	205-12108	STORMWATER MANAGEMENT BUDGET	14906.00 DOL
0020	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0021	205-12618	SWQCP PREPARATION	1.00 LS
0022	207-08264	SUBGRADE TREATMENT, TYPE II	81.00 SYS
0023	207-12498	SUBGRADE TREATMENT, TYPE ID	676.00 SYS
0024	211-09265	STRUCTURE BACKFILL, TYPE 2	1615.00 CYS
0025	213-09270	FLOWABLE BACKFILL, REMOVABLE	2.00 CYS
0026	301-12234	COMPACTED AGGREGATE NO. 53	14.00 CYS
0027	303-01180	COMPACTED AGGREGATE NO. 53	88.00 TON
0028	306-08043	MILLING, TRANSITION	468.00 SYS
0029	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	90.00 TON
0030	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	83.00 TON
0031	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	206.00 TON

0032	401-10258	JOINT ADHESIVE, SURFACE	675.00	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	375.00	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	675.00	LFT
0035	406-05521	ASPHALT FOR TACK COAT	1636.00	SYS
0036	601-02241	GUARDRAIL, REMOVE	1000.00	LFT
0037	610-07487	HMA FOR APPROACHES, TYPE B	19.00	TON
0038	611-06497	MAILBOX ASSEMBLY, SINGLE	3.00	EACH
0039	615-06505	MONUMENT, B	4.00	EACH
0040	616-05688	RIPRAP, CLASS 1	364.00	TON
0041	616-06405	RIPRAP, REVETMENT	105.00	TON
0042	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	1154.00	SYS
0043	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0044	621-02770	EROSION CONTROL BLANKET	883.00	SYS
0045	621-06559	MULCHED SEEDING R	1564.00	SYS
0046	621-06567	WATER	0.80	kGAL
0047	621-06574	SODDING	173.00	SYS
0048	628-11729	CELLULAR TELEPHONE, TYPE A	9.00	EACH
0049	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0050	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0051	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	9.00	MOS
0052	714-11185	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 10 FT. X 8 FT.	137.00	LFT
0053	714-11311	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 7 FT. X 5 FT.	52.00	LFT
0054	714-11311	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 7 FT. X 5 FT.	17.50	LFT
0055	714-11311	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 7 FT. X 5 FT.	21.50	LFT
0056	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	250.00	LFT
0057	715-05049	PIPE, TYPE 4, CIRCULAR, 8 IN.	58.00	LFT
0058	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	17.00	LFT
0059	715-05119	PIPE, TYPE 1, CIRCULAR, 15 IN.	90.00	LFT
0060	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	33.00	LFT
0061	715-46005	PIPE END SECTION, DIAMETER 15 IN.	1.00	EACH
0062	718-06531	OUTLET PROTECTOR, 3	1.00	EACH
0063	718-12308	GEOTEXTILE FOR UNDERDRAIN, TYPE 2B	171.00	SYS
0064	718-52610	AGGREGATE FOR UNDERDRAINS	21.00	CYS
0065	720-45035	INLET, F7	1.00	EACH
0066	720-45410	MANHOLE, C4	2.00	EACH
0067	720-95310	INLET, P12A MODIFIED	1.00	EACH
0068	801-04308	ROAD CLOSURE SIGN ASSEMBLY	13.00	EACH

0069	801-06625	DETOUR ROUTE MARKER ASSEMBLY	60.00	EACH
0070	801-06640	CONSTRUCTION SIGN, A	48.00	EACH
0071	801-06645	CONSTRUCTION SIGN, B	8.00	EACH
0072	801-06775	MAINTAINING TRAFFIC	1.00	LS
0073	801-07119	BARRICADE, III-B	336.00	LFT
0074	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	56.00	LFT
0075	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	450.00	LFT
0076	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	100.00	LFT

Call: 191

Contract: R -41129-A

Section No.: 1 INTERSECTION IMPROVEMENT WITH ADDED TURN LANES

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	10.00 EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	10.00 EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0005	109-08360	CONTRACT LIENS	1.00 DOL
0006	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0007	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0008	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0009	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0010	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0011	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0012	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0013	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0014	202-02240	PAVEMENT REMOVAL	395.00 SYS
0015	202-02273	CENTER CURB, CONCRETE, REMOVE	119.00 SYS
0016	202-02278	CURB, CONCRETE, REMOVE	2032.00 LFT
0017	202-02637	PIPE ABANDON AND GROUT FILL	19.00 LFT
0018	202-74080	OVERHEAD SIGN STRUCTURE, CANTILEVER, REMOVE	1.00 EACH
0019	202-86946	HANDHOLE, REMOVE	5.00 EACH
0020	202-91385	INLET, REMOVE	4.00 EACH
0021	202-93047	MANHOLE, REMOVE	1.00 EACH
0022	202-94954	BARRIER WALL, CONCRETE, REMOVE	39.00 LFT
0023	202-95027	IMPACT ATTENUATOR, REMOVE	1.00 EACH
0024	202-96022	CONCRETE FOUNDATION, REMOVE	3.00 EACH
0025	202-96133	PIPE, REMOVE	100.00 LFT
0026	202-96328	FOUNDATION, STREET LIGHT, REMOVE	4.00 EACH
0027	203-02000	EXCAVATION, COMMON	2025.00 CYS
0028	203-02070	BORROW	645.00 CYS
0029	205-12108	STORMWATER MANAGEMENT BUDGET	18500.00 DOL
0030	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0031	205-12618	SWQCP PREPARATION	1.00 LS

0032	207-08264	SUBGRADE TREATMENT, TYPE II	229.00	SYS
0033	207-09935	SUBGRADE TREATMENT, TYPE IC	2654.00	SYS
0034	211-09265	STRUCTURE BACKFILL, TYPE 2	180.00	CYS
0035	214-11796	GEOGRID, TYPE IB	149.00	SYS
0036	301-12234	COMPACTED AGGREGATE NO. 53	21.00	CYS
0037	303-01180	COMPACTED AGGREGATE NO. 53	91.00	TON
0038	304-07789	WIDENING WITH HMA, TYPE D	411.00	TON
0039	306-08034	MILLING, ASPHALT, 1 1/2 IN.	17466.00	SYS
0040	306-08432	MILLING, APPROACH	91.00	SYS
0041	306-11872	MILLING, PROFILE	1241.00	SYS
0042	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	1701.00	TON
0043	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	260.00	TON
0044	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	693.00	TON
0045	401-10258	JOINT ADHESIVE, SURFACE	12835.00	LFT
0046	401-10259	JOINT ADHESIVE, INTERMEDIATE	484.00	LFT
0047	401-12483	RAPID PENETRATING EMULSION	12835.00	LFT
0048	402-10086	HMA FOR TEMPORARY PAVEMENT, C	35.00	TON
0049	406-05520	ASPHALT FOR TACK COAT	7.00	TON
0050	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	2.00	TON
0051	502-03289	QUALITY ASSURANCE ADJUSTMENT	1.00	DOL
0052	502-06627	PCCP, 6 IN.	178.00	SYS
0053	601-09146	IMPACT ATTENUATOR, CR1-W1, TL-2	1.00	EACH
0054	604-06070	SIDEWALK, CONCRETE	718.00	SYS
0055	604-08086	CURB RAMP, CONCRETE	124.00	SYS
0056	604-12083	DETECTABLE WARNING SURFACES	27.00	SYS
0057	605-06120	CURB, CONCRETE	2264.00	LFT
0058	605-06255	CENTER CURB, D CONCRETE	126.00	SYS
0059	605-09137	CURB, TURNOUT	35.00	LFT
0060	610-07487	HMA FOR APPROACHES, TYPE B	91.00	TON
0061	616-06405	RIPRAP, REVETMENT	37.00	TON
0062	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	89.00	SYS
0063	621-06570	TOPSOIL	494.00	CYS
0064	621-06574	SODDING	379.00	SYS
0065	621-06575	SODDING, NURSERY	4018.00	SYS
0066	628-09402	FIELD OFFICE, B	12.00	MOS
0067	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0068	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL

0069	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0070	628-11781	CELLULAR TELEPHONE SERVICE, 750 MIN.	12.00	MOS
0071	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0072	715-05032	PIPE, TYPE 2, CIRCULAR, 15 IN.	42.00	LFT
0073	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	279.00	LFT
0074	715-05327	PIPE, TYPE 2, DEFORMED, MIN. AREA 1.83 SFT	166.00	LFT
0075	715-08305	HMA FOR STRUCTURE INSTALLATION, TYPE B	11.00	TON
0076	715-08307	HMA FOR STRUCTURE INSTALLATION, TYPE D	43.00	TON
0077	715-09064	VIDEO INSPECTION FOR PIPE	487.00	LFT
0078	715-46000	PIPE END SECTION, DIAMETER 12 IN.	4.00	EACH
0079	715-46005	PIPE END SECTION, DIAMETER 15 IN.	1.00	EACH
0080	720-01092	MANHOLE, J15 MODIFIED	3.00	EACH
0081	720-44000	CASTING, ADJUST TO GRADE	3.00	EACH
0082	720-44025	CASTING, 4, FURNISH AND ADJUST TO GRADE	2.00	EACH
0083	720-44040	CASTING, 7, FURNISH AND ADJUST TO GRADE	1.00	EACH
0084	720-44055	CASTING, 10, FURNISH AND ADJUST TO GRADE	1.00	EACH
0085	720-45035	INLET, F7	1.00	EACH
0086	720-45069	INLET, P12	1.00	EACH
0087	720-45410	MANHOLE, C4	1.00	EACH
0088	720-91352	CATCH BASIN, F7	1.00	EACH
0089	720-94840	CASTING, WATER VALVE, ADJUST TO GRADE	8.00	EACH
0090	720-98174	INLET, B15	5.00	EACH
0091	720-98555	INLET, C15	2.00	EACH
0092	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	25425.00	LFT
0093	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	25.00	EACH
0094	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	112.00	LFT
0095	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	400.00	LFT
0096	801-06640	CONSTRUCTION SIGN, A	23.00	EACH
0097	801-06645	CONSTRUCTION SIGN, B	20.00	EACH
0098	801-06775	MAINTAINING TRAFFIC	1.00	LS
0099	801-07119	BARRICADE, III-B	312.00	LFT
0100	801-94295	SIGNAL HEAD RELOCATE	20.00	EACH
0101	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	196.00	LFT
0102	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	12.00	EACH
0103	802-07135	CABLE SPAN SIGN STRUCTURE FOUNDATION, IV	2.00	EACH
0104	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	190.00	SFT
0105	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	35.00	SFT

0106	802-11886	CANTILEVER SIGN SUPPORT FOUNDATION, DRILLED SHAFT 48 IN.	1.00 EACH
0107	802-74070	OVERHEAD SIGN STRUCTURE, CABLE SPAN, REMOVE	1.00 EACH
0108	802-76125	OVERHEAD SIGN STRUCTURE, CABLESPAN	1.00 EACH
0109	802-76135	OVERHEAD SIGN STRUCTURE, CANTILEVER, SINGLE ARM	1.00 EACH
0110	805-01479	CONTROLLER CABINET FOUNDATION, P1 MODIFIED	1.00 EACH
0111	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	8.00 EACH
0112	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	8.00 EACH
0113	805-04602	CONTROLLER, REWIRE	1.00 EACH
0114	805-06600	CONDUIT, PVC, 3 IN.	36.00 LFT
0115	805-08214	CONDUIT, PVC, 2 IN. SCHEDULE 40	243.00 LFT
0116	805-11744	HANDHOLE SIGNAL TYPE 2	11.00 EACH
0117	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	1484.00 LFT
0118	805-11817	PEDESTRIAN PUSH BUTTON, APS	8.00 EACH
0119	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	1.00 EACH
0120	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	4584.00 LFT
0121	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	3845.00 LFT
0122	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	4482.00 LFT
0123	805-78785	SIGNAL DETECTOR HOUSING	9.00 EACH
0124	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1644.00 LFT
0125	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	8.00 EACH
0126	805-92504	LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	1.00 EACH
0127	807-02191	HANDHOLE LIGHTING	1.00 EACH
0128	807-02603	LIGHT STANDARD RELOCATE	4.00 EACH
0129	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	44.00 LFT
0130	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	1334.00 LFT
0131	807-11981	LIGHTING FOUNDATION, CONCRETE WITH GROUNDING 36 IN. DIA X 96 IN.	4.00 EACH
0132	807-86910	CONNECTOR KIT, UNFUSED	12.00 EACH
0133	807-86915	CONNECTOR KIT, FUSED	12.00 EACH
0134	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	21.00 EACH
0135	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	4.00 EACH
0136	807-86930	INSULATION LINK, NON-WATERPROOFED	20.00 EACH
0137	807-86935	INSULATION LINK, WATERPROOFED	8.00 EACH
0138	808-06716	LINE, REMOVE	2788.00 LFT
0139	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS
0140	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	1100.00 LFT
0141	808-10032	LINE, MULTI-COMPONENT, DOTTED, WHITE, 8 IN.	140.00 LFT
0142	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	965.00 LFT

0143	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	204.00	LFT
0144	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	1653.00	LFT
0145	808-10047	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, WHITE, 12 IN.	391.00	LFT
0146	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	2988.00	LFT
0147	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	174.00	LFT
0148	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	925.00	LFT
0149	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	2915.00	LFT
0150	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	17.00	EACH
0151	808-10099	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 24 IN.	162.00	LFT
0152	808-11481	LINE, MULTI-COMPONENT, DOTTED, WHITE, 4 IN.	358.00	LFT
0153	808-11548	LINE, MULTI-COMPONENT, DOTTED, YELLOW, 4 IN.	179.00	LFT
0154	808-11776	TRANSVERSE MARKING, MULTI-COMPONENT, YIELD LINE, WHITE, 24 IN.	77.00	LFT
0155	808-12032	GROOVING FOR PAVEMENT MARKINGS	10502.00	LFT



Call: 201

Contract: R -41306-A

Section No.: 1 BIKE AND PEDESTRIAN FACILITIES

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0009	203-02000	EXCAVATION, COMMON	2873.00 CYS
0010	203-02070	BORROW	5982.00 CYS
0011	205-12108	STORMWATER MANAGEMENT BUDGET	6855.00 DOL
0012	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0013	205-12618	SWQCP PREPARATION	1.00 LS
0014	207-08266	SUBGRADE TREATMENT, TYPE III	1474.00 SYS
0015	211-09266	STRUCTURE BACKFILL, TYPE 3	6098.00 CYS
0016	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	214.00 SYS
0017	301-12232	COMPACTED AGGREGATE NO. 5	33.00 CYS
0018	301-12234	COMPACTED AGGREGATE NO. 53	324.00 CYS
0019	406-05521	ASPHALT FOR TACK COAT	1670.00 SYS
0020	502-03289	QUALITY ASSURANCE ADJUSTMENT	1.00 DOL
0021	502-06627	PCCP, 6 IN.	201.00 SYS
0022	603-03692	FENCE WOOD	563.00 LFT
0023	603-03829	FENCE	104.00 LFT
0024	603-03829	FENCE	431.00 LFT
0025	604-05528	HMA FOR SIDEWALK	301.00 TON
0026	605-06120	CURB, CONCRETE	40.00 LFT
0027	618-03812	BENCH	5.00 EACH
0028	618-03812	BENCH	1.00 EACH
0029	618-04181	BICYCLE RACK	4.00 EACH
0030	618-12007	PET WASTE STATION	2.00 EACH
0031	618-97672	TRASH RECEPTACLE	2.00 EACH

0032	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 EACH
0033	621-02770	EROSION CONTROL BLANKET	1429.00 SYS
0034	621-06545	FERTILIZER	0.42 TON
0035	621-06553	SEED MIXTURE R	213.00 LBS
0036	621-06565	MULCHING MATERIAL	2.10 TON
0037	628-09403	FIELD OFFICE, C	12.00 MOS
0038	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0039	712-04784	STRUCTURE	1.00 EACH
0040	720-44000	CASTING, ADJUST TO GRADE	4.00 EACH
0041	732-11770	AGGREGATE FOR DRAINAGE FILL	386.00 CYS
0042	732-11811	MODULAR BLOCK WALL ERECTION	9571.00 SFT
0043	732-11812	MODULAR BLOCK WALL WITH GROUND REINFORCEMENT	9571.00 SFT
0044	801-06645	CONSTRUCTION SIGN, B	3.00 EACH
0045	802-04250	SIGN, TRAIL INFORMATION	1.00 EACH
0046	802-04250	SIGN, TRAIL INFORMATION	1.00 EACH
0047	802-07060	SIGN, SHEET, RELOCATE	1.00 EACH

Call: 211

Contract: R -41685-A

Section No.: 1 ASPHALT RESURFACE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	202-90277	DETECTOR HOUSING, REMOVE	25.00 EACH
0011	202-93741	GUARDRAIL, END TREATMENT, REMOVE	7.00 EACH
0012	203-02070	BORROW	70.00 CYS
0013	203-08607	LINEAR GRADING	890.00 LFT
0014	203-08607	LINEAR GRADING	1000.00 LFT
0015	207-12498	SUBGRADE TREATMENT, TYPE ID	1251.00 SYS
0016	301-12234	COMPACTED AGGREGATE NO. 53	156.00 CYS
0017	303-01180	COMPACTED AGGREGATE NO. 53	60.00 TON
0018	303-07449	COMPACTED AGGREGATE NO. 73	200.00 TON
0019	304-12623	HMA PATCHING FULL DEPTH TYPE B	688.00 TON
0020	304-12624	HMA PATCHING PARTIAL DEPTH TYPE B	4710.00 TON
0021	306-08036	MILLING, ASPHALT, 2 IN.	178120.00 SYS
0022	306-08432	MILLING, APPROACH	6588.00 SYS
0023	401-06264	PROFILOGRAPH, HMA	1.00 LS
0024	401-07340	QC/QA-HMA, 3, 64, SURFACE, 12.5 mm	19593.00 TON
0025	401-10258	JOINT ADHESIVE, SURFACE	102421.00 LFT
0026	401-11785	LIQUID ASPHALT SEALANT	102421.00 LFT
0027	406-05520	ASPHALT FOR TACK COAT	46.00 TON
0028	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	10.00 TON
0029	601-02241	GUARDRAIL, REMOVE	555.00 LFT
0030	601-05999	CURVED TERMINAL END	4.00 EACH
0031	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	256.00 LFT

0032	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	3.00 EACH
0033	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00 EACH
0034	601-94689	GUARDRAIL, END TREATMENT, OS	3.00 EACH
0035	610-07487	HMA FOR APPROACHES, TYPE B	725.00 TON
0036	615-06525	CASTING ADJUST TO GRADE, MONUMENT	2.00 EACH
0037	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00 EACH
0038	621-06559	MULCHED SEEDING R	700.00 SYS
0039	628-09401	FIELD OFFICE, A	9.00 MOS
0040	628-11729	CELLULAR TELEPHONE, TYPE A	2.00 EACH
0041	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00 DOL
0042	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00 DOL
0043	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	18.00 MOS
0044	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0045	720-01355	INLET, CLEAN EXISTING	7.00 EACH
0046	720-44000	CASTING, ADJUST TO GRADE	9.00 EACH
0047	720-44000	CASTING, ADJUST TO GRADE	22.00 EACH
0048	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	6.00 EACH
0049	801-03290	CONSTRUCTION SIGN, C	3.00 EACH
0050	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	14180.00 LFT
0051	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	14180.00 LFT
0052	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	550.00 LFT
0053	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	550.00 LFT
0054	801-06640	CONSTRUCTION SIGN, A	45.00 EACH
0055	801-06710	FLASHING ARROW SIGN	250.00 DAY
0056	801-06775	MAINTAINING TRAFFIC	1.00 LS
0057	801-12042	TRUCK MOUNTED ATTENUATOR	250.00 DAY
0058	805-06595	CONDUIT, PVC, 2 IN.	1650.00 LFT
0059	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	11550.00 LFT
0060	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	7500.00 LFT
0061	805-78785	SIGNAL DETECTOR HOUSING	25.00 EACH
0062	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	3850.00 LFT
0063	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS
0064	808-12032	GROOVING FOR PAVEMENT MARKINGS	130570.00 LFT
0065	808-75051	LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	51590.00 LFT
0066	808-75054	LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN.	64726.00 LFT
0067	808-75059	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 4 IN.	14254.00 LFT
0068	808-75071	PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC, LANE INDICATION ARROW	16.00 EACH

0069	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	550.00	LFT
0070	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	610.00	LFT
0071	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1288.00	EACH
0072	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	20.00	EACH

Call: 225

Contract: R -42652-C

Section No.: 1 CONCRETE PAVEMENT RESTORATION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	202-90277	DETECTOR HOUSING, REMOVE	6.00 EACH
0012	205-12108	STORMWATER MANAGEMENT BUDGET	5702.50 DOL
0013	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0014	207-12498	SUBGRADE TREATMENT, TYPE ID	777.00 SYS
0015	302-06464	SUBBASE FOR PCCP	145.00 CYS
0016	303-07449	COMPACTED AGGREGATE NO. 73	459.00 TON
0017	304-12627	HMA PATCHING FULL DEPTH TYPE D	132.00 TON
0018	306-08036	MILLING, ASPHALT, 2 IN.	34302.00 SYS
0019	401-07353	QC/QA-HMA, 4, 76, SURFACE, 12.5 mm	3774.00 TON
0020	401-10258	JOINT ADHESIVE, SURFACE	23040.00 LFT
0021	401-11785	LIQUID ASPHALT SEALANT	23040.00 LFT
0022	406-05520	ASPHALT FOR TACK COAT	9.00 TON
0023	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	3.00 TON
0024	503-03489	RETROFITTED TIE BARS	424.00 EACH
0025	503-05240	D-1 CONTRACTION JOINT	300.00 LFT
0026	506-06333	PCCP PATCHING, FULL DEPTH	577.00 SYS
0027	506-06334	PCCP PATCHING, PARTIAL DEPTH	50.00 SYS
0028	507-08272	JOINTS IN PCCP, SAW AND SEAL	119976.00 LFT
0029	507-12099	PCCP GROOVING	17675.00 SYS
0030	507-12191	JOINT REPAIR, PARTIAL DEPTH	1000.00 SFT
0031	507-12192	JOINT REPAIR, BOTTOM-HALF	50.00 SFT

0032	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 EACH
0033	621-06574	SODDING	600.00 SYS
0034	628-09402	FIELD OFFICE, B	11.00 MOS
0035	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0036	628-11977	COMPUTER SYSTEM	1.00 EACH
0037	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	520.00 LFT
0038	718-06529	OUTLET PROTECTOR, 2	12.00 EACH
0039	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	2681.00 LFT
0040	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	32.00 EACH
0041	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00 EACH
0042	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	102722.00 LFT
0043	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	253320.00 LFT
0044	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	14.00 EACH
0045	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	216.00 LFT
0046	801-06640	CONSTRUCTION SIGN, A	115.00 EACH
0047	801-06710	FLASHING ARROW SIGN	400.00 DAY
0048	801-06775	MAINTAINING TRAFFIC	1.00 LS
0049	801-07118	BARRICADE, III-A	380.00 LFT
0050	801-08403	TEMPORARY TRAFFIC BARRIER TYPE 4	7500.00 LFT
0051	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	6.00 EACH
0052	801-12042	TRUCK MOUNTED ATTENUATOR	200.00 DAY
0053	801-12348	TEMPORARY WORKSITE SPEED DISPLAY ASSEMBLY	2.00 EACH
0054	801-12652	QUEUE TRUCK	200.00 DAY
0055	801-97643	TEMPORARY BUZZ STRIPS	720.00 LFT
0056	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	120.00 LFT
0057	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	3300.00 LFT
0058	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	920.00 LFT
0059	805-78785	SIGNAL DETECTOR HOUSING	6.00 EACH
0060	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1100.00 LFT
0061	808-06716	LINE, REMOVE	78162.00 LFT
0062	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS
0063	808-12032	GROOVING FOR PAVEMENT MARKINGS	97736.00 LFT
0064	808-12134	LINE, PREFORMED PLASTIC, DOTTED, WHITE, 4 IN.	2868.00 LFT
0065	808-75051	LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	39142.00 LFT
0066	808-75053	LINE, PREFORMED PLASTIC, SOLID, WHITE, 8 IN.	4134.00 LFT
0067	808-75054	LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN.	37572.00 LFT
0068	808-75061	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 5 IN.	14020.00 LFT

0069	808-75067	TRANSVERSE MARKING, PREFORMED PLASTIC, STOP LINE, WHITE, 24 IN.	108.00	LFT
0070	808-75071	PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC, LANE INDICATION ARROW	14.00	EACH
0071	808-75073	PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC, ONLY	1.00	EACH
0072	808-75510	TRANSVERSE MARKING, PREFORMED PLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	420.00	LFT
0073	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	269.00	EACH
0074	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	145.00	EACH

Call: 231

Contract: R -42670-A

Section No.: 1 IDIQ, PAVEMENT PATCHING

Line	Item No	Item Code	Description	Quantity	Unit
	0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0002	109-08360	CONTRACT LIENS	1.00	DOL
	0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0005	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0007	110-12655	MOBILIZATION AND DEMOBILIZATION, IDIQ	1.00	DOL
	0008	304-12625	HMA PATCHING FULL DEPTH TYPE C	1000.00	TON
	0009	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	1500.00	TON
	0010	304-12627	HMA PATCHING FULL DEPTH TYPE D	500.00	TON
	0011	304-12628	HMA PATCHING PARTIAL DEPTH TYPE D	500.00	TON
	0012	406-05520	ASPHALT FOR TACK COAT	20.00	TON
	0013	506-06333	PCCP PATCHING, FULL DEPTH	250.00	SYS
	0014	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1000.00	LFT
	0015	801-06640	CONSTRUCTION SIGN, A	84.00	EACH
	0016	801-06645	CONSTRUCTION SIGN, B	12.00	EACH
	0017	801-12440	MAINTAINING TRAFFIC, IDIQ	1.00	DOL
	0018	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	1000.00	LFT
	0019	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	2000.00	LFT
	0020	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	2000.00	LFT



Call: 241

Contract: R -43132-A

Section No.: 1 TREE REMOVAL AND TRIMMING

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0007	201-01015	CLEARING AND GRUBBING	1.00 LS
0008	201-02245	TREE 6 IN., REMOVE	52.00 EACH
0009	201-02245	TREE 6 IN., REMOVE	4.00 EACH
0010	201-02250	TREE 10 IN., REMOVE	64.00 EACH
0011	201-02250	TREE 10 IN., REMOVE	4.00 EACH
0012	201-02255	TREE 18 IN., REMOVE	26.00 EACH
0013	201-02255	TREE 18 IN., REMOVE	4.00 EACH
0014	201-02260	TREE 30 IN., REMOVE	15.00 EACH
0015	201-02260	TREE 30 IN., REMOVE	3.00 EACH
0016	201-02265	TREE 48 IN., REMOVE	4.00 EACH
0017	201-02265	TREE 48 IN., REMOVE	4.00 EACH
0018	201-02270	TREE 60 IN., REMOVE	4.00 EACH
0019	201-02270	TREE 60 IN., REMOVE	2.00 EACH
0020	801-06710	FLASHING ARROW SIGN	20.00 DAY
0021	801-06775	MAINTAINING TRAFFIC	1.00 LS
0022	801-92448	CONSTRUCTION SIGNS MOBILE	330.00 DAY

Call: 251

Contract: R -43155-A

Section No.: 1 TREE REMOVAL AND TRIMMING

<b>Line</b>			<b>Quantity</b>	<b>Unit</b>
<b>Item No</b>	<b>Item Code</b>	<b>Description</b>		
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0005	201-02245	TREE 6 IN., REMOVE	100.00	EACH
0006	201-02250	TREE 10 IN., REMOVE	100.00	EACH
0007	201-02255	TREE 18 IN., REMOVE	50.00	EACH
0008	201-02260	TREE 30 IN., REMOVE	50.00	EACH
0009	201-02265	TREE 48 IN., REMOVE	30.00	EACH
0010	201-02270	TREE 60 IN., REMOVE	30.00	EACH
0011	801-06640	CONSTRUCTION SIGN, A	50.00	EACH
0012	801-06710	FLASHING ARROW SIGN	50.00	DAY
0013	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 281

Contract: RS-39385-A

Section No.: 1 ASPHALT RESURFACE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	207-12498	SUBGRADE TREATMENT, TYPE ID	326.00	SYS
0011	303-07449	COMPACTED AGGREGATE NO. 73	2936.00	TON
0012	304-12625	HMA PATCHING FULL DEPTH TYPE C	214.00	TON
0013	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	22.00	TON
0014	306-08036	MILLING, ASPHALT, 2 IN.	189637.00	SYS
0015	306-08432	MILLING, APPROACH	15067.00	SYS
0016	401-06264	PROFILOGRAPH, HMA	1.00	LS
0017	401-07347	QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	20861.00	TON
0018	401-10258	JOINT ADHESIVE, SURFACE	64027.00	LFT
0019	401-11785	LIQUID ASPHALT SEALANT	64027.00	LFT
0020	402-07452	HMA WEDGE AND LEVEL, TYPE C	50.00	TON
0021	406-05520	ASPHALT FOR TACK COAT	53.00	TON
0022	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	12.00	TON
0023	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	54265.00	LFT
0024	610-07487	HMA FOR APPROACHES, TYPE B	1246.00	TON
0025	628-09402	FIELD OFFICE, B	10.00	MOS
0026	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0027	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	27874.00	LFT
0028	801-06640	CONSTRUCTION SIGN, A	45.00	EACH
0029	801-06775	MAINTAINING TRAFFIC	1.00	LS
0030	808-04298	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, R X R	4.00	EACH
0031	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	23420.00	LFT

0032	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	217363.00	LFT
0033	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	89454.00	LFT
0034	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0035	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	20.00	LFT
0036	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	2.00	EACH
0037	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2397.00	EACH
0038	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	2397.00	EACH

Call: 291

Contract: RS-39413-A

Section No.: 1 HMA OVERLAY, PREVENTIVE MAINTENANCE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	207-12498	SUBGRADE TREATMENT, TYPE ID	229.00 SYS
0011	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	10.00 CYS
0012	302-06464	SUBBASE FOR PCCP	229.00 CYS
0013	303-01180	COMPACTED AGGREGATE NO. 53	400.00 TON
0014	304-12624	HMA PATCHING PARTIAL DEPTH TYPE B	159.00 TON
0015	304-12628	HMA PATCHING PARTIAL DEPTH TYPE D	940.00 TON
0016	306-08034	MILLING, ASPHALT, 1 1/2 IN.	662138.00 SYS
0017	306-08043	MILLING, TRANSITION	200.00 SYS
0018	306-08432	MILLING, APPROACH	1122.00 SYS
0019	401-06264	PROFILOGRAPH, HMA	1.00 LS
0020	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	12799.00 TON
0021	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1257.00 TON
0022	401-10258	JOINT ADHESIVE, SURFACE	307830.00 LFT
0023	401-12483	RAPID PENETRATING EMULSION	307830.00 LFT
0024	402-07787	HMA WEDGE AND LEVEL, TYPE D	50.00 TON
0025	406-05520	ASPHALT FOR TACK COAT	199.00 TON
0026	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	5.00 TON
0027	410-09530	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm - SMA	40570.00 TON
0028	503-03489	RETROFITTED TIE BARS	60.00 EACH
0029	503-05240	D-1 CONTRACTION JOINT	24.00 LFT
0030	506-06333	PCCP PATCHING, FULL DEPTH	229.00 SYS
0031	605-05523	CURB, HMA	50.00 LFT

0032	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	303020.00	LFT
0033	610-07487	HMA FOR APPROACHES, TYPE B	109.00	TON
0034	621-02770	EROSION CONTROL BLANKET	500.00	SYS
0035	628-09403	FIELD OFFICE, C	15.00	MOS
0036	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0037	628-11977	COMPUTER SYSTEM	1.00	EACH
0038	720-01355	INLET, CLEAN EXISTING	3.00	EACH
0039	720-44000	CASTING, ADJUST TO GRADE	5.00	EACH
0040	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.00	EACH
0041	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	19363.00	LFT
0042	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	19363.00	LFT
0043	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	2500.00	LFT
0044	801-06640	CONSTRUCTION SIGN, A	84.00	EACH
0045	801-06710	FLASHING ARROW SIGN	120.00	DAY
0046	801-06775	MAINTAINING TRAFFIC	1.00	LS
0047	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	2200.00	LFT
0048	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	6.00	EACH
0049	801-12042	TRUCK MOUNTED ATTENUATOR	120.00	DAY
0050	801-12324	LAW ENFORCEMENT OFFICER	1200.00	HRS
0051	801-12647	LAW ENFORCEMENT OFFICER TRAINING	1.00	DOL
0052	802-91122	SIGN GROUND MOUNTED RESET	4.00	EACH
0053	804-11920	DELINEATOR POST FLEXIBLE, TYPE I	25.00	EACH
0054	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0055	808-11882	LINE, PREFORMED PLASTIC, DOTTED, WHITE, 5 IN.	564.00	LFT
0056	808-12032	GROOVING FOR PAVEMENT MARKINGS	344106.00	LFT
0057	808-12666	LINE PREFORMED PLASTIC SOLID WHITE 10 IN.	4000.00	LFT
0058	808-75052	LINE, PREFORMED PLASTIC, SOLID, WHITE, 6 IN.	151510.00	LFT
0059	808-75057	LINE, PREFORMED PLASTIC, SOLID, YELLOW, 6 IN.	151510.00	LFT
0060	808-75061	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 5 IN.	36523.00	LFT
0061	808-75067	TRANSVERSE MARKING, PREFORMED PLASTIC, STOP LINE, WHITE, 24 IN.	50.00	LFT
0062	808-75510	TRANSVERSE MARKING, PREFORMED PLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	410.00	LFT
0063	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2237.00	EACH
0064	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	2237.00	EACH
0065	808-91662	TRANSVERSE MARKING, PREFORMED PLASTIC, CROSSHATCH LINE, WHITE 12 IN.	440.00	LFT

Call: 301

Contract: RS-39809-A

Section No.: 1 ASPHALT RESURFACE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0013	202-02240	PAVEMENT REMOVAL	330.00 SYS
0014	202-02271	HEADWALL, REMOVE	2.00 EACH
0015	202-02272	PAVED SIDE DITCH, REMOVE	320.00 LFT
0016	202-05545	REGULATED MATERIALS, DISPOSE, TYPE C	1887.00 CYS
0017	202-05555	REGULATED MATERIALS, TRANSPORT, TYPE C	1887.00 CYS
0018	202-06580	CONTAMINATED SOIL, REMOVE	1887.00 CYS
0019	202-51330	PRESENT STRUCTURE, REMOVE	1.00 LS
0020	202-52710	SIDEWALK CONCRETE, REMOVE	26.00 SYS
0021	202-93615	CONCRETE, REMOVE	107.00 SYS
0022	202-93741	GUARDRAIL, END TREATMENT, REMOVE	1.00 EACH
0023	202-97009	FIRE HYDRANT ASSEMBLY, REMOVE	6.00 EACH
0024	203-02000	EXCAVATION, COMMON	5151.00 CYS
0025	203-02070	BORROW	248.00 CYS
0026	205-11626	PUMP AROUND	2.00 EACH
0027	205-12108	STORMWATER MANAGEMENT BUDGET	42600.00 DOL
0028	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0029	205-12618	SWQCP PREPARATION	1.00 LS
0030	207-08264	SUBGRADE TREATMENT, TYPE II	1203.00 SYS
0031	207-09935	SUBGRADE TREATMENT, TYPE IC	1611.00 SYS

0032	207-12498	SUBGRADE TREATMENT, TYPE ID	196.00	SYS
0033	207-12635	SUBGRADE TREATMENT, TYPE IBC	16302.00	SYS
0034	211-09264	STRUCTURE BACKFILL, TYPE 1	7685.00	CYS
0035	211-09264	STRUCTURE BACKFILL, TYPE 1	5100.00	CYS
0036	211-09264	STRUCTURE BACKFILL, TYPE 1	1700.00	CYS
0037	211-09268	STRUCTURE BACKFILL, TYPE 5	429.20	CYS
0038	214-11796	GEOGRID, TYPE IB	621.00	SYS
0039	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	197.00	SYS
0040	301-12232	COMPACTED AGGREGATE NO. 5	31.00	CYS
0041	301-12234	COMPACTED AGGREGATE NO. 53	16.00	CYS
0042	302-07455	DENSE GRADED SUBBASE	1061.00	CYS
0043	303-01180	COMPACTED AGGREGATE NO. 53	243.00	TON
0044	303-07449	COMPACTED AGGREGATE NO. 73	594.00	TON
0045	304-07494	WIDENING WITH HMA, TYPE C	69.00	TON
0046	304-12625	HMA PATCHING FULL DEPTH TYPE C	949.00	TON
0047	304-12625	HMA PATCHING FULL DEPTH TYPE C	15.00	TON
0048	304-12625	HMA PATCHING FULL DEPTH TYPE C	35.00	TON
0049	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	266.00	TON
0050	306-08034	MILLING, ASPHALT, 1 1/2 IN.	46799.00	SYS
0051	306-08036	MILLING, ASPHALT, 2 IN.	7879.00	SYS
0052	306-08432	MILLING, APPROACH	4665.00	SYS
0053	401-06264	PROFILOGRAPH, HMA	1.00	LS
0054	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	3801.00	TON
0055	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1942.00	TON
0056	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	22.00	TON
0057	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	1801.00	TON
0058	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	74.00	TON
0059	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	4258.00	TON
0060	401-10258	JOINT ADHESIVE, SURFACE	29157.00	LFT
0061	401-10259	JOINT ADHESIVE, INTERMEDIATE	7661.00	LFT
0062	401-11785	LIQUID ASPHALT SEALANT	29157.00	LFT
0063	406-05520	ASPHALT FOR TACK COAT	35.10	TON
0064	601-06035	GUARDRAIL, RESET	100.00	LFT
0065	601-06038	GUARDRAIL, END TREATMENT, II	1.00	EACH
0066	601-09238	HAND DIG GUARDRAIL POST HOLES	4.00	EACH
0067	604-03643	BRICK PAVERS	13.00	SYS
0068	604-06070	SIDEWALK, CONCRETE	2459.00	SYS



0069	604-08086	CURB RAMP, CONCRETE	362.00	SYS
0070	604-12083	DETECTABLE WARNING SURFACES	60.00	SYS
0071	605-06120	CURB, CONCRETE	3663.00	LFT
0072	605-06140	CURB AND GUTTER, CONCRETE	441.00	LFT
0073	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	9943.00	LFT
0074	610-07488	HMA FOR APPROACHES, TYPE C	352.00	TON
0075	610-08446	PCCP FOR APPROACHES, 6 IN.	523.00	SYS
0076	610-09108	PCCP FOR APPROACHES, 9 IN.	538.00	SYS
0077	611-06497	MAILBOX ASSEMBLY, SINGLE	19.00	EACH
0078	611-06498	MAILBOX ASSEMBLY, DOUBLE	1.00	EACH
0079	611-08232	MAILBOX ASSEMBLY, RESET SINGLE	2.00	EACH
0080	615-06490	RIGHT-OF-WAY MARKER	11.00	EACH
0081	615-06505	MONUMENT, B	7.00	EACH
0082	615-06520	MONUMENT, RE-ESTABLISH	2.00	EACH
0083	615-06527	MONUMENT, SECTION CORNER	3.00	EACH
0084	616-06405	RIPRAP, REVETMENT	352.00	TON
0085	616-06405	RIPRAP, REVETMENT	21.00	TON
0086	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	487.00	SYS
0087	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	38.00	SYS
0088	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	18.00	SYS
0089	616-12496	SLOPE PROTECTION	30.00	SYS
0090	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0091	621-02770	EROSION CONTROL BLANKET	250.00	SYS
0092	621-06559	MULCHED SEEDING R	1518.00	SYS
0093	621-06567	WATER	19.00	kGAL
0094	621-06575	SODDING, NURSERY	4705.00	SYS
0095	621-06575	SODDING, NURSERY	750.00	SYS
0096	621-06575	SODDING, NURSERY	150.00	SYS
0097	628-09402	FIELD OFFICE, B	13.00	MOS
0098	628-11976	COMPUTER SYSTEM EQUIPMENT	4.00	EACH
0099	702-44240	CONCRETE, A, STRUCTURES	4.60	CYS
0100	703-06029	REINFORCING BARS, EPOXY COATED	756.30	LBS
0101	714-11195	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 10 FT X 9 FT	52.00	LFT
0102	715-02744	GATE VALVE AND VALVE BOX 6 IN	6.00	EACH
0103	715-02745	GATE VALVE WITH VALVE BOX 8 IN.	11.00	EACH
0104	715-04987	CONNECTION	16.00	EACH
0105	715-05024	PIPE, TYPE 2, CIRCULAR, 36 IN.	1692.00	LFT

0106	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	5376.00	LFT
0107	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	28.00	LFT
0108	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	1742.00	LFT
0109	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	386.00	LFT
0110	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	120.00	LFT
0111	715-05153	PIPE, TYPE 2, CIRCULAR, 21 IN.	285.00	LFT
0112	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	330.00	LFT
0113	715-05159	PIPE, TYPE 2, CIRCULAR, 42 IN.	228.00	LFT
0114	715-05161	PIPE, TYPE 2, CIRCULAR, 48 IN.	1162.00	LFT
0115	715-05408	PIPE, SANITARY SEWER, 8 IN.	20.00	LFT
0116	715-05411	PIPE, SANITARY SEWER, 12 IN.	604.00	LFT
0117	715-05412	PIPE, SANITARY SEWER, 15 IN.	3944.00	LFT
0118	715-06004	CONCRETE ANCHOR, 48 IN.	1.00	EACH
0119	715-07794	WATER MAIN CONNECTIONS	18.00	EACH
0120	715-09064	VIDEO INSPECTION FOR PIPE	5945.00	LFT
0121	715-11879	SEWER, SANITARY LATERAL, CONNECTIONS	2355.00	LFT
0122	715-11896	WATER SERVICE CONNECTION	10.00	EACH
0123	715-12674	GATE VALVE AND VALVE BOX 12 IN	11.00	EACH
0124	715-90853	TAPPING SLEEVE WITH VALVE	1.00	EACH
0125	715-93403	WATER SERVICE CONNECTION, 0.75 IN.	38.00	EACH
0126	715-93912	WATER MAIN, 6 IN.	216.00	LFT
0127	715-93913	WATER MAIN, 8 IN.	1098.00	LFT
0128	715-98165	WATER MAIN, 12 IN.	3246.00	LFT
0129	718-06528	OUTLET PROTECTOR, 1	2.00	EACH
0130	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	3000.00	LFT
0131	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	3686.00	SYS
0132	718-52610	AGGREGATE FOR UNDERDRAINS	484.00	CYS
0133	720-44000	CASTING, ADJUST TO GRADE	6.00	EACH
0134	720-45030	INLET, E7	3.00	EACH
0135	720-45045	INLET, J10	88.00	EACH
0136	720-45055	INLET, M10	29.00	EACH
0137	720-45410	MANHOLE, C4	11.00	EACH
0138	720-45510	MANHOLE, C4 MODIFIED	20.00	EACH
0139	720-91973	MANHOLE, H4	33.00	EACH
0140	720-94612	MANHOLE, K4	14.00	EACH
0141	720-96999	FIRE HYDRANT ASSEMBLY	12.00	EACH
0142	720-98174	INLET, B15	6.00	EACH

0143	732-03944	BACKFLOW PREVENTER	1.00 EACH
0144	801-04308	ROAD CLOSURE SIGN ASSEMBLY	36.00 EACH
0145	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	1840.00 LFT
0146	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1840.00 LFT
0147	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	24.00 LFT
0148	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	24.00 LFT
0149	801-06625	DETOUR ROUTE MARKER ASSEMBLY	79.00 EACH
0150	801-06640	CONSTRUCTION SIGN, A	86.00 EACH
0151	801-06775	MAINTAINING TRAFFIC	1.00 LS
0152	801-07118	BARRICADE, III-A	540.00 LFT
0153	801-07119	BARRICADE, III-B	384.00 LFT
0154	801-92448	CONSTRUCTION SIGNS MOBILE	750.00 DAY
0155	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	204.00 LFT
0156	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	99.40 SFT
0157	804-76350	DELINEATOR WITH POST, D3	2.00 EACH
0158	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	582.00 LFT
0159	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	933.00 LFT
0160	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	933.00 LFT
0161	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	476.00 LFT
0162	805-78785	SIGNAL DETECTOR HOUSING	2.00 EACH
0163	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	660.00 LFT
0164	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS
0165	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	34138.00 LFT
0166	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	27472.00 LFT
0167	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	2252.00 LFT
0168	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	351.00 LFT
0169	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	6.00 EACH
0170	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	1555.00 LFT
0171	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	8.00 EACH
0172	808-12032	GROOVING FOR PAVEMENT MARKINGS	39809.00 LFT
0173	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	660.00 LFT
0174	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	364.00 EACH
0175	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	111.00 EACH

Call: 311

Contract: RS-40563-A

Section No.: 1 INTERSECTION IMPROVEMENT, MEDIAN U-TURN

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
	0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0012	202-91385	INLET, REMOVE	4.00	EACH
	0013	203-02000	EXCAVATION, COMMON	2475.00	CYS
	0014	203-02070	BORROW	1590.00	CYS
	0015	205-12108	STORMWATER MANAGEMENT BUDGET	25145.00	DOL
	0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0017	205-12618	SWQCP PREPARATION	1.00	LS
	0018	207-12635	SUBGRADE TREATMENT, TYPE IBC	7925.00	SYS
	0019	211-02050	B BORROW	28.00	CYS
	0020	211-09265	STRUCTURE BACKFILL, TYPE 2	75.00	CYS
	0021	303-01180	COMPACTED AGGREGATE NO. 53	1781.00	TON
	0022	401-06264	PROFILOGRAPH, HMA	1.00	LS
	0023	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	553.00	TON
	0024	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	938.00	TON
	0025	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	3011.00	TON
	0026	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	1182.00	TON
	0027	502-03289	QUALITY ASSURANCE ADJUSTMENT	1.00	DOL
	0028	502-06999	PCCP, 8 IN.	152.00	SYS
	0029	503-05240	D-1 CONTRACTION JOINT	105.00	LFT
	0030	605-06145	CURB AND GUTTER, B, CONCRETE	222.00	LFT
	0031	605-06255	CENTER CURB, D CONCRETE	238.00	SYS

0032	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	462.00	LFT
0033	616-06405	RIPRAP, REVETMENT	19.00	TON
0034	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	47.00	SYS
0035	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0036	621-06545	FERTILIZER	4.00	TON
0037	621-06553	SEED MIXTURE R	2249.00	LBS
0038	621-06565	MULCHING MATERIAL	22.00	TON
0039	621-06567	WATER	5.00	kGAL
0040	621-06574	SODDING	1180.00	SYS
0041	628-09402	FIELD OFFICE, B	15.00	MOS
0042	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0043	628-11977	COMPUTER SYSTEM	1.00	EACH
0044	629-12029	PLANT GROWTH LAYER	8686.00	SYS
0045	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	3901.00	LFT
0046	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	327.00	LFT
0047	715-05121	PIPE, TYPE 1, CIRCULAR, 18 IN.	150.00	LFT
0048	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	24.00	LFT
0049	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	109.00	LFT
0050	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	19.00	LFT
0051	715-09064	VIDEO INSPECTION FOR PIPE	128.00	LFT
0052	715-46010	PIPE END SECTION, DIAMETER 18 IN.	4.00	EACH
0053	718-06528	OUTLET PROTECTOR, 1	12.00	EACH
0054	718-12306	GEOTEXTILE FOR UNDERDRAIN, TYPE 1B	2674.00	SYS
0055	718-52610	AGGREGATE FOR UNDERDRAINS	337.00	CYS
0056	720-45069	INLET, P12	5.00	EACH
0057	720-45415	MANHOLE, D4	1.00	EACH
0058	720-98174	INLET, B15	1.00	EACH
0059	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.00	EACH
0060	801-03290	CONSTRUCTION SIGN, C	10.00	EACH
0061	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3372.00	LFT
0062	801-06640	CONSTRUCTION SIGN, A	18.00	EACH
0063	801-06645	CONSTRUCTION SIGN, B	6.00	EACH
0064	801-06775	MAINTAINING TRAFFIC	1.00	LS
0065	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0066	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	440.00	LFT
0067	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	87.00	LFT
0068	802-05703	SIGN POST, SQUARE TYPE 3 REINFORCED ANCHOR BASE	26.00	LFT

0069	802-07057	SIGN, PANEL, WITH LEGEND	376.00	SFT
0070	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	38.00	EACH
0071	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	72.00	SFT
0072	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	362.00	SFT
0073	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	65.00	SFT
0074	802-12222	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, A	4.00	EACH
0075	802-12223	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, B	4.00	EACH
0076	802-76095	STRUCTURAL STEEL, BREAKAWAY	2182.00	LBS
0077	804-06770	DELINEATOR POST	31.00	EACH
0078	807-02191	HANDHOLE LIGHTING	7.00	EACH
0079	807-02934	LIGHTING FOUNDATION, CONCRETE WITH GROUNDING 36 IN. X 36 IN. X 96 IN.	22.00	EACH
0080	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	646.00	LFT
0081	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	4467.00	LFT
0082	807-12202	LUMINAIRE, LOW LUMEN ROADWAY	22.00	EACH
0083	807-12343	CABLE, POLE CIRCUIT, XHHW, NO 10 COPPER, STRANDED, 1/C	2570.00	LFT
0084	807-85752	LIGHT POLE, 40 FT. E.M.H. 10.0 FT. MAST ARM, BREAKAWAY BASE	7.00	EACH
0085	807-85762	LIGHT POLE, 40 FT. E.M.H. 15.0 FT. MAST ARM, BREAKAWAY BASE	15.00	EACH
0086	807-86805	SERVICE POINT, I	1.00	EACH
0087	807-86910	CONNECTOR KIT, UNFUSED	22.00	EACH
0088	807-86915	CONNECTOR KIT, FUSED	22.00	EACH
0089	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	44.00	EACH
0090	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	22.00	EACH
0091	807-86930	INSULATION LINK, NON-WATERPROOFED	44.00	EACH
0092	807-86935	INSULATION LINK, WATERPROOFED	22.00	EACH
0093	808-06716	LINE, REMOVE	2656.00	LFT
0094	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0095	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	2808.00	LFT
0096	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	2336.00	LFT
0097	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	3740.00	LFT
0098	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	2820.00	LFT
0099	808-10038	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE WHITE 24 IN.	281.00	LFT
0100	808-10042	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, YELLOW 12 IN.	474.00	LFT
0101	808-10047	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, WHITE, 12 IN.	160.00	LFT
0102	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	93.00	LFT
0103	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	2.00	EACH
0104	808-10058	LINE, MULTI-COMPONENT, SOLID, YELLOW, 8 IN.	438.00	LFT
0105	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	24.00	EACH

0106	808-11776	TRANSVERSE MARKING, MULTI-COMPONENT, YIELD LINE, WHITE, 24 IN.	28.00	LFT
0107	808-12032	GROOVING FOR PAVEMENT MARKINGS	12263.00	LFT
0108	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	149.00	EACH

Call: 321

Contract: RS-40939-A

Section No.: 1 ASPHALT RESURFACE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	207-12498	SUBGRADE TREATMENT, TYPE ID	786.00 SYS
0012	304-12623	HMA PATCHING FULL DEPTH TYPE B	555.00 TON
0013	304-12624	HMA PATCHING PARTIAL DEPTH TYPE B	262.00 TON
0014	306-08036	MILLING, ASPHALT, 2 IN.	330349.00 SYS
0015	306-08043	MILLING, TRANSITION	400.00 SYS
0016	306-08432	MILLING, APPROACH	27255.00 SYS
0017	401-06264	PROFILOGRAPH, HMA	1.00 LS
0018	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	36339.00 TON
0019	401-10258	JOINT ADHESIVE, SURFACE	118910.00 LFT
0020	401-11785	LIQUID ASPHALT SEALANT	118910.00 LFT
0021	406-05520	ASPHALT FOR TACK COAT	108.00 TON
0022	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	15.00 TON
0023	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	81795.00 LFT
0024	610-07487	HMA FOR APPROACHES, TYPE B	2998.00 TON
0025	615-06525	CASTING ADJUST TO GRADE, MONUMENT	2.00 EACH
0026	628-09403	FIELD OFFICE, C	10.00 MOS
0027	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0028	720-44000	CASTING, ADJUST TO GRADE	2.00 EACH
0029	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	15926.00 LFT
0030	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	15926.00 LFT
0031	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	1150.00 LFT



0032	801-06213	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, (RXR)	2.00 EACH
0033	801-06640	CONSTRUCTION SIGN, A	99.00 EACH
0034	801-06645	CONSTRUCTION SIGN, B	1.00 EACH
0035	801-06775	MAINTAINING TRAFFIC	1.00 LS
0036	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00 EACH
0037	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	6625.00 LFT
0038	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	663.00 LFT
0039	805-78785	SIGNAL DETECTOR HOUSING	16.00 EACH
0040	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	2120.00 LFT
0041	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	414.00 LFT
0042	808-04298	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, R X R	2.00 EACH
0043	808-04723	LINE, THERMOPLASTIC, FOR BUZZ STRIPS, 4 IN.	420.00 LFT
0044	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	3928.00 LFT
0045	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	104031.00 LFT
0046	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	372.00 LFT
0047	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS
0048	808-10118	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 24 IN.	24.00 LFT
0049	808-12032	GROOVING FOR PAVEMENT MARKINGS	129310.00 LFT
0050	808-12667	LINE THERMOPLASTIC SOLID WHITE 10 IN.	260.00 LFT
0051	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	121430.00 LFT
0052	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	85918.00 LFT
0053	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	7324.00 LFT
0054	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	35808.00 LFT
0055	808-75272	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	140.00 LFT
0056	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	740.00 LFT
0057	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	556.00 LFT
0058	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	28.00 EACH
0059	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2367.00 EACH
0060	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	2367.00 EACH

Call: 331

Contract: RS-41081-A

Section No.: 1 ASPAHLT RESURFACE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	10.00 EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0004	109-08360	CONTRACT LIENS	1.00 DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0009	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0010	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0011	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0012	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0013	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0014	202-02278	CURB, CONCRETE, REMOVE	2922.00 LFT
0015	202-52710	SIDEWALK CONCRETE, REMOVE	2387.00 SYS
0016	202-90277	DETECTOR HOUSING, REMOVE	24.00 EACH
0017	205-12108	STORMWATER MANAGEMENT BUDGET	5170.00 DOL
0018	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0019	207-08264	SUBGRADE TREATMENT, TYPE II	84.00 SYS
0020	207-12498	SUBGRADE TREATMENT, TYPE ID	5213.00 SYS
0021	301-12234	COMPACTED AGGREGATE NO. 53	70.00 CYS
0022	302-06464	SUBBASE FOR PCCP	15.00 CYS
0023	303-01180	COMPACTED AGGREGATE NO. 53	82.00 TON
0024	303-07449	COMPACTED AGGREGATE NO. 73	173.00 TON
0025	304-12625	HMA PATCHING FULL DEPTH TYPE C	2876.00 TON
0026	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	1879.00 TON
0027	306-08036	MILLING, ASPHALT, 2 IN.	222219.00 SYS
0028	306-08432	MILLING, APPROACH	23622.00 SYS
0029	401-06264	PROFILOGRAPH, HMA	1.00 LS
0030	401-07347	QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	24305.00 TON
0031	401-10258	JOINT ADHESIVE, SURFACE	93375.00 LFT

0032	401-11785	LIQUID ASPHALT SEALANT	136022.00	LFT
0033	406-05520	ASPHALT FOR TACK COAT	82.00	TON
0034	506-06333	PCCP PATCHING, FULL DEPTH	75.00	SYS
0035	604-06070	SIDEWALK, CONCRETE	1277.00	SYS
0036	604-08086	CURB RAMP, CONCRETE	1320.00	SYS
0037	604-12083	DETECTABLE WARNING SURFACES	296.00	SYS
0038	604-12084	DETECTABLE WARNING SURFACES, RETROFIT	57.00	SYS
0039	604-95344	HAND RAIL, PEDESTRIAN	15.00	LFT
0040	605-06120	CURB, CONCRETE	3151.00	LFT
0041	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	62753.00	LFT
0042	610-07488	HMA FOR APPROACHES, TYPE C	2624.00	TON
0043	611-08232	MAILBOX ASSEMBLY, RESET SINGLE	3.00	EACH
0044	621-06567	WATER	20.00	KGAL
0045	621-06575	SODDING, NURSERY	299.00	SYS
0046	628-09402	FIELD OFFICE, B	13.00	MOS
0047	628-11976	COMPUTER SYSTEM EQUIPMENT	4.00	EACH
0048	720-44000	CASTING, ADJUST TO GRADE	59.00	EACH
0049	720-44000	CASTING, ADJUST TO GRADE	62.00	EACH
0050	720-44000	CASTING, ADJUST TO GRADE	75.00	EACH
0051	720-94840	CASTING, WATER VALVE, ADJUST TO GRADE	70.00	EACH
0052	801-03291	CONSTRUCTION SIGN, D	19.00	EACH
0053	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	14839.00	LFT
0054	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	14839.00	LFT
0055	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	74.00	LFT
0056	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	74.00	LFT
0057	801-06640	CONSTRUCTION SIGN, A	145.00	EACH
0058	801-06645	CONSTRUCTION SIGN, B	566.00	EACH
0059	801-06775	MAINTAINING TRAFFIC	1.00	LS
0060	801-07118	BARRICADE, III-A	768.00	LFT
0061	801-92448	CONSTRUCTION SIGNS MOBILE	550.00	DAY
0062	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	21.00	LFT
0063	802-07060	SIGN, SHEET, RELOCATE	4.00	EACH
0064	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	11005.00	LFT
0065	805-78785	SIGNAL DETECTOR HOUSING	24.00	EACH
0066	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	3808.00	LFT
0067	808-04298	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, R X R	4.00	EACH
0068	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	73411.00	LFT

0069	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	351.00	LFT
0070	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	5440.00	LFT
0071	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	7864.00	LFT
0072	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	6313.00	LFT
0073	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0074	808-12032	GROOVING FOR PAVEMENT MARKINGS	115164.00	LFT
0075	808-12273	TRANSVERSE MARKING, THERMOPLASTIC, PARKING LINE, WHITE 4 IN.	462.00	LFT
0076	808-12274	TRANSVERSE MARKING, THERMOPLASTIC, PARKING LINE, BLUE 4 IN.	936.00	LFT
0077	808-74815	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 12 IN.	183.00	LFT
0078	808-75008	LINE, PAINT, SOLID, WHITE, 8 IN.	33.00	LFT
0079	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	5070.00	LFT
0080	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	31949.00	LFT
0081	808-75290	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 24 IN.	615.00	LFT
0082	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	1410.00	LFT
0083	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	3416.00	LFT
0084	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	32.00	EACH
0085	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	2.00	EACH
0086	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1206.00	EACH
0087	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	635.00	EACH
0088	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	4756.00	LFT
0089	808-97664	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ADA ACCESSIBLE SYMBOL	8.00	EACH
0090	808-98875	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 6 IN.	848.00	LFT

Call: 401

Contract: B -30773-A

Section No.: 1

BRIDGE REHABILITATION OR REPAIR

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0011	202-02240	PAVEMENT REMOVAL	27.00 SYS
0012	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0013	203-02000	EXCAVATION, COMMON	739.00 CYS
0014	203-02070	BORROW	1493.00 CYS
0015	203-51223	EXCAVATION, WATERWAY	170.00 CYS
0016	205-12108	STORMWATER MANAGEMENT BUDGET	25000.00 DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0018	205-12618	SWQCP PREPARATION	1.00 LS
0019	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	28.00 CYS
0020	207-08264	SUBGRADE TREATMENT, TYPE II	42.00 SYS
0021	207-09935	SUBGRADE TREATMENT, TYPE IC	3676.00 SYS
0022	211-06467	AGGREGATE FOR END BENT BACKFILL	26.00 CYS
0023	211-09265	STRUCTURE BACKFILL, TYPE 2	14.00 CYS
0024	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	2793.00 SYS
0025	301-12234	COMPACTED AGGREGATE NO. 53	7.00 CYS
0026	302-06464	SUBBASE FOR PCCP	30.00 CYS
0027	303-01180	COMPACTED AGGREGATE NO. 53	335.00 TON
0028	306-08034	MILLING, ASPHALT, 1 1/2 IN.	672.00 SYS
0029	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	218.00 TON
0030	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	347.00 TON
0031	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	771.00 TON

0032	401-10258	JOINT ADHESIVE, SURFACE	1450.00	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	1173.00	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	1450.00	LFT
0035	402-10084	HMA FOR TEMPORARY PAVEMENT, B	710.00	TON
0036	406-05520	ASPHALT FOR TACK COAT	3.00	TON
0037	601-02241	GUARDRAIL, REMOVE	623.00	LFT
0038	601-06374	GUARDRAIL, TRANSITION, TGS-1	4.00	EACH
0039	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	338.00	LFT
0040	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00	EACH
0041	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0042	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	114.00	SYS
0043	610-07487	HMA FOR APPROACHES, TYPE B	9.00	TON
0044	615-06490	RIGHT-OF-WAY MARKER	10.00	EACH
0045	615-06505	MONUMENT, B	3.00	EACH
0046	616-05688	RIPRAP, CLASS 1	660.00	TON
0047	616-06405	RIPRAP, REVETMENT	18.00	TON
0048	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	320.00	SYS
0049	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0050	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0051	619-12506	CLEAN STEEL BRIDGE TOP FLANGES QP-2 BRIDGE NO.	1.00	LS
0052	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0053	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0054	621-02770	EROSION CONTROL BLANKET	5082.00	SYS
0055	621-04258	SEED MIXTURE	6.00	LBS
0056	621-06545	FERTILIZER	1.00	TON
0057	621-06553	SEED MIXTURE R	12.00	LBS
0058	622-05639	PLANT, DECIDUOUS SHRUB, 18 TO 24 IN.	32.00	EACH
0059	622-05650	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 IN. TO 2.5 IN.	63.00	EACH
0060	622-52436	SIGN, DO NOT MOW OR SPRAY	8.00	EACH
0061	628-09402	FIELD OFFICE, B	12.00	MOS
0062	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0063	629-12029	PLANT GROWTH LAYER	5082.00	SYS
0064	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	8.00	EACH
0065	702-51005	CONCRETE, A, SUBSTRUCTURE	13.00	CYS
0066	702-51863	FIELD DRILLED HOLE IN CONCRETE	40.00	EACH
0067	703-06029	REINFORCING BARS, EPOXY COATED	31639.00	LBS
0068	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	26.00	EACH

0069	704-51002	CONCRETE, C, SUPERSTRUCTURE	104.90	CYS
0070	709-51821	SURFACE SEAL	1.00	LS
0071	710-09158	PATCHING CONCRETE STRUCTURES	35.00	SFT
0072	711-51038	STRUCTURAL STEEL	1.00	LS
0073	711-51866	RIVET, REMOVE	2233.00	EACH
0074	711-51876	JACKING AND SUPPORTING, TRUSSES	1.00	LS
0075	711-96800	STUD SHEAR CONNECTORS	810.00	EACH
0076	713-07661	GUARDRAIL, END TREATMENT, OS, TEMP BRIDGE APPROACH	4.00	EACH
0077	713-51335	TEMPORARY BRIDGE AND APPROACHES	1.00	LS
0078	713-99365	GUARDRAIL, W BEAM 6.3 FT SPACING TEMPORARY BRIDGE APPROACHES	175.00	LFT
0079	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	270.00	LFT
0080	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	8.00	EACH
0081	715-46000	PIPE END SECTION, DIAMETER 12 IN.	1.00	EACH
0082	718-12306	GEOTEXTILE FOR UNDERDRAIN, TYPE 1B	72.00	SYS
0083	720-45410	MANHOLE, C4	1.00	EACH
0084	724-12103	PRE-COMPRESSED FOAM JOINT	50.00	LFT
0085	727-90308	EPOXY INJECTION, CRACK PREPARATION	22.00	LFT
0086	727-90309	EPOXY INJECTION, EPOXY MATERIAL	3.00	GAL
0087	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0088	801-04308	ROAD CLOSURE SIGN ASSEMBLY	9.00	EACH
0089	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	3125.00	LFT
0090	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2764.00	LFT
0091	801-06625	DETOUR ROUTE MARKER ASSEMBLY	45.00	EACH
0092	801-06640	CONSTRUCTION SIGN, A	42.00	EACH
0093	801-06645	CONSTRUCTION SIGN, B	16.00	EACH
0094	801-06649	TEMPORARY RAISED PAVEMENT MARKER, GRADE 1	29.00	EACH
0095	801-06775	MAINTAINING TRAFFIC	1.00	LS
0096	801-07118	BARRICADE, III-A	72.00	LFT
0097	801-07119	BARRICADE, III-B	120.00	LFT
0098	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0099	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	205.00	LFT
0100	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	46.00	LFT
0101	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	64.00	LFT
0102	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	1.00	EACH
0103	802-07060	SIGN, SHEET, RELOCATE	23.00	EACH
0104	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	43.00	SFT
0105	804-06740	DELINEATOR WITH POST, D2	49.00	EACH

0106	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	60.00	LFT
0107	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1833.00	LFT
0108	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	2374.00	LFT
0109	808-06716	LINE, REMOVE	400.00	LFT
0110	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	9.00	EACH
0111	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	10.00	EACH



Call: 411

Contract: B -36441-A

Section No.: 1 BRIDGE REPLACEMENT

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0011	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
	0012	203-02000	EXCAVATION, COMMON	4005.00	CYS
	0013	203-02070	BORROW	11480.00	CYS
	0014	205-12108	STORMWATER MANAGEMENT BUDGET	20661.00	DOL
	0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0016	205-12618	SWQCP PREPARATION	1.00	LS
	0017	206-51220	EXCAVATION, WET	1105.00	CYS
	0018	206-51225	EXCAVATION, DRY	75.00	CYS
	0019	206-51235	COFFERDAM	1.00	LS
	0020	207-08262	SUBGRADE TREATMENT, TYPE I	2794.00	SYS
	0021	207-08264	SUBGRADE TREATMENT, TYPE II	597.00	SYS
	0022	207-09935	SUBGRADE TREATMENT, TYPE IC	154.00	SYS
	0023	211-02050	B BORROW	365.00	CYS
	0024	211-06467	AGGREGATE FOR END BENT BACKFILL	47.00	CYS
	0025	211-09268	STRUCTURE BACKFILL, TYPE 5	76.00	CYS
	0026	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	28.00	CYS
	0027	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	154.00	SYS
	0028	301-12234	COMPACTED AGGREGATE NO. 53	54.00	CYS
	0029	302-06464	SUBBASE FOR PCCP	29.00	CYS
	0030	303-01180	COMPACTED AGGREGATE NO. 53	319.00	TON
	0031	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	204.00	TON

0032	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	697.00 TON
0033	401-10258	JOINT ADHESIVE, SURFACE	990.00 LFT
0034	401-11785	LIQUID ASPHALT SEALANT	990.00 LFT
0035	406-05520	ASPHALT FOR TACK COAT	1.00 TON
0036	503-12477	TERMINAL JOINT, TYPE HMA	58.00 LFT
0037	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	13.00 LFT
0038	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00 EACH
0039	601-94689	GUARDRAIL, END TREATMENT, OS	4.00 EACH
0040	602-06729	BARRIER, DELINEATOR	20.00 EACH
0041	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	142.00 SYS
0042	610-07487	HMA FOR APPROACHES, TYPE B	74.00 TON
0043	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00 EACH
0044	615-06490	RIGHT-OF-WAY MARKER	14.00 EACH
0045	615-06505	MONUMENT, B	4.00 EACH
0046	615-06510	MONUMENT, C	1.00 EACH
0047	616-06405	RIPRAP, REVETMENT	719.00 TON
0048	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	968.00 SYS
0049	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 EACH
0050	621-03909	SEED MIXTURE, NATIVE	113.00 LBS
0051	621-06545	FERTILIZER	0.30 TON
0052	621-06553	SEED MIXTURE R	144.00 LBS
0053	621-06565	MULCHING MATERIAL	1.00 TON
0054	621-06567	WATER	2.00 KGAL
0055	621-06574	SODDING	491.00 SYS
0056	622-05639	PLANT, DECIDUOUS SHRUB, 18 TO 24 IN.	338.00 EACH
0057	622-05648	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. OR UNDER	667.00 EACH
0058	622-52436	SIGN, DO NOT MOW OR SPRAY	60.00 EACH
0059	628-09402	FIELD OFFICE, B	12.00 MOS
0060	629-12029	PLANT GROWTH LAYER	4795.00 SYS
0061	701-06011	DYNAMIC PILE LOAD TEST	2.00 EACH
0062	701-09557	TEST PILE, DYNAMIC, PRODUCTION	119.00 LFT
0063	701-09559	TEST PILE, DYNAMIC, RESTRIKE	2.00 EACH
0064	701-09663	PILE, STEEL PIPE, 0.312 IN., 14 IN.	1869.00 LFT
0065	701-09679	CONICAL PILE TIP, 14 IN.	40.00 EACH
0066	702-51005	CONCRETE, A, SUBSTRUCTURE	152.60 CYS
0067	702-51015	CONCRETE, B, FOOTINGS	94.80 CYS
0068	702-51046	CONCRETE, FOUNDATION SEAL	400.80 CYS

0069	702-92857	CONCRETE, C, SUBSTRUCTURE	25.50	CYS
0070	703-06028	REINFORCING BARS	35078.00	LBS
0071	703-06029	REINFORCING BARS, EPOXY COATED	101692.00	LBS
0072	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	30.00	EACH
0073	704-51002	CONCRETE, C, SUPERSTRUCTURE	345.60	CYS
0074	706-06351	CONCRETE BRIDGE RAILING TRANSITION, TPF-1	4.00	EACH
0075	706-11404	RAILING, STEEL PF-1	659.00	LFT
0076	706-11602	RAILING, CONCRETE PF-1	39.40	CYS
0077	707-09382	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 54 IN. X 61 IN.	1276.00	LFT
0078	709-51821	SURFACE SEAL	1.00	LS
0079	714-12522	STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS, 11 FT X 4 FT	73.00	LFT
0080	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	35.00	LFT
0081	715-05173	PIPE, TYPE 3, CIRCULAR, 24 IN.	80.00	LFT
0082	715-05407	PIPE, END BENT DRAIN, 6 IN.	117.00	LFT
0083	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00	EACH
0084	715-46020	PIPE END SECTION, DIAMETER 24 IN.	4.00	EACH
0085	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	85.00	SYS
0086	720-44000	CASTING, ADJUST TO GRADE	1.00	EACH
0087	720-44000	CASTING, ADJUST TO GRADE	1.00	EACH
0088	724-12103	PRE-COMPRESSED FOAM JOINT	58.00	LFT
0089	731-03915	ARCHITECTURAL SURFACE TREATMENT	2437.00	SFT
0090	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00	EACH
0091	801-06645	CONSTRUCTION SIGN, B	6.00	EACH
0092	801-06775	MAINTAINING TRAFFIC	1.00	LS
0093	801-07118	BARRICADE, III-A	72.00	LFT
0094	801-07119	BARRICADE, III-B	72.00	LFT
0095	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	74.00	LFT
0096	802-07060	SIGN, SHEET, RELOCATE	1.00	EACH
0097	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	34.00	SFT
0098	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	2510.00	LFT
0099	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	2660.00	LFT
0100	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	47.00	LFT

Call: 421

Contract: B -37355-B

Section No.: 1 BRIDGE REPLACEMENT

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0011	202-51330	PRESENT STRUCTURE, REMOVE	1.00 LS
0012	202-91922	STUMP, REMOVE	13.00 EACH
0013	203-02000	EXCAVATION, COMMON	1354.00 CYS
0014	203-02070	BORROW	550.00 CYS
0015	205-09387	TEMPORARY TURBIDITY CURTAIN	90.00 LFT
0016	205-12108	STORMWATER MANAGEMENT BUDGET	10000.00 DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0018	205-12618	SWQCP PREPARATION	1.00 LS
0019	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	112.00 CYS
0020	206-51235	COFFERDAM	1.00 LS
0021	207-08264	SUBGRADE TREATMENT, TYPE II	630.00 SYS
0022	207-09935	SUBGRADE TREATMENT, TYPE IC	2111.00 SYS
0023	211-06467	AGGREGATE FOR END BENT BACKFILL	30.00 CYS
0024	211-09264	STRUCTURE BACKFILL, TYPE 1	1.00 CYS
0025	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	148.00 SYS
0026	302-06464	SUBBASE FOR PCCP	37.00 CYS
0027	303-01180	COMPACTED AGGREGATE NO. 53	790.00 TON
0028	306-08043	MILLING, TRANSITION	273.00 SYS
0029	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	163.00 TON
0030	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	273.00 TON
0031	401-10258	JOINT ADHESIVE, SURFACE	786.00 LFT

0032	401-10259	JOINT ADHESIVE, INTERMEDIATE	674.00	LFT
0033	401-11785	LIQUID ASPHALT SEALANT	786.00	LFT
0034	406-05521	ASPHALT FOR TACK COAT	1973.00	SYS
0035	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	4.00	EACH
0036	601-02241	GUARDRAIL, REMOVE	578.00	LFT
0037	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0038	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	200.00	LFT
0039	602-06729	BARRIER, DELINEATOR	12.00	EACH
0040	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	149.00	SYS
0041	610-07487	HMA FOR APPROACHES, TYPE B	174.00	TON
0042	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00	EACH
0043	611-06498	MAILBOX ASSEMBLY, DOUBLE	5.00	EACH
0044	615-06490	RIGHT-OF-WAY MARKER	13.00	EACH
0045	615-06505	MONUMENT, B	4.00	EACH
0046	615-06515	MONUMENT, D	1.00	EACH
0047	616-06405	RIPRAP, REVETMENT	148.00	TON
0048	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	169.00	SYS
0049	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0050	621-06559	MULCHED SEEDING R	3502.00	SYS
0051	622-52436	SIGN, DO NOT MOW OR SPRAY	4.00	EACH
0052	628-09402	FIELD OFFICE, B	8.00	MOS
0053	628-09409	MOBILE INTERNET SERVICE	8.00	MOS
0054	701-02936	PILE, STEEL H, HP 14 X 89	344.00	LFT
0055	701-06011	DYNAMIC PILE LOAD TEST	4.00	EACH
0056	701-09557	TEST PILE, DYNAMIC, PRODUCTION	241.00	LFT
0057	701-09559	TEST PILE, DYNAMIC, RESTRIKE	4.00	EACH
0058	701-09684	PILE SHOE, HP 14 X 89	10.00	EACH
0059	701-09739	PILE SHOE, HP 12 X 53	8.00	EACH
0060	701-51195	PILE, STEEL H HP 12 X 53	345.00	LFT
0061	702-51005	CONCRETE, A, SUBSTRUCTURE	140.00	CYS
0062	702-51015	CONCRETE, B, FOOTINGS	10.00	CYS
0063	703-06028	REINFORCING BARS	21440.00	LBS
0064	703-06029	REINFORCING BARS, EPOXY COATED	85230.00	LBS
0065	704-51002	CONCRETE, C, SUPERSTRUCTURE	253.00	CYS
0066	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0067	706-51020	RAILING, CONCRETE C	40.00	CYS
0068	707-09865	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 36 IN. X 49 IN.	828.00	LFT

0069	709-51821	SURFACE SEAL	1.00	LS
0070	713-04331	TEMPORARY CAUSEWAY	1.00	LS
0071	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	35.00	LFT
0072	715-05407	PIPE, END BENT DRAIN, 6 IN.	80.00	LFT
0073	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00	EACH
0074	724-12103	PRE-COMPRESSED FOAM JOINT	55.00	LFT
0075	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00	EACH
0076	801-06625	DETOUR ROUTE MARKER ASSEMBLY	27.00	EACH
0077	801-06640	CONSTRUCTION SIGN, A	7.00	EACH
0078	801-06645	CONSTRUCTION SIGN, B	6.00	EACH
0079	801-06775	MAINTAINING TRAFFIC	1.00	LS
0080	801-07118	BARRICADE, III-A	48.00	LFT
0081	801-07119	BARRICADE, III-B	72.00	LFT
0082	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	1864.00	LFT
0083	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	1864.00	LFT
0084	808-12032	GROOVING FOR PAVEMENT MARKINGS	3728.00	LFT

Call: 431

Contract: B -37710-A

Section No.: 1 BRIDGE REPLACEMENT

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0012	202-01261	TESTING FOR ASBESTOS	1.00 EACH
0013	202-06542	RELOCATE	1.00 EACH
0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0015	203-02000	EXCAVATION, COMMON	1934.00 CYS
0016	203-02010	EXCAVATION, ROCK	190.00 CYS
0017	203-02070	BORROW	2620.00 CYS
0018	203-51223	EXCAVATION, WATERWAY	602.00 CYS
0019	204-02290	SETTLEMENT PLATE	2.00 EACH
0020	204-11633	VIBRATING WIRE PIEZOMETER	2.00 EACH
0021	205-12108	STORMWATER MANAGEMENT BUDGET	39257.00 DOL
0022	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0023	205-12618	SWQCP PREPARATION	1.00 LS
0024	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	101.00 CYS
0025	207-08264	SUBGRADE TREATMENT, TYPE II	85.00 SYS
0026	207-09895	SUBGRADE TREATMENT, TYPE V	509.00 SYS
0027	207-09935	SUBGRADE TREATMENT, TYPE IC	2066.00 SYS
0028	211-06467	AGGREGATE FOR END BENT BACKFILL	37.30 CYS
0029	211-09264	STRUCTURE BACKFILL, TYPE 1	19.00 CYS
0030	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	234.00 SYS
0031	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	128.00 SYS

0032	301-12232	COMPACTED AGGREGATE NO. 5	72.00	CYS
0033	301-12233	COMPACTED AGGREGATE NO. 8	1411.00	CYS
0034	301-12234	COMPACTED AGGREGATE NO. 53	286.00	CYS
0035	302-06464	SUBBASE FOR PCCP	32.00	CYS
0036	306-08034	MILLING, ASPHALT, 1 1/2 IN.	454.00	SYS
0037	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	221.00	TON
0038	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	412.00	TON
0039	401-10258	JOINT ADHESIVE, SURFACE	2070.00	LFT
0040	401-10259	JOINT ADHESIVE, INTERMEDIATE	1920.00	LFT
0041	401-11785	LIQUID ASPHALT SEALANT	2070.00	LFT
0042	406-05521	ASPHALT FOR TACK COAT	2376.00	SYS
0043	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	37.50	LFT
0044	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	2.00	EACH
0045	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	1.00	EACH
0046	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	1.00	EACH
0047	601-94689	GUARDRAIL, END TREATMENT, OS	2.00	EACH
0048	602-06729	BARRIER, DELINEATOR	18.00	EACH
0049	603-03692	FENCE WOOD	118.00	LFT
0050	604-05528	HMA FOR SIDEWALK	68.00	TON
0051	604-06070	SIDEWALK, CONCRETE	22.00	SYS
0052	608-05741	WICK DRAIN	45056.00	LFT
0053	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	131.70	SYS
0054	610-07487	HMA FOR APPROACHES, TYPE B	16.00	TON
0055	615-06490	RIGHT-OF-WAY MARKER	16.00	EACH
0056	615-06505	MONUMENT, B	5.00	EACH
0057	616-05688	RIPRAP, CLASS 1	1459.00	TON
0058	616-06405	RIPRAP, REVETMENT	220.00	TON
0059	616-06451	RIPRAP, UNIFORM	79.00	TON
0060	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	2130.00	SYS
0061	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0062	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0063	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0064	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0065	621-02770	EROSION CONTROL BLANKET	3593.00	SYS
0066	621-06545	FERTILIZER	0.10	TON
0067	621-06559	MULCHED SEEDING R	1788.00	SYS
0068	621-06560	MULCHED SEEDING U	2666.00	SYS



0069	621-06567	WATER	4.30 kGAL
0070	621-06574	SODDING	408.00 SYS
0071	621-06575	SODDING, NURSERY	131.00 SYS
0072	628-09402	FIELD OFFICE, B	20.00 MOS
0073	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0074	628-11977	COMPUTER SYSTEM	1.00 EACH
0075	701-09558	TEST PILE, INDICATOR, PRODUCTION	106.00 LFT
0076	701-09560	TEST PILE, INDICATOR, RESTRIKE	2.00 EACH
0077	701-09683	PILE SHOE, HP 12 X 74	8.00 EACH
0078	701-95780	PILE, STEEL H, HP 12 X 74	258.00 LFT
0079	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	7.00 EACH
0080	702-51005	CONCRETE, A, SUBSTRUCTURE	87.30 CYS
0081	702-92857	CONCRETE, C, SUBSTRUCTURE	27.10 CYS
0082	703-06028	REINFORCING BARS	18967.00 LBS
0083	703-06029	REINFORCING BARS, EPOXY COATED	101130.00 LBS
0084	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	28.00 EACH
0085	704-51002	CONCRETE, C, SUPERSTRUCTURE	265.00 CYS
0086	706-09960	RAILING, CONCRETE FC	603.00 LFT
0087	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00 EACH
0088	709-51821	SURFACE SEAL	1.00 LS
0089	709-51821	SURFACE SEAL	1.00 LS
0090	711-12147	SUPERSTRUCTURE INSTALLATION	1.00 LS
0091	711-51035	STRUCTURAL STEEL	18879.00 LBS
0092	711-51038	STRUCTURAL STEEL	1.00 LS
0093	712-94080	TIMBER DECK	1332.00 SFT
0094	715-05123	PIPE, TYPE 1, CIRCULAR, 24 IN.	28.00 LFT
0095	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	46.00 LFT
0096	715-05407	PIPE, END BENT DRAIN, 6 IN.	70.00 LFT
0097	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	7.00 EACH
0098	715-46020	PIPE END SECTION, DIAMETER 24 IN.	4.00 EACH
0099	718-12307	GEOTEXTILE FOR UNDERDRAIN, TYPE 2A	401.00 SYS
0100	728-11672	DRILLED SHAFT EXPLORATORY CORE	201.00 LFT
0101	728-11674	DRILLED SHAFT 48 IN. DIAMETER	109.00 LFT
0102	728-11789	DRILLED SHAFT 42 IN. DIAMETER	32.00 LFT
0103	731-93947	LEVELING PAD, CONCRETE	130.00 LFT
0104	732-11810	MODULAR BLOCK WALL	2827.00 SFT
0105	732-11811	MODULAR BLOCK WALL ERECTION	2827.00 SFT

0106	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00 EACH
0107	801-06625	DETOUR ROUTE MARKER ASSEMBLY	18.00 EACH
0108	801-06640	CONSTRUCTION SIGN, A	12.00 EACH
0109	801-06775	MAINTAINING TRAFFIC	1.00 LS
0110	801-07118	BARRICADE, III-A	48.00 LFT
0111	801-07119	BARRICADE, III-B	48.00 LFT
0112	801-07120	BARRICADE, III, PERMANENT	32.00 LFT
0113	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	103.50 LFT
0114	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	53.80 SFT
0115	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1974.00 LFT
0116	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1730.00 LFT
0117	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	43.00 LFT

Call: 441

Contract: B -39320-A

Section No.: 1

REPLACE SUPERSTRUCTURE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	202-02240	PAVEMENT REMOVAL	1024.00 SYS
0012	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0013	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0014	202-51368	SLOPEWALL, REMOVE	410.00 SYS
0015	202-96128	GUTTER, CONCRETE, REMOVE	700.00 LFT
0016	203-02000	EXCAVATION, COMMON	780.00 CYS
0017	203-08607	LINEAR GRADING	970.00 LFT
0018	205-12108	STORMWATER MANAGEMENT BUDGET	15650.00 DOL
0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0020	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	40.00 CYS
0021	207-09935	SUBGRADE TREATMENT, TYPE IC	1735.00 SYS
0022	211-06467	AGGREGATE FOR END BENT BACKFILL	40.00 CYS
0023	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	1735.00 SYS
0024	301-12234	COMPACTED AGGREGATE NO. 53	220.00 CYS
0025	302-06464	SUBBASE FOR PCCP	62.00 CYS
0026	303-01180	COMPACTED AGGREGATE NO. 53	474.00 TON
0027	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	108.00 TON
0028	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	180.00 TON
0029	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	792.00 TON
0030	401-10258	JOINT ADHESIVE, SURFACE	960.00 LFT
0031	401-10259	JOINT ADHESIVE, INTERMEDIATE	960.00 LFT

0032	401-11785	LIQUID ASPHALT SEALANT	960.00	LFT
0033	406-05521	ASPHALT FOR TACK COAT	2617.00	SYS
0034	503-12477	TERMINAL JOINT, TYPE HMA	74.00	LFT
0035	601-02241	GUARDRAIL, REMOVE	1081.25	LFT
0036	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	381.75	LFT
0037	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	2.00	EACH
0038	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	8.00	EACH
0039	601-94689	GUARDRAIL, END TREATMENT, OS	6.00	EACH
0040	602-06729	BARRIER, DELINEATOR	14.00	EACH
0041	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	245.60	SYS
0042	615-06505	MONUMENT, B	2.00	EACH
0043	616-06405	RIPRAP, REVETMENT	80.00	TON
0044	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	150.00	SYS
0045	616-51367	SLOPEWALL, CONCRETE, 4 IN.	410.00	SYS
0046	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0047	621-06559	MULCHED SEEDING R	1250.00	SYS
0048	621-06567	WATER	1.00	kGAL
0049	621-06574	SODDING	50.00	SYS
0050	628-09402	FIELD OFFICE, B	21.00	MOS
0051	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0052	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0053	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0054	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	21.00	MOS
0055	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0056	628-11977	COMPUTER SYSTEM	1.00	EACH
0057	702-51005	CONCRETE, A, SUBSTRUCTURE	46.70	CYS
0058	702-51863	FIELD DRILLED HOLE IN CONCRETE	194.00	EACH
0059	702-92857	CONCRETE, C, SUBSTRUCTURE	46.70	CYS
0060	703-06028	REINFORCING BARS	7252.00	LBS
0061	703-06029	REINFORCING BARS, EPOXY COATED	134225.00	LBS
0062	703-08247	EMBEDDED GALVANIC ANODE	150.00	EACH
0063	703-96512	BAR SPLICE	150.00	EACH
0064	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	42.00	EACH
0065	704-51002	CONCRETE, C, SUPERSTRUCTURE	316.60	CYS
0066	706-09960	RAILING, CONCRETE FC	610.00	LFT
0067	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	8.00	EACH
0068	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS

0069	709-51821	SURFACE SEAL	1.00	LS
0070	709-51821	SURFACE SEAL	1.00	LS
0071	710-09158	PATCHING CONCRETE STRUCTURES	85.00	SFT
0072	711-51038	STRUCTURAL STEEL	1.00	LS
0073	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	50.00	LFT
0074	715-05407	PIPE, END BENT DRAIN, 6 IN.	128.00	LFT
0075	718-06528	OUTLET PROTECTOR, 1	2.00	EACH
0076	718-12309	GEOTEXTILE FOR UNDERDRAIN, TYPE 3	100.00	SYS
0077	720-02442	PIPE PLUG EXISTING	6.00	EACH
0078	720-44296	INLET, CAP	8.00	EACH
0079	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	50.00	SFT
0080	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	60.00	SFT
0081	724-12103	PRE-COMPRESSED FOAM JOINT	146.00	LFT
0082	724-12420	BRIDGE JOINT NOSING	100.00	SFT
0083	724-12461	CONCRETE FOR PATCHING STRUCTURAL EXPANSION JOINT	34.00	SFT
0084	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	369.00	SYS
0085	801-03290	CONSTRUCTION SIGN, C	2.00	EACH
0086	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00	EACH
0087	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	5680.00	LFT
0088	801-06625	DETOUR ROUTE MARKER ASSEMBLY	81.00	EACH
0089	801-06640	CONSTRUCTION SIGN, A	115.00	EACH
0090	801-06645	CONSTRUCTION SIGN, B	22.00	EACH
0091	801-06710	FLASHING ARROW SIGN	72.00	DAY
0092	801-06775	MAINTAINING TRAFFIC	1.00	LS
0093	801-07118	BARRICADE, III-A	144.00	LFT
0094	801-07119	BARRICADE, III-B	48.00	LFT
0095	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	1040.00	LFT
0096	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	720.00	LFT
0097	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0098	802-91122	SIGN GROUND MOUNTED RESET	1.00	EACH
0099	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1450.00	LFT
0100	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1450.00	LFT
0101	808-06716	LINE, REMOVE	420.00	LFT
0102	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	725.00	LFT
0103	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	25.00	EACH
0104	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	43.00	EACH
0105	809-08372	ROADWAY WEATHER INFORMATION SYSTEM	1.00	EACH

Call: 451

Contract: B -39532-A

Section No.: 1 BRIDGE MAINTENANCE AND REPAIR

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-02240	PAVEMENT REMOVAL	232.00	SYS
0012	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0013	202-52710	SIDEWALK CONCRETE, REMOVE	125.00	SYS
0014	203-02000	EXCAVATION, COMMON	230.00	CYS
0015	205-12108	STORMWATER MANAGEMENT BUDGET	4525.00	DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	205-12618	SWQCP PREPARATION	1.00	LS
0018	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	80.00	CYS
0019	206-51235	COFFERDAM	1.00	LS
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	420.00	SYS
0021	211-06467	AGGREGATE FOR END BENT BACKFILL	34.00	CYS
0022	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	420.00	SYS
0023	301-12234	COMPACTED AGGREGATE NO. 53	30.00	CYS
0024	302-06464	SUBBASE FOR PCCP	58.00	CYS
0025	304-12623	HMA PATCHING FULL DEPTH TYPE B	145.00	TON
0026	306-08034	MILLING, ASPHALT, 1 1/2 IN.	165.00	SYS
0027	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	15.00	TON
0028	401-10258	JOINT ADHESIVE, SURFACE	120.00	LFT
0029	401-11785	LIQUID ASPHALT SEALANT	120.00	LFT
0030	406-05521	ASPHALT FOR TACK COAT	510.00	SYS
0031	503-12477	TERMINAL JOINT, TYPE HMA	52.00	LFT

0032	601-02241	GUARDRAIL, REMOVE	45.00	LFT
0033	604-06070	SIDEWALK, CONCRETE	125.00	SYS
0034	605-06120	CURB, CONCRETE	240.00	LFT
0035	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	223.00	SYS
0036	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0037	621-06560	MULCHED SEEDING U	950.00	SYS
0038	628-09401	FIELD OFFICE, A	6.00	MOS
0039	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	8.00	EACH
0040	702-51005	CONCRETE, A, SUBSTRUCTURE	8.30	CYS
0041	702-51863	FIELD DRILLED HOLE IN CONCRETE	252.00	EACH
0042	703-06029	REINFORCING BARS, EPOXY COATED	156440.00	LBS
0043	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	38.00	EACH
0044	704-51002	CONCRETE, C, SUPERSTRUCTURE	390.40	CYS
0045	706-06372	CONCRETE BRIDGE RAILING TRANSITION, TTX	4.00	EACH
0046	706-09965	RAILING, CONCRETE TX	525.00	LFT
0047	709-07110	SEAL COAT GRAFFITI RESISTANT	1600.00	SFT
0048	709-51821	SURFACE SEAL	1.00	LS
0049	710-09158	PATCHING CONCRETE STRUCTURES	100.00	SFT
0050	711-51038	STRUCTURAL STEEL	1.00	LS
0051	715-05407	PIPE, END BENT DRAIN, 6 IN.	120.00	LFT
0052	718-12307	GEOTEXTILE FOR UNDERDRAIN, TYPE 2A	90.00	SYS
0053	724-12103	PRE-COMPRESSED FOAM JOINT	72.00	LFT
0054	801-03290	CONSTRUCTION SIGN, C	4.00	EACH
0055	801-03291	CONSTRUCTION SIGN, D	6.00	EACH
0056	801-04308	ROAD CLOSURE SIGN ASSEMBLY	3.00	EACH
0057	801-06625	DETOUR ROUTE MARKER ASSEMBLY	17.00	EACH
0058	801-06640	CONSTRUCTION SIGN, A	4.00	EACH
0059	801-06645	CONSTRUCTION SIGN, B	19.00	EACH
0060	801-06775	MAINTAINING TRAFFIC	1.00	LS
0061	801-06775	MAINTAINING TRAFFIC	1.00	LS
0062	801-07118	BARRICADE, III-A	96.00	LFT
0063	801-07119	BARRICADE, III-B	48.00	LFT
0064	802-91122	SIGN GROUND MOUNTED RESET	2.00	EACH
0065	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	170.00	LFT
0066	807-01653	WIRE, NO. 4 COPPER, IN CONDUIT, BRIDGE 1/C	170.00	LFT
0067	807-04866	LUMINAIRE	2.00	EACH
0068	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	876.00	LFT

Call: 461

Contract: B -39741-A

Section No.: 1

BRIDGE REHABILITATION OR REPAIR

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	111-04714	STOCKPILED MATERIAL	2800.00 EACH
0011	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0012	202-02240	PAVEMENT REMOVAL	808.00 SYS
0013	202-02279	CURB AND GUTTER, REMOVE	466.00 LFT
0014	202-03135	REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	2167.00 SFT
0015	202-03729	REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	426.00 LFT
0016	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0017	202-86946	HANDHOLE, REMOVE	3.00 EACH
0018	202-90277	DETECTOR HOUSING, REMOVE	3.00 EACH
0019	202-96328	FOUNDATION, STREET LIGHT, REMOVE	1.00 EACH
0020	203-02000	EXCAVATION, COMMON	50.00 CYS
0021	203-02070	BORROW	745.00 CYS
0022	205-12108	STORMWATER MANAGEMENT BUDGET	24455.00 DOL
0023	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0024	205-12618	SWQCP PREPARATION	1.00 LS
0025	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	88.00 CYS
0026	206-51235	COFFERDAM	1.00 LS
0027	207-08264	SUBGRADE TREATMENT, TYPE II	327.00 SYS
0028	207-09935	SUBGRADE TREATMENT, TYPE IC	842.00 SYS
0029	211-06467	AGGREGATE FOR END BENT BACKFILL	100.00 CYS
0030	211-09268	STRUCTURE BACKFILL, TYPE 5	2.00 CYS
0031	214-11796	GEOGRID, TYPE IB	105.00 SYS



0032	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	1200.00	SYS
0033	301-12232	COMPACTED AGGREGATE NO. 5	54.00	CYS
0034	301-12234	COMPACTED AGGREGATE NO. 53	135.00	CYS
0035	302-06464	SUBBASE FOR PCCP	184.00	CYS
0036	304-07493	WIDENING WITH HMA, TYPE B	35.00	TON
0037	306-08037	MILLING, ASPHALT, 3 IN.	951.00	SYS
0038	401-10258	JOINT ADHESIVE, SURFACE	962.00	LFT
0039	401-11785	LIQUID ASPHALT SEALANT	962.00	LFT
0040	406-05521	ASPHALT FOR TACK COAT	951.00	SYS
0041	503-03489	RETROFITTED TIE BARS	109.00	EACH
0042	503-05240	D-1 CONTRACTION JOINT	107.00	LFT
0043	503-12476	JOINTED REINFORCED CONCRETE PAVEMENT 12 IN.	478.00	SYS
0044	503-12478	TERMINAL JOINT, TYPE PCCP	108.00	LFT
0045	503-12479	EXPANSION JOINT WITH LOAD TRANSFER	108.00	LFT
0046	601-01115	GUARDRAIL, W-BEAM, 1 FT 6.75 IN. SPACING	37.50	LFT
0047	601-02103	GUARDRAIL, W-BEAM, SHOP CURVED, 6 FT 3 IN. SPACING	25.00	LFT
0048	601-02241	GUARDRAIL, REMOVE	463.00	LFT
0049	601-09146	IMPACT ATTENUATOR, CR1-W1, TL-2	1.00	EACH
0050	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	137.50	LFT
0051	601-12283	GUARDRAIL, MGS W-BEAM, 1 FT 6.75 IN SPACING	31.25	LFT
0052	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	2.00	EACH
0053	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	2.00	EACH
0054	601-94689	GUARDRAIL, END TREATMENT, OS	2.00	EACH
0055	604-06070	SIDEWALK, CONCRETE	254.00	SYS
0056	604-08086	CURB RAMP, CONCRETE	34.00	SYS
0057	604-12083	DETECTABLE WARNING SURFACES	7.00	SYS
0058	605-06090	CURB, INTEGRAL CONCRETE	146.00	LFT
0059	605-06140	CURB AND GUTTER, CONCRETE	306.00	LFT
0060	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	328.80	SYS
0061	610-07487	HMA FOR APPROACHES, TYPE B	216.00	TON
0062	616-05688	RIPRAP, CLASS 1	2806.00	TON
0063	616-06405	RIPRAP, REVETMENT	24.00	TON
0064	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	2276.00	SYS
0065	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.00	EACH
0066	621-02770	EROSION CONTROL BLANKET	1008.00	SYS
0067	621-03909	SEED MIXTURE, NATIVE	15.00	LBS
0068	621-06545	FERTILIZER	1.00	TON

0069	621-06554	SEED MIXTURE U	170.00	LBS
0070	621-06554	SEED MIXTURE U	10.00	LBS
0071	621-06565	MULCHING MATERIAL	3.00	TON
0072	622-05640	PLANT, DECIDUOUS SHRUB, 24 TO 36 IN.	30.00	EACH
0073	622-05649	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN.	152.00	EACH
0074	622-52436	SIGN, DO NOT MOW OR SPRAY	6.00	EACH
0075	628-09402	FIELD OFFICE, B	24.00	MOS
0076	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0077	702-04325	TEMPORARY SHORING	1.00	LS
0078	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	24.00	EACH
0079	702-51005	CONCRETE, A, SUBSTRUCTURE	148.00	CYS
0080	702-51863	FIELD DRILLED HOLE IN CONCRETE	926.00	EACH
0081	703-01540	THREADED TIE BAR ASSEMBLY	88.00	EACH
0082	703-06028	REINFORCING BARS	4633.00	LBS
0083	703-06029	REINFORCING BARS, EPOXY COATED	380272.00	LBS
0084	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	1572.00	EACH
0085	704-51002	CONCRETE, C, SUPERSTRUCTURE	1126.40	CYS
0086	706-06353	CONCRETE BRIDGE RAILING TRANSITION, TPS-1	4.00	EACH
0087	706-11418	RAILING, STEEL PS-1	903.00	LFT
0088	706-11604	RAILING, CONCRETE PS-1	56.80	CYS
0089	709-51821	SURFACE SEAL	1.00	LS
0090	710-09158	PATCHING CONCRETE STRUCTURES	400.00	SFT
0091	711-51038	STRUCTURAL STEEL	1.00	LS
0092	711-51038	STRUCTURAL STEEL	1.00	LS
0093	713-04331	TEMPORARY CAUSEWAY	1.00	LS
0094	715-05203	PIPE, TYPE 4, CIRCULAR, 4 IN.	21.00	LFT
0095	715-05407	PIPE, END BENT DRAIN, 6 IN.	166.00	LFT
0096	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0097	720-44000	CASTING, ADJUST TO GRADE	1.00	EACH
0098	724-03855	EXPANSION JOINT SLIDING PLATE	19.00	LFT
0099	724-12103	PRE-COMPRESSED FOAM JOINT	130.00	LFT
0100	801-03290	CONSTRUCTION SIGN, C	12.00	EACH
0101	801-03291	CONSTRUCTION SIGN, D	8.00	EACH
0102	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	EACH
0103	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	10249.00	LFT
0104	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	120.00	LFT
0105	801-06539	TEMPORARY TRAFFIC SIGNAL INSTALLATION, MAINTAIN	1.00	LS

0106	801-06625	DETOUR ROUTE MARKER ASSEMBLY	22.00 EACH
0107	801-06640	CONSTRUCTION SIGN, A	31.00 EACH
0108	801-06645	CONSTRUCTION SIGN, B	9.00 EACH
0109	801-06710	FLASHING ARROW SIGN	240.00 DAY
0110	801-06775	MAINTAINING TRAFFIC	1.00 LS
0111	801-06775	MAINTAINING TRAFFIC	1.00 LS
0112	801-07118	BARRICADE, III-A	72.00 LFT
0113	801-07119	BARRICADE, III-B	48.00 LFT
0114	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	680.00 LFT
0115	801-94295	SIGNAL HEAD RELOCATE	4.00 EACH
0116	802-07060	SIGN, SHEET, RELOCATE	2.00 EACH
0117	802-91122	SIGN GROUND MOUNTED RESET	6.00 EACH
0118	805-01842	HANDHOLE SIGNAL TYPE 1	4.00 EACH
0119	805-01843	SIGNAL HANDHOLE ADJUST TO GRADE	2.00 EACH
0120	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	1681.00 LFT
0121	805-02373	SIGNAL CABLE, INTERCONNECT, FIBER OPTIC	919.00 LFT
0122	805-04602	CONTROLLER, REWIRE	2.00 EACH
0123	805-11817	PEDESTRIAN PUSH BUTTON, APS	2.00 EACH
0124	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	1140.00 LFT
0125	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	169.00 LFT
0126	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	110.00 LFT
0127	805-78785	SIGNAL DETECTOR HOUSING	1.00 EACH
0128	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	284.00 LFT
0129	807-04744	LIGHTING	1.00 LS
0130	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	160.00 LFT
0131	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	120.00 LFT
0132	808-06716	LINE, REMOVE	1467.00 LFT
0133	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	280.00 LFT
0134	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	2348.00 LFT
0135	808-10099	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 24 IN.	186.00 LFT
0136	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	804.00 LFT
0137	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	54.00 LFT
0138	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	2.00 EACH
0139	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	1.00 EACH
0140	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	12.00 EACH
0141	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	12.00 EACH

Call: 471

Contract: B -39761-A

Section No.: 1

REPLACE SUPERSTRUCTURE

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0011	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
	0012	203-02000	EXCAVATION, COMMON	431.00	CYS
	0013	203-08607	LINEAR GRADING	802.00	LFT
	0014	205-12108	STORMWATER MANAGEMENT BUDGET	10584.00	DOL
	0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0016	205-12618	SWQCP PREPARATION	1.00	LS
	0017	206-51220	EXCAVATION, WET	43.00	CYS
	0018	206-51225	EXCAVATION, DRY	43.00	CYS
	0019	207-09935	SUBGRADE TREATMENT, TYPE IC	410.00	SYS
	0020	211-02050	B BORROW	51.00	CYS
	0021	211-09267	STRUCTURE BACKFILL, TYPE 4	11.00	CYS
	0022	214-12236	GEOTEXTILE FOR PAVEMENT TYPE 1A	104.00	SYS
	0023	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	181.00	SYS
	0024	301-12234	COMPACTED AGGREGATE NO. 53	78.00	CYS
	0025	302-06464	SUBBASE FOR PCCP	45.00	CYS
	0026	304-07493	WIDENING WITH HMA, TYPE B	95.00	TON
	0027	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	30.00	TON
	0028	306-08034	MILLING, ASPHALT, 1 1/2 IN.	110.00	SYS
	0029	306-08041	MILLING, PCCP	155.00	SYS
	0030	306-08042	MILLING, SCARIFICATION	220.00	SYS
	0031	306-08043	MILLING, TRANSITION	440.00	SYS

0032	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	89.00 TON
0033	401-07372	QC/QA-HMA, 3, 64, INTERMEDIATE, 12.5 mm	73.00 TON
0034	401-10258	JOINT ADHESIVE, SURFACE	900.00 LFT
0035	401-10259	JOINT ADHESIVE, INTERMEDIATE	810.00 LFT
0036	401-11785	LIQUID ASPHALT SEALANT	1710.00 LFT
0037	406-05521	ASPHALT FOR TACK COAT	2043.00 SYS
0038	601-02241	GUARDRAIL, REMOVE	268.00 LFT
0039	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	406.00 LFT
0040	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00 EACH
0041	601-94689	GUARDRAIL, END TREATMENT, OS	4.00 EACH
0042	602-06729	BARRIER, DELINEATOR	4.00 EACH
0043	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	270.00 LFT
0044	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	181.00 SYS
0045	615-06505	MONUMENT, B	2.00 EACH
0046	616-05688	RIPRAP, CLASS 1	426.00 TON
0047	616-06405	RIPRAP, REVETMENT	38.00 TON
0048	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	515.00 SYS
0049	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00 EACH
0050	621-02770	EROSION CONTROL BLANKET	518.00 SYS
0051	621-06553	SEED MIXTURE R	22.00 LBS
0052	621-06574	SODDING	51.00 SYS
0053	628-09403	FIELD OFFICE, C	11.00 MOS
0054	628-11730	CELLULAR TELEPHONE, TYPE B	1.00 EACH
0055	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00 DOL
0056	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	11.00 MOS
0057	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	4.00 EACH
0058	702-51005	CONCRETE, A, SUBSTRUCTURE	17.00 CYS
0059	702-51863	FIELD DRILLED HOLE IN CONCRETE	20.00 EACH
0060	703-06029	REINFORCING BARS, EPOXY COATED	75367.00 LBS
0061	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	34.00 EACH
0062	704-51002	CONCRETE, C, SUPERSTRUCTURE	128.00 CYS
0063	706-09960	RAILING, CONCRETE FC	158.00 LFT
0064	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00 EACH
0065	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00 LS
0066	709-51821	SURFACE SEAL	1.00 LS
0067	709-51821	SURFACE SEAL	1.00 LS
0068	710-09158	PATCHING CONCRETE STRUCTURES	500.00 SFT

0069	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	4.00	EACH
0070	722-01066	HYDRODEMOLITION	406.00	SYS
0071	722-12380	BRIDGE DECK OVERLAY, BUDGET	11025.00	DOL
0072	722-12382	TRANSVERSE GROOVING	406.00	SYS
0073	722-12463	BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY	255.00	SYS
0074	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	735.00	SFT
0075	722-51874	OVERLAY DAM	67.00	SFT
0076	801-04308	ROAD CLOSURE SIGN ASSEMBLY	22.00	EACH
0077	801-06625	DETOUR ROUTE MARKER ASSEMBLY	74.00	EACH
0078	801-06640	CONSTRUCTION SIGN, A	22.00	EACH
0079	801-06775	MAINTAINING TRAFFIC	1.00	LS
0080	801-07118	BARRICADE, III-A	144.00	LFT
0081	801-07119	BARRICADE, III-B	264.00	LFT
0082	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	135.00	LFT
0083	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1074.00	LFT
0084	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	7.00	EACH
0085	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	7.00	EACH

Call: 471

Contract: B -39761-A

Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED CONCRETE

**Line**

Item No	Item Code	Description	Quantity	Unit
0086	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	406.00	SYS

Call: 471

Contract: B -39761-A

Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED

**Line**

Item No	Item Code	Description	Quantity	Unit
0087	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	406.00	SYS

Call: 481

Contract: B -39895-A

Section No.: 1 BRIDGE REPLACEMENT

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0011	202-51330	PRESENT STRUCTURE, REMOVE	1.00 LS
0012	203-02000	EXCAVATION, COMMON	1710.00 CYS
0013	205-12108	STORMWATER MANAGEMENT BUDGET	17400.00 DOL
0014	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0015	205-12618	SWQCP PREPARATION	1.00 LS
0016	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	105.00 CYS
0017	207-08264	SUBGRADE TREATMENT, TYPE II	70.00 SYS
0018	207-12635	SUBGRADE TREATMENT, TYPE IBC	5715.00 SYS
0019	211-02050	B BORROW	145.00 CYS
0020	211-06467	AGGREGATE FOR END BENT BACKFILL	24.00 CYS
0021	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	166.00 SYS
0022	301-12234	COMPACTED AGGREGATE NO. 53	13.00 CYS
0023	302-06464	SUBBASE FOR PCCP	42.00 CYS
0024	303-01180	COMPACTED AGGREGATE NO. 53	620.00 TON
0025	401-06264	PROFILOGRAPH, HMA	1.00 LS
0026	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	398.00 TON
0027	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	665.00 TON
0028	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	2295.00 TON
0029	401-10258	JOINT ADHESIVE, SURFACE	3555.00 LFT
0030	401-10259	JOINT ADHESIVE, INTERMEDIATE	3555.00 LFT
0031	401-11785	LIQUID ASPHALT SEALANT	3555.00 LFT

0032	406-05521	ASPHALT FOR TACK COAT	14370.00	SYS
0033	601-09238	HAND DIG GUARDRAIL POST HOLES	6.00	EACH
0034	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	750.00	LFT
0035	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00	EACH
0036	601-94689	GUARDRAIL, END TREATMENT, OS	6.00	EACH
0037	602-06729	BARRIER, DELINEATOR	4.00	EACH
0038	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	166.00	SYS
0039	611-06497	MAILBOX ASSEMBLY, SINGLE	2.00	EACH
0040	615-06505	MONUMENT, B	2.00	EACH
0041	615-06510	MONUMENT, C	1.00	EACH
0042	616-05689	RIPRAP, CLASS 2	795.00	TON
0043	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	749.00	SYS
0044	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0045	621-03787	SEED MIXTURE D	1.00	LBS
0046	621-06545	FERTILIZER	1.00	TON
0047	621-06553	SEED MIXTURE R	275.00	LBS
0048	621-06565	MULCHING MATERIAL	3.00	TON
0049	621-06567	WATER	1.00	KGAL
0050	621-06574	SODDING	24.00	SYS
0051	628-09403	FIELD OFFICE, C	12.00	MOS
0052	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0053	701-02938	CORED HOLE IN ROCK, 24 IN	66.00	LFT
0054	701-09739	PILE SHOE, HP 12 X 53	12.00	EACH
0055	701-51195	PILE, STEEL H HP 12 X 53	240.00	LFT
0056	703-01540	THREADED TIE BAR ASSEMBLY	40.00	EACH
0057	703-06029	REINFORCING BARS, EPOXY COATED	28573.00	LBS
0058	704-51002	CONCRETE, C, SUPERSTRUCTURE	90.20	CYS
0059	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0060	706-51020	RAILING, CONCRETE C	9.50	CYS
0061	707-11443	STRUCTURAL MEMBER, CONCRETE, BOX BEAM, 17 IN. X 36 IN.	297.00	LFT
0062	709-51821	SURFACE SEAL	1.00	LS
0063	715-05407	PIPE, END BENT DRAIN, 6 IN.	100.00	LFT
0064	718-12307	GEOTEXTILE FOR UNDERDRAIN, TYPE 2A	76.00	SYS
0065	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0066	801-06625	DETOUR ROUTE MARKER ASSEMBLY	32.00	EACH
0067	801-06640	CONSTRUCTION SIGN, A	19.00	EACH
0068	801-06775	MAINTAINING TRAFFIC	1.00	LS



0069	801-07118	BARRICADE, III-A	96.00	LFT
0070	801-07119	BARRICADE, III-B	48.00	LFT
0071	802-04893	REFERENCE POST	2.00	EACH
0072	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	84.00	LFT
0073	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	13.00	SFT
0074	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	2550.00	LFT
0075	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	2550.00	LFT

Call: 491

Contract: B -40942-A

Section No.: 1 BRIDGE PAINTING

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0008	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00 LS
0009	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00 LS
0010	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00 LS
0011	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00 LS
0012	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00 LS
0013	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00 LS
0014	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00 LS
0015	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00 LS
0016	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00 LS
0017	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00 LS
0018	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00 LS
0019	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00 LS
0020	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00 LS
0021	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00 LS
0022	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00 LS
0023	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00 LS
0024	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00 LS
0025	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00 LS
0026	622-03672	TREE PROTECTION AND TRIMMING	1.00 LS
0027	628-09403	FIELD OFFICE, C	14.00 MOS
0028	628-11730	CELLULAR TELEPHONE, TYPE B	2.00 EACH
0029	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00 DOL
0030	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	28.00 MOS
0031	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH

0032	709-51821	SURFACE SEAL	1.00	LS
0033	709-51821	SURFACE SEAL	1.00	LS
0034	709-51821	SURFACE SEAL	1.00	LS
0035	709-51821	SURFACE SEAL	1.00	LS
0036	709-51821	SURFACE SEAL	1.00	LS
0037	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	20.00	EACH
0038	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	EACH
0039	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	6780.00	LFT
0040	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	24.00	LFT
0041	801-06539	TEMPORARY TRAFFIC SIGNAL INSTALLATION, MAINTAIN	1.00	LS
0042	801-06625	DETOUR ROUTE MARKER ASSEMBLY	37.00	EACH
0043	801-06640	CONSTRUCTION SIGN, A	179.00	EACH
0044	801-06645	CONSTRUCTION SIGN, B	10.00	EACH
0045	801-06710	FLASHING ARROW SIGN	500.00	DAY
0046	801-06775	MAINTAINING TRAFFIC	1.00	LS
0047	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	4.00	EACH
0048	801-07119	BARRICADE, III-B	48.00	LFT
0049	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	2090.00	LFT
0050	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	1430.00	LFT
0051	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	12.00	EACH
0052	808-06716	LINE, REMOVE	1305.00	LFT
0053	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	480.00	LFT
0054	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	800.00	LFT

Call: 501

Contract: B -40955-A

Section No.: 1

BRIDGE THIN DECK OVERLAY

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0008	203-08607	LINEAR GRADING	260.00 LFT
0009	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00 EACH
0010	621-06559	MULCHED SEEDING R	88.00 SYS
0011	628-09401	FIELD OFFICE, A	6.00 MOS
0012	628-11729	CELLULAR TELEPHONE, TYPE A	2.00 EACH
0013	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00 DOL
0014	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00 DOL
0015	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	12.00 MOS
0016	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0017	709-51821	SURFACE SEAL	1.00 LS
0018	709-51821	SURFACE SEAL	1.00 LS
0019	709-51821	SURFACE SEAL	1.00 LS
0020	709-51821	SURFACE SEAL	1.00 LS
0021	709-51821	SURFACE SEAL	1.00 LS
0022	709-51821	SURFACE SEAL	1.00 LS
0023	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	90.00 SFT
0024	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	409.00 SFT
0025	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	912.00 SYS
0026	801-03291	CONSTRUCTION SIGN, D	4.00 EACH
0027	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	5184.00 LFT
0028	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	46.00 LFT
0029	801-06640	CONSTRUCTION SIGN, A	64.00 EACH
0030	801-06645	CONSTRUCTION SIGN, B	8.00 EACH
0031	801-06710	FLASHING ARROW SIGN	21.00 DAY

0032	801-06775	MAINTAINING TRAFFIC	1.00	LS
0033	801-07118	BARRICADE, III-A	72.00	LFT
0034	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0035	801-12081	PORTABLE SIGNAL	1.00	LS
0036	801-12081	PORTABLE SIGNAL	1.00	LS
0037	801-12081	PORTABLE SIGNAL	1.00	LS
0038	801-12482	DRIVEWAY ASSISTANCE DEVICE	4.00	EACH
0039	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	100.00	LFT
0040	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1671.00	LFT
0041	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1111.00	LFT
0042	808-06716	LINE, REMOVE	1441.00	LFT
0043	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2.00	EACH

Call: 511

Contract: B -41059-A

Section No.: 1

BRIDGE THIN DECK OVERLAY

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	202-02240	PAVEMENT REMOVAL	945.00 SYS
0012	202-96133	PIPE, REMOVE	6.00 LFT
0013	203-02000	EXCAVATION, COMMON	715.00 CYS
0014	205-12108	STORMWATER MANAGEMENT BUDGET	11000.00 DOL
0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0016	207-12498	SUBGRADE TREATMENT, TYPE ID	2345.00 SYS
0017	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	472.00 SYS
0018	301-12234	COMPACTED AGGREGATE NO. 53	182.00 CYS
0019	302-06464	SUBBASE FOR PCCP	190.00 CYS
0020	303-01180	COMPACTED AGGREGATE NO. 53	151.00 TON
0021	304-12627	HMA PATCHING FULL DEPTH TYPE D	120.00 TON
0022	306-08041	MILLING, PCCP	207.00 SYS
0023	306-08041	MILLING, PCCP	259.00 SYS
0024	306-08041	MILLING, PCCP	243.00 SYS
0025	306-08043	MILLING, TRANSITION	3507.00 SYS
0026	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	229.00 TON
0027	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	282.00 TON
0028	401-07357	QC/QA-HMA, 3, 64, INTERMEDIATE, 9.5 mm	64.00 TON
0029	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	201.00 TON
0030	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	125.00 TON
0031	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	325.00 TON

0032	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	497.00	TON
0033	401-10258	JOINT ADHESIVE, SURFACE	5030.00	LFT
0034	401-10259	JOINT ADHESIVE, INTERMEDIATE	3656.00	LFT
0035	401-11785	LIQUID ASPHALT SEALANT	5642.00	LFT
0036	406-05521	ASPHALT FOR TACK COAT	6130.00	SYS
0037	507-08271	JOINTS IN PCCP, FILLED	93.00	LFT
0038	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	752.00	SYS
0039	619-12460	DISPOSAL OF CLEANING WASTE NONHAZARDOUS, BRIDGE NO	1.00	LS
0040	619-95315	CLEAN AND PAINT BEARING ASSEMBLIES, BRIDGE NO.	1.00	LS
0041	628-09402	FIELD OFFICE, B	16.00	MOS
0042	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0043	628-11977	COMPUTER SYSTEM	1.00	EACH
0044	702-51863	FIELD DRILLED HOLE IN CONCRETE	124.00	EACH
0045	703-01540	THREADED TIE BAR ASSEMBLY	212.00	EACH
0046	703-06029	REINFORCING BARS, EPOXY COATED	42944.00	LBS
0047	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	110.00	EACH
0048	704-51002	CONCRETE, C, SUPERSTRUCTURE	1.00	CYS
0049	708-51813	PNEUMATICALLY PLACED MORTAR	396.00	SFT
0050	709-51821	SURFACE SEAL	1.00	LS
0051	709-51821	SURFACE SEAL	1.00	LS
0052	709-51821	SURFACE SEAL	1.00	LS
0053	709-51821	SURFACE SEAL	1.00	LS
0054	709-51821	SURFACE SEAL	1.00	LS
0055	709-51821	SURFACE SEAL	1.00	LS
0056	709-51821	SURFACE SEAL	1.00	LS
0057	709-51821	SURFACE SEAL	1.00	LS
0058	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	3506.00	LFT
0059	715-05407	PIPE, END BENT DRAIN, 6 IN.	12.00	LFT
0060	718-06526	HMA FOR UNDERDRAINS	46.00	TON
0061	718-06528	OUTLET PROTECTOR, 1	8.00	EACH
0062	718-06531	OUTLET PROTECTOR, 3	8.00	EACH
0063	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	2056.00	SYS
0064	718-52610	AGGREGATE FOR UNDERDRAINS	160.00	CYS
0065	720-01355	INLET, CLEAN EXISTING	8.00	EACH
0066	722-01066	HYDRODEMOLITION	1761.00	SYS
0067	722-12380	BRIDGE DECK OVERLAY, BUDGET	25710.00	DOL
0068	722-12382	TRANSVERSE GROOVING	1248.00	SYS

0069	722-12384	BRIDGE DECK OVERLAY, ADDITIONAL SURFACE PREP	346.00	LFT
0070	722-12463	BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY	1761.00	SYS
0071	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	490.00	SFT
0072	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	1133.00	SFT
0073	724-12103	PRE-COMPRESSED FOAM JOINT	437.00	LFT
0074	724-12461	CONCRETE FOR PATCHING STRUCTURAL EXPANSION JOINT	35.00	SFT
0075	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	7695.00	SYS
0076	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	12.00	EACH
0077	801-04308	ROAD CLOSURE SIGN ASSEMBLY	15.00	EACH
0078	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	1204.00	LFT
0079	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	34472.00	LFT
0080	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	70.00	LFT
0081	801-06625	DETOUR ROUTE MARKER ASSEMBLY	73.00	EACH
0082	801-06640	CONSTRUCTION SIGN, A	98.00	EACH
0083	801-06645	CONSTRUCTION SIGN, B	49.00	EACH
0084	801-06710	FLASHING ARROW SIGN	360.00	DAY
0085	801-06775	MAINTAINING TRAFFIC	1.00	LS
0086	801-07118	BARRICADE, III-A	240.00	LFT
0087	801-07119	BARRICADE, III-B	288.00	LFT
0088	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	3264.00	LFT
0089	801-12082	FIXED TEMPORARY SIGNAL	1.00	LS
0090	802-12532	RODENT SCREEN	4.00	EACH
0091	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	143.00	LFT
0092	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	10776.00	LFT
0093	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	6185.00	LFT
0094	808-06716	LINE, REMOVE	17470.00	LFT
0095	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	592.00	LFT
0096	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	511.00	LFT
0097	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	511.00	LFT
0098	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	23.00	EACH

Call: 511

Contract: B -41059-A

Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED CONCRETE

**Line**

Item No	Item Code	Description	Quantity	Unit
0099	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	2004.00	SYS



Call: 511

Contract: B -41059-A

Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED

**Line**

**Item No** **Item Code** **Description**

0100 722-01061 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED

**Quantity** **Unit**

2004.00 SYS

Call: 521

Contract: B -41197-A

Section No.: 1

BRIDGE DECK OVERLAY

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0013	202-02240	PAVEMENT REMOVAL	3407.00 SYS
0014	202-94954	BARRIER WALL, CONCRETE, REMOVE	1126.00 LFT
0015	203-02000	EXCAVATION, COMMON	179.00 CYS
0016	205-12108	STORMWATER MANAGEMENT BUDGET	16050.00 DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0018	205-12618	SWQCP PREPARATION	1.00 LS
0019	206-51235	COFFERDAM	1.00 LS
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	3862.00 SYS
0021	211-02050	B BORROW	16.00 CYS
0022	211-09264	STRUCTURE BACKFILL, TYPE 1	50.00 CYS
0023	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	3862.00 SYS
0024	301-12234	COMPACTED AGGREGATE NO. 53	68.00 CYS
0025	302-06464	SUBBASE FOR PCCP	108.00 CYS
0026	306-08036	MILLING, ASPHALT, 2 IN.	2588.00 SYS
0027	401-07353	QC/QA-HMA, 4, 76, SURFACE, 12.5 mm	286.00 TON
0028	401-10258	JOINT ADHESIVE, SURFACE	2940.00 LFT
0029	401-11785	LIQUID ASPHALT SEALANT	2940.00 LFT
0030	406-05521	ASPHALT FOR TACK COAT	2588.00 SYS
0031	502-03289	QUALITY ASSURANCE ADJUSTMENT	1.00 DOL

0032	502-06331	PCCP, 14 IN.	1925.00	SYS
0033	503-05240	D-1 CONTRACTION JOINT	1599.00	LFT
0034	503-12478	TERMINAL JOINT, TYPE PCCP	267.00	LFT
0035	503-12479	EXPANSION JOINT WITH LOAD TRANSFER	264.00	LFT
0036	503-12505	JOINTED REINFORCED CONCRETE PAVEMENT 14 IN.	1164.00	SYS
0037	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	2.00	EACH
0038	601-02241	GUARDRAIL, REMOVE	150.00	LFT
0039	601-06035	GUARDRAIL, RESET	100.00	LFT
0040	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	100.00	LFT
0041	602-01064	CONCRETE BARRIER	425.00	LFT
0042	602-06729	BARRIER, DELINEATOR	60.00	EACH
0043	602-11938	CONCRETE BARRIER, MODIFIED SECTION	108.50	CYS
0044	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	3100.00	LFT
0045	609-06262	REINFORCED CONCRETE BRIDGE APPROACH, 14 IN.	553.00	SYS
0046	616-05688	RIPRAP, CLASS 1	952.00	TON
0047	616-06405	RIPRAP, REVETMENT	78.00	TON
0048	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	774.00	SYS
0049	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0050	621-06574	SODDING	95.00	SYS
0051	621-12612	SEED MIXTURE FLOODPLAIN	2.00	LBS
0052	628-09403	FIELD OFFICE, C	10.00	MOS
0053	702-51863	FIELD DRILLED HOLE IN CONCRETE	273.00	EACH
0054	703-06029	REINFORCING BARS, EPOXY COATED	44196.00	LBS
0055	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	252.00	EACH
0056	706-11601	RAILING, CONCRETE FT	19.80	CYS
0057	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TFT	1.00	EACH
0058	709-51821	SURFACE SEAL	1.00	LS
0059	709-51821	SURFACE SEAL	1.00	LS
0060	710-09158	PATCHING CONCRETE STRUCTURES	80.00	SFT
0061	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	1612.00	LFT
0062	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	16.00	LFT
0063	718-06528	OUTLET PROTECTOR, 1	8.00	EACH
0064	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	808.00	SYS
0065	718-52610	AGGREGATE FOR UNDERDRAINS	120.00	CYS
0066	720-45141	INLET, H5 MODIFIED	2.00	EACH
0067	722-01066	HYDRODEMOLITION	5482.00	SYS
0068	722-12380	BRIDGE DECK OVERLAY, BUDGET	93930.00	DOL

0069	722-12381	BRIDGE DECK OVERLAY, LMC-VE	5414.00	SYS
0070	722-12382	TRANSVERSE GROOVING	6077.00	SYS
0071	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	5482.00	SYS
0072	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	906.00	SFT
0073	724-11063	STRUCTURAL EXPANSION JOINT, SS, REPLACE	261.00	LFT
0074	724-12103	PRE-COMPRESSED FOAM JOINT	267.00	LFT
0075	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	6.00	EACH
0076	801-04308	ROAD CLOSURE SIGN ASSEMBLY	3.00	EACH
0077	801-06201	TEMPORARY PANEL SIGNS	360.00	SFT
0078	801-06202	TEMPORARY PANEL SIGN SUPPORTS	108.00	LFT
0079	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	43038.00	LFT
0080	801-06625	DETOUR ROUTE MARKER ASSEMBLY	25.00	EACH
0081	801-06640	CONSTRUCTION SIGN, A	45.00	EACH
0082	801-06645	CONSTRUCTION SIGN, B	4.00	EACH
0083	801-06710	FLASHING ARROW SIGN	30.00	DAY
0084	801-06775	MAINTAINING TRAFFIC	1.00	LS
0085	801-07118	BARRICADE, III-A	72.00	LFT
0086	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	3439.00	LFT
0087	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	3.00	EACH
0088	801-12652	QUEUE TRUCK	40.00	DAY
0089	802-03821	SIGN, SHEET, WITH LEGEND,	6.00	EACH
0090	808-06716	LINE, REMOVE	10038.00	LFT
0091	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0092	808-12032	GROOVING FOR PAVEMENT MARKINGS	14475.00	LFT
0093	808-75051	LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	4220.00	LFT
0094	808-75053	LINE, PREFORMED PLASTIC, SOLID, WHITE, 8 IN.	3355.00	LFT
0095	808-75054	LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN.	4815.00	LFT
0096	808-75059	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 4 IN.	2020.00	LFT
0097	808-75510	TRANSVERSE MARKING, PREFORMED PLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	65.00	LFT
0098	808-75994	PRISMATIC REFLECTOR	136.00	EACH
0099	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	25.00	EACH
0100	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	56.00	EACH

Call: 531

Contract: B -41201-A

Section No.: 1 BRIDGE DECK OVERLAY

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	202-51368	SLOPEWALL, REMOVE	7.00 SYS
0011	203-02000	EXCAVATION, COMMON	47.00 CYS
0012	207-12498	SUBGRADE TREATMENT, TYPE ID	65.00 SYS
0013	213-08068	DRILLED HOLE FOR FLOWABLE BACKFILL	3.00 EACH
0014	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	36.00 CYS
0015	306-08034	MILLING, ASPHALT, 1 1/2 IN.	628.00 SYS
0016	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	26.00 TON
0017	401-07329	QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	32.00 TON
0018	401-07399	QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm	9.00 TON
0019	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	36.00 TON
0020	401-10258	JOINT ADHESIVE, SURFACE	228.00 LFT
0021	401-10259	JOINT ADHESIVE, INTERMEDIATE	8.00 LFT
0022	401-11785	LIQUID ASPHALT SEALANT	228.00 LFT
0023	406-05521	ASPHALT FOR TACK COAT	821.00 SYS
0024	507-08272	JOINTS IN PCCP, SAW AND SEAL	185.00 LFT
0025	616-51367	SLOPEWALL, CONCRETE, 4 IN.	7.00 SYS
0026	616-93772	INSPECTION HOLE	3.00 EACH
0027	628-09402	FIELD OFFICE, B	12.00 MOS
0028	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00 EACH
0029	709-51821	SURFACE SEAL	1.00 LS
0030	709-51821	SURFACE SEAL	1.00 LS
0031	710-09158	PATCHING CONCRETE STRUCTURES	47.00 SFT

0032	722-01066	HYDRODEMOLITION	1266.00	SYS
0033	722-12380	BRIDGE DECK OVERLAY, BUDGET	24890.00	DOL
0034	722-12382	TRANSVERSE GROOVING	1266.00	SYS
0035	722-12463	BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY	941.00	SYS
0036	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	325.00	SYS
0037	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	150.00	SFT
0038	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	498.00	SFT
0039	722-51874	OVERLAY DAM	88.00	SFT
0040	727-90308	EPOXY INJECTION, CRACK PREPARATION	150.00	LFT
0041	727-90309	EPOXY INJECTION, EPOXY MATERIAL	10.00	GAL
0042	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0043	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	884.00	SYS
0044	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	624.00	LFT
0045	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	13788.00	LFT
0046	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	24.00	LFT
0047	801-06640	CONSTRUCTION SIGN, A	40.00	EACH
0048	801-06645	CONSTRUCTION SIGN, B	14.00	EACH
0049	801-06710	FLASHING ARROW SIGN	60.00	DAY
0050	801-06775	MAINTAINING TRAFFIC	1.00	LS
0051	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	1.00	EACH
0052	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	1059.00	LFT
0053	801-12081	PORTABLE SIGNAL	1.00	LS
0054	808-06716	LINE, REMOVE	3450.00	LFT
0055	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	1086.00	LFT
0056	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	2032.00	LFT
0057	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	3622.00	LFT
0058	808-12032	GROOVING FOR PAVEMENT MARKINGS	3096.00	LFT
0059	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	25.00	EACH

Call: 531

Contract: B -41201-A

Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED CONCRETE

**Line**

Item No	Item Code	Description	Quantity	Unit
0060	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	1266.00	SYS

Call: 531

Contract: B -41201-A

Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED

**Line**

<b>Item No</b>	<b>Item Code</b>	<b>Description</b>
0061	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED

**Quantity Unit**

1266.00 SYS

Call: 541

Contract: B -41206-A

Section No.: 1 BRIDGE PAINTING

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-02250	TREE 10 IN., REMOVE	2.00 EACH
0011	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0012	202-01502	LIGHT STANDARD, REMOVE	10.00 EACH
0013	202-01845	CONDUIT, REMOVE	840.00 LFT
0014	301-12234	COMPACTED AGGREGATE NO. 53	100.00 CYS
0015	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1680.00 SYS
0016	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	156.00 TON
0017	401-10258	JOINT ADHESIVE, SURFACE	720.00 LFT
0018	401-11785	LIQUID ASPHALT SEALANT	720.00 LFT
0019	406-05521	ASPHALT FOR TACK COAT	1808.00 SYS
0020	503-12480	TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT	600.00 SFT
0021	507-07482	CRACKS IN PCCP, ROUT AND SEAL	1020.00 LFT
0022	507-08269	CRACKS IN PCCP, FILLED	2536.00 LFT
0023	507-08271	JOINTS IN PCCP, FILLED	300.00 LFT
0024	507-08272	JOINTS IN PCCP, SAW AND SEAL	300.00 LFT
0025	602-06729	BARRIER, DELINEATOR	112.00 EACH
0026	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	480.00 LFT
0027	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00 LS
0028	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00 LS
0029	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00 LS
0030	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00 LS
0031	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00 LS



0032	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0033	628-09402	FIELD OFFICE, B	10.00	MOS
0034	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0035	703-08247	EMBEDDED GALVANIC ANODE	60.00	EACH
0036	709-51821	SURFACE SEAL	1.00	LS
0037	709-51821	SURFACE SEAL	1.00	LS
0038	709-51821	SURFACE SEAL	1.00	LS
0039	709-51821	SURFACE SEAL	1.00	LS
0040	709-51821	SURFACE SEAL	1.00	LS
0041	709-51821	SURFACE SEAL	1.00	LS
0042	710-09158	PATCHING CONCRETE STRUCTURES	20.00	SFT
0043	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	300.00	SFT
0044	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	516.00	SFT
0045	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	516.00	SFT
0046	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	181.00	SFT
0047	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	181.00	SFT
0048	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	165.00	SFT
0049	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	165.00	SFT
0050	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	9562.00	SYS
0051	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	EACH
0052	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	101610.00	LFT
0053	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	41060.00	LFT
0054	801-06625	DETOUR ROUTE MARKER ASSEMBLY	19.00	EACH
0055	801-06640	CONSTRUCTION SIGN, A	109.00	EACH
0056	801-06645	CONSTRUCTION SIGN, B	26.00	EACH
0057	801-06649	TEMPORARY RAISED PAVEMENT MARKER, GRADE 1	3944.00	EACH
0058	801-06710	FLASHING ARROW SIGN	120.00	DAY
0059	801-06775	MAINTAINING TRAFFIC	1.00	LS
0060	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	2.00	EACH
0061	801-07118	BARRICADE, III-A	48.00	LFT
0062	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	7114.00	LFT
0063	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	14.00	EACH
0064	801-12031	TEMPORARY PORTABLE RUMBLE STRIPS	180.00	DAY
0065	801-12652	QUEUE TRUCK	196.00	DAY
0066	802-04893	REFERENCE POST	4.00	EACH
0067	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	1010.00	LFT
0068	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	2020.00	LFT

0069	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	2020.00	LFT
0070	808-12032	GROOVING FOR PAVEMENT MARKINGS	724.00	LFT
0071	808-75994	PRISMATIC REFLECTOR	396.00	EACH

Call: 551

Contract: B -41207-A

Section No.: 1

BRIDGE DECK OVERLAY

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-01015	CLEARING AND GRUBBING	1.00 LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0012	202-02240	PAVEMENT REMOVAL	894.00 SYS
0013	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0015	202-94810	CURB TURNOUT, REMOVE	4.00 EACH
0016	203-02000	EXCAVATION, COMMON	315.00 CYS
0017	203-08607	LINEAR GRADING	330.00 LFT
0018	205-12108	STORMWATER MANAGEMENT BUDGET	4965.00 DOL
0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0020	205-12618	SWQCP PREPARATION	1.00 LS
0021	206-51235	COFFERDAM	1.00 LS
0022	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	894.00 SYS
0023	302-06464	SUBBASE FOR PCCP	230.00 CYS
0024	303-01180	COMPACTED AGGREGATE NO. 53	58.00 TON
0025	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1778.00 SYS
0026	306-08043	MILLING, TRANSITION	3334.00 SYS
0027	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	426.00 TON
0028	401-10258	JOINT ADHESIVE, SURFACE	3370.00 LFT
0029	401-11785	LIQUID ASPHALT SEALANT	3370.00 LFT
0030	406-05520	ASPHALT FOR TACK COAT	4.00 TON
0031	503-12480	TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT	160.00 SFT

0032	507-08269	CRACKS IN PCCP, FILLED	310.00	LFT
0033	507-08272	JOINTS IN PCCP, SAW AND SEAL	329.00	LFT
0034	601-02241	GUARDRAIL, REMOVE	1385.00	LFT
0035	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	700.00	LFT
0036	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	4.00	EACH
0037	601-12291	GUARDRAIL MGS TRANSITION WITH CURB	4.00	EACH
0038	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00	EACH
0039	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0040	605-05523	CURB, HMA	80.00	LFT
0041	605-09137	CURB, TURNOUT	46.00	LFT
0042	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	894.00	SYS
0043	616-06405	RIPRAP, REVETMENT	1178.00	TON
0044	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	1099.00	SYS
0045	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.00	EACH
0046	621-03909	SEED MIXTURE, NATIVE	30.00	LBS
0047	628-09402	FIELD OFFICE, B	12.00	MOS
0048	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0049	628-11977	COMPUTER SYSTEM	1.00	EACH
0050	701-93790	CLEAN AND EPOXY COAT EXISTING PILES	1.00	LS
0051	703-06029	REINFORCING BARS, EPOXY COATED	55916.00	LBS
0052	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	8.00	EACH
0053	709-12077	FIBER WRAP CONCRETE CASING SYSTEM	290.00	SFT
0054	709-51821	SURFACE SEAL	1.00	LS
0055	709-51821	SURFACE SEAL	1.00	LS
0056	709-51821	SURFACE SEAL	1.00	LS
0057	709-51821	SURFACE SEAL	1.00	LS
0058	709-51821	SURFACE SEAL	1.00	LS
0059	710-09158	PATCHING CONCRETE STRUCTURES	70.00	SFT
0060	711-51035	STRUCTURAL STEEL	570.00	LBS
0061	711-51035	STRUCTURAL STEEL	284.00	LBS
0062	711-51035	STRUCTURAL STEEL	284.00	LBS
0063	720-44000	CASTING, ADJUST TO GRADE	4.00	EACH
0064	722-01066	HYDRODEMOLITION	4935.00	SYS
0065	722-12380	BRIDGE DECK OVERLAY, BUDGET	55715.40	DOL
0066	722-12382	TRANSVERSE GROOVING	5386.00	SYS
0067	722-12463	BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY	3248.00	SYS
0068	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	1687.00	SYS

0069	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	265.00	SFT
0070	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	50.00	SFT
0071	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	280.00	SFT
0072	722-51874	OVERLAY DAM	324.00	SFT
0073	724-11063	STRUCTURAL EXPANSION JOINT, SS, REPLACE	176.00	LFT
0074	727-90308	EPOXY INJECTION, CRACK PREPARATION	391.00	LFT
0075	727-90309	EPOXY INJECTION, EPOXY MATERIAL	92.00	GAL
0076	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0077	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0078	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0079	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	1555.00	SYS
0080	801-02595	CONTROLLER RESET TIMING	5.00	EACH
0081	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00	EACH
0082	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	35759.00	LFT
0083	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	13455.00	LFT
0084	801-06539	TEMPORARY TRAFFIC SIGNAL INSTALLATION, MAINTAIN	1.00	LS
0085	801-06625	DETOUR ROUTE MARKER ASSEMBLY	48.00	EACH
0086	801-06640	CONSTRUCTION SIGN, A	86.00	EACH
0087	801-06645	CONSTRUCTION SIGN, B	16.00	EACH
0088	801-06649	TEMPORARY RAISED PAVEMENT MARKER, GRADE 1	1521.00	EACH
0089	801-06710	FLASHING ARROW SIGN	300.00	DAY
0090	801-06775	MAINTAINING TRAFFIC	1.00	LS
0091	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	4.00	EACH
0092	801-07118	BARRICADE, III-A	176.00	LFT
0093	801-07119	BARRICADE, III-B	152.00	LFT
0094	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	2935.00	LFT
0095	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	313.00	LFT
0096	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0097	802-04893	REFERENCE POST	12.00	EACH
0098	802-07057	SIGN, PANEL, WITH LEGEND	72.00	SFT
0099	802-12222	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, A	8.00	EACH
0100	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	686.00	LFT
0101	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	3612.00	LFT
0102	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	5306.00	LFT
0103	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	155.00	LFT
0104	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	35.00	EACH

Call: 551

Contract: B -41207-A

Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED CONCRETE

**Line**

<b>Item No</b>	<b>Item Code</b>	<b>Description</b>	<b>Quantity</b>	<b>Unit</b>
0105	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	4935.00	SYS

Call: 551

Contract: B -41207-A

Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED CONCRETE

**Line**

<b>Item No</b>	<b>Item Code</b>	<b>Description</b>	<b>Quantity</b>	<b>Unit</b>
0106	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	4935.00	SYS

Call: 561

Contract: B -41208-A

Section No.: 1 BRIDGE DECK OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	5288.00	SYS
0013	202-11501	SHORING	1.00	LS
0014	202-51133	RAILING, REMOVE	42.00	LFT
0015	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0016	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0017	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0018	202-51368	SLOPEWALL, REMOVE	4.00	SYS
0019	202-94749	CURB, ASPHALT, REMOVE	2771.00	LFT
0020	202-94954	BARRIER WALL, CONCRETE, REMOVE	146.00	LFT
0021	202-96133	PIPE, REMOVE	715.00	LFT
0022	203-02000	EXCAVATION, COMMON	4016.00	CYS
0023	205-08594	FILTER SOCK	250.00	LFT
0024	205-09387	TEMPORARY TURBIDITY CURTAIN	250.00	LFT
0025	205-12108	STORMWATER MANAGEMENT BUDGET	5100.00	DOL
0026	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0027	205-12618	SWQCP PREPARATION	1.00	LS
0028	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	114.00	CYS
0029	206-51235	COFFERDAM	1.00	LS
0030	207-09935	SUBGRADE TREATMENT, TYPE IC	9097.00	SYS
0031	211-06467	AGGREGATE FOR END BENT BACKFILL	230.00	CYS

0032	213-08068	DRILLED HOLE FOR FLOWABLE BACKFILL	10.00 EACH
0033	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	27.00 CYS
0034	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	9097.00 SYS
0035	301-12234	COMPACTED AGGREGATE NO. 53	121.00 CYS
0036	302-06464	SUBBASE FOR PCCP	755.00 CYS
0037	303-01180	COMPACTED AGGREGATE NO. 53	228.00 TON
0038	306-08034	MILLING, ASPHALT, 1 1/2 IN.	864.00 SYS
0039	306-08043	MILLING, TRANSITION	3561.00 SYS
0040	401-07329	QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	751.00 TON
0041	401-07399	QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm	706.00 TON
0042	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	2866.00 TON
0043	401-10258	JOINT ADHESIVE, SURFACE	3724.00 LFT
0044	401-10259	JOINT ADHESIVE, INTERMEDIATE	960.00 LFT
0045	401-11785	LIQUID ASPHALT SEALANT	5219.00 LFT
0046	406-05520	ASPHALT FOR TACK COAT	12.90 TON
0047	406-05521	ASPHALT FOR TACK COAT	4636.00 SYS
0048	502-06329	PCCP, 12 IN.	1810.00 SYS
0049	503-03489	RETROFITTED TIE BARS	1371.00 EACH
0050	503-05240	D-1 CONTRACTION JOINT	669.00 LFT
0051	503-05310	TERMINAL JOINT	155.00 LFT
0052	503-12476	JOINTED REINFORCED CONCRETE PAVEMENT 12 IN.	595.00 SYS
0053	503-12477	TERMINAL JOINT, TYPE HMA	465.00 LFT
0054	503-12478	TERMINAL JOINT, TYPE PCCP	134.00 LFT
0055	503-12479	EXPANSION JOINT WITH LOAD TRANSFER	402.00 LFT
0056	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	2.00 EACH
0057	601-02241	GUARDRAIL, REMOVE	394.00 LFT
0058	601-06035	GUARDRAIL, RESET	250.00 LFT
0059	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	4.00 EACH
0060	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00 EACH
0061	601-99132	GUARDRAIL, TRANSITION, VH, 6 FT 3 IN. SPACING	2.00 EACH
0062	602-06729	BARRIER, DELINEATOR	20.00 EACH
0063	602-11938	CONCRETE BARRIER, MODIFIED SECTION	21.50 CYS
0064	602-91266	CONCRETE MEDIAN BARRIER MODIFIED	146.00 LFT
0065	605-05523	CURB, HMA	2771.00 LFT
0066	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	2771.00 LFT
0067	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	1407.20 SYS
0068	616-05688	RIPRAP, CLASS 1	185.00 TON



0069	616-06405	RIPRAP, REVETMENT	589.00 TON
0070	616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	185.00 SYS
0071	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	607.00 SYS
0072	616-51366	SLOPEWALL, CONCRETE, 5 IN.	4.00 SYS
0073	616-51367	SLOPEWALL, CONCRETE, 4 IN.	6.00 SYS
0074	616-93772	INSPECTION HOLE	6.00 EACH
0075	619-11050	CLEAN STEEL BRIDGE, PARTIAL, QP-2, BRIDGE NO.	1.00 LS
0076	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00 LS
0077	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00 LS
0078	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00 LS
0079	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 EACH
0080	621-06560	MULCHED SEEDING U	2000.00 SYS
0081	628-09403	FIELD OFFICE, C	12.00 MOS
0082	628-11976	COMPUTER SYSTEM EQUIPMENT	4.00 EACH
0083	702-44240	CONCRETE, A, STRUCTURES	60.00 CYS
0084	702-51863	FIELD DRILLED HOLE IN CONCRETE	920.00 EACH
0085	703-06029	REINFORCING BARS, EPOXY COATED	139114.00 LBS
0086	703-08247	EMBEDDED GALVANIC ANODE	140.00 EACH
0087	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	892.00 EACH
0088	704-51002	CONCRETE, C, SUPERSTRUCTURE	231.00 CYS
0089	706-09959	RAILING, CONCRETE FT	22.00 LFT
0090	706-09960	RAILING, CONCRETE FC	68.00 LFT
0091	706-11600	RAILING, CONCRETE FC	6.00 CYS
0092	706-11601	RAILING, CONCRETE FT	12.60 CYS
0093	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00 EACH
0094	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TFT	4.00 EACH
0095	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00 LS
0096	709-51821	SURFACE SEAL	1.00 LS
0097	709-51821	SURFACE SEAL	1.00 LS
0098	709-51821	SURFACE SEAL	1.00 LS
0099	709-51821	SURFACE SEAL	1.00 LS
0100	709-51821	SURFACE SEAL	1.00 LS
0101	710-09158	PATCHING CONCRETE STRUCTURES	525.00 SFT
0102	711-51864	DRILLED HOLE	272.00 EACH
0103	711-90114	JACKING AND SUPPORTING, SUPERSTRUCTURE	1.00 LS
0104	711-96800	STUD SHEAR CONNECTORS	1651.00 EACH
0105	713-04331	TEMPORARY CAUSEWAY	1.00 LS

0106	715-05407	PIPE, END BENT DRAIN, 6 IN.	576.00	LFT
0107	718-12307	GEOTEXTILE FOR UNDERDRAIN, TYPE 2A	651.00	SYS
0108	718-52610	AGGREGATE FOR UNDERDRAINS	7.00	CYS
0109	720-01355	INLET, CLEAN EXISTING	13.00	EACH
0110	720-44000	CASTING, ADJUST TO GRADE	8.00	EACH
0111	722-01066	HYDRODEMOLITION	9171.00	SYS
0112	722-12380	BRIDGE DECK OVERLAY, BUDGET	177751.00	DOL
0113	722-12382	TRANSVERSE GROOVING	9744.00	SYS
0114	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	9171.00	SYS
0115	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	4576.00	SFT
0116	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	4150.00	SFT
0117	722-51874	OVERLAY DAM	396.00	SFT
0118	724-03276	STRUCTURAL EXPANSION JOINT SEALING SYS	307.00	LFT
0119	724-12103	PRE-COMPRESSED FOAM JOINT	396.00	LFT
0120	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	4020.00	SYS
0121	801-03290	CONSTRUCTION SIGN, C	5.00	EACH
0122	801-04746	ENERGY ABSORBING TERMINAL, CZ, TL-	2.00	EACH
0123	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	6470.00	LFT
0124	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	38778.00	LFT
0125	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	2.00	EACH
0126	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	64.00	LFT
0127	801-06625	DETOUR ROUTE MARKER ASSEMBLY	32.00	EACH
0128	801-06640	CONSTRUCTION SIGN, A	132.00	EACH
0129	801-06645	CONSTRUCTION SIGN, B	23.00	EACH
0130	801-06710	FLASHING ARROW SIGN	370.00	DAY
0131	801-06775	MAINTAINING TRAFFIC	1.00	LS
0132	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	2.00	EACH
0133	801-07118	BARRICADE, III-A	346.00	LFT
0134	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	6360.00	LFT
0135	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	2180.00	LFT
0136	801-12042	TRUCK MOUNTED ATTENUATOR	20.00	DAY
0137	802-03821	SIGN, SHEET, WITH LEGEND,	2.00	EACH
0138	802-04893	REFERENCE POST	8.00	EACH
0139	808-06716	LINE, REMOVE	10598.00	LFT
0140	808-10032	LINE, MULTI-COMPONENT, DOTTED, WHITE, 8 IN.	2015.00	LFT
0141	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	8935.00	LFT
0142	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	10425.00	LFT

0143	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	480.00	LFT
0144	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	4445.00	LFT
0145	808-12032	GROOVING FOR PAVEMENT MARKINGS	16810.00	LFT
0146	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	68.00	EACH
0147	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	225.00	EACH

Call: 561

Contract: B -41208-A

Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED CONCRETE

**Line**

<b>Item No</b>	<b>Item Code</b>	<b>Description</b>	<b>Quantity</b>	<b>Unit</b>
0148	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	9268.20	SYS

Call: 561

Contract: B -41208-A

Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED CONCRETE

**Line**

<b>Item No</b>	<b>Item Code</b>	<b>Description</b>	<b>Quantity</b>	<b>Unit</b>
0149	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	9268.20	SYS

Call: 571

Contract: B -41212-A

Section No.: 1 BRIDGE DECK SEALING

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0012	202-02240	PAVEMENT REMOVAL	752.00 SYS
0013	202-02278	CURB, CONCRETE, REMOVE	200.00 LFT
0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0015	202-52710	SIDEWALK CONCRETE, REMOVE	123.00 SYS
0016	203-02000	EXCAVATION, COMMON	337.00 CYS
0017	205-12108	STORMWATER MANAGEMENT BUDGET	7200.00 DOL
0018	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0019	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	42.00 CYS
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	752.00 SYS
0021	211-02050	B BORROW	6.00 CYS
0022	211-09267	STRUCTURE BACKFILL, TYPE 4	26.80 CYS
0023	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	752.00 SYS
0024	301-12234	COMPACTED AGGREGATE NO. 53	75.00 CYS
0025	302-06464	SUBBASE FOR PCCP	76.40 CYS
0026	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	37.00 TON
0027	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	62.00 TON
0028	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	270.00 TON
0029	401-10258	JOINT ADHESIVE, SURFACE	240.00 LFT
0030	401-10259	JOINT ADHESIVE, INTERMEDIATE	240.00 LFT
0031	401-11785	LIQUID ASPHALT SEALANT	240.00 LFT

0032	406-05521	ASPHALT FOR TACK COAT	446.00	SYS
0033	503-12477	TERMINAL JOINT, TYPE HMA	134.00	LFT
0034	604-06070	SIDEWALK, CONCRETE	123.00	SYS
0035	605-06090	CURB, INTEGRAL CONCRETE	82.00	LFT
0036	605-06120	CURB, CONCRETE	120.00	LFT
0037	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	304.00	SYS
0038	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0039	621-06560	MULCHED SEEDING U	2670.00	SYS
0040	628-09403	FIELD OFFICE, C	6.00	MOS
0041	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0042	702-04325	TEMPORARY SHORING	1.00	LS
0043	702-51863	FIELD DRILLED HOLE IN CONCRETE	42.00	EACH
0044	703-06029	REINFORCING BARS, EPOXY COATED	94512.00	LBS
0045	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	289.00	EACH
0046	704-51002	CONCRETE, C, SUPERSTRUCTURE	304.90	CYS
0047	704-51106	DECK DRAIN	18.00	EACH
0048	706-04683	RAILING	41.00	LFT
0049	706-06353	CONCRETE BRIDGE RAILING TRANSITION, TPS-1	2.00	EACH
0050	706-06353	CONCRETE BRIDGE RAILING TRANSITION, TPS-1	2.00	EACH
0051	706-11418	RAILING, STEEL PS-1	115.00	LFT
0052	706-11604	RAILING, CONCRETE PS-1	12.00	CYS
0053	709-51821	SURFACE SEAL	1.00	LS
0054	709-51821	SURFACE SEAL	1.00	LS
0055	710-09158	PATCHING CONCRETE STRUCTURES	50.00	SFT
0056	715-05407	PIPE, END BENT DRAIN, 6 IN.	200.00	LFT
0057	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0058	718-12308	GEOTEXTILE FOR UNDERDRAIN, TYPE 2B	125.60	SYS
0059	724-12103	PRE-COMPRESSED FOAM JOINT	134.00	LFT
0060	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.00	EACH
0061	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	7.00	EACH
0062	801-03290	CONSTRUCTION SIGN, C	2.00	EACH
0063	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	640.00	LFT
0064	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	6775.00	LFT
0065	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	840.00	LFT
0066	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	24.00	LFT
0067	801-06640	CONSTRUCTION SIGN, A	33.00	EACH
0068	801-06645	CONSTRUCTION SIGN, B	11.00	EACH

0069	801-06710	FLASHING ARROW SIGN	280.00	DAY
0070	801-06775	MAINTAINING TRAFFIC	1.00	LS
0071	801-07118	BARRICADE, III-A	217.00	LFT
0072	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	240.00	LFT
0073	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	200.00	LFT
0074	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0075	808-06716	LINE, REMOVE	990.00	LFT
0076	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	352.00	LFT
0077	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	200.00	LFT
0078	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	1235.00	LFT
0079	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	180.00	LFT
0080	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	48.00	LFT
0081	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	4.00	EACH
0082	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	6.00	EACH

Call: 581

Contract: B -41213-A

Section No.: 1

BRIDGE DECK OVERLAY

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0013	202-02240	PAVEMENT REMOVAL	2054.00 SYS
0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0015	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0016	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0017	202-91385	INLET, REMOVE	2.00 EACH
0018	203-02000	EXCAVATION, COMMON	895.50 CYS
0019	203-02020	EXCAVATION, UNCLASSIFIED	114.00 CYS
0020	205-12108	STORMWATER MANAGEMENT BUDGET	41470.00 DOL
0021	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0022	205-12618	SWQCP PREPARATION	1.00 LS
0023	207-09935	SUBGRADE TREATMENT, TYPE IC	2296.00 SYS
0024	211-06467	AGGREGATE FOR END BENT BACKFILL	59.00 CYS
0025	301-12234	COMPACTED AGGREGATE NO. 53	228.00 CYS
0026	302-06464	SUBBASE FOR PCCP	241.50 CYS
0027	306-08043	MILLING, TRANSITION	3314.00 SYS
0028	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	388.00 TON
0029	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	96.00 TON
0030	401-07393	QC/QA-HMA, 4, 64, INTERMEDIATE, 19.0 mm	88.00 TON
0031	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	802.00 TON

0032	401-10258	JOINT ADHESIVE, SURFACE	2520.00	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	1320.00	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	2520.00	LFT
0035	406-05521	ASPHALT FOR TACK COAT	3692.00	SYS
0036	503-12477	TERMINAL JOINT, TYPE HMA	399.00	LFT
0037	601-02241	GUARDRAIL, REMOVE	1215.00	LFT
0038	601-06035	GUARDRAIL, RESET	100.00	LFT
0039	601-06303	IMPACT ATTENUATOR, RESET, R2-W2, TL-2	2.00	EACH
0040	601-12284	GUARDRAIL, MGS W-BEAM, DOUBLE FACED 6 FT 3 IN SPACING	50.00	LFT
0041	601-12291	GUARDRAIL MGS TRANSITION WITH CURB	6.00	EACH
0042	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	2.00	EACH
0043	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	2.00	EACH
0044	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0045	601-94690	GUARDRAIL, END TREATMENT, MS	2.00	EACH
0046	602-06729	BARRIER, DELINEATOR	52.00	EACH
0047	605-06120	CURB, CONCRETE	280.00	LFT
0048	605-09131	CURB AND GUTTER, TURNOUT CONCRETE	88.00	LFT
0049	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	956.00	SYS
0050	611-08232	MAILBOX ASSEMBLY, RESET SINGLE	1.00	EACH
0051	616-06405	RIPRAP, REVETMENT	160.00	TON
0052	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	226.00	SYS
0053	619-11051	CLEAN STEEL BRIDGE, QP-1, BRIDGE NO.	1.00	LS
0054	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0055	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0056	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0057	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0058	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0059	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0060	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0061	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0062	619-12460	DISPOSAL OF CLEANING WASTE NONHAZARDOUS, BRIDGE NO	1.00	LS
0063	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0064	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0065	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0066	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0067	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0068	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.00	EACH



0069	621-06560	MULCHED SEEDING U	8720.00	SYS
0070	621-06574	SODDING	72.00	SYS
0071	621-12612	SEED MIXTURE FLOODPLAIN	15.00	LBS
0072	628-09402	FIELD OFFICE, B	14.00	MOS
0073	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0074	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	8.00	EACH
0075	702-51863	FIELD DRILLED HOLE IN CONCRETE	400.00	EACH
0076	702-92857	CONCRETE, C, SUBSTRUCTURE	14.00	CYS
0077	703-06029	REINFORCING BARS, EPOXY COATED	83464.00	LBS
0078	703-08247	EMBEDDED GALVANIC ANODE	177.00	EACH
0079	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	588.00	EACH
0080	704-51002	CONCRETE, C, SUPERSTRUCTURE	128.00	CYS
0081	706-11600	RAILING, CONCRETE FC	14.40	CYS
0082	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	12.00	EACH
0083	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0084	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0085	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0086	709-51821	SURFACE SEAL	1.00	LS
0087	709-51821	SURFACE SEAL	1.00	LS
0088	709-51821	SURFACE SEAL	1.00	LS
0089	710-09158	PATCHING CONCRETE STRUCTURES	880.00	SFT
0090	711-51864	DRILLED HOLE	128.00	EACH
0091	711-90114	JACKING AND SUPPORTING, SUPERSTRUCTURE	1.00	LS
0092	711-90114	JACKING AND SUPPORTING, SUPERSTRUCTURE	1.00	LS
0093	715-05407	PIPE, END BENT DRAIN, 6 IN.	280.00	LFT
0094	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	1.00	EACH
0095	718-12308	GEOTEXTILE FOR UNDERDRAIN, TYPE 2B	175.00	SYS
0096	722-01066	HYDRODEMOLITION	4861.00	SYS
0097	722-12380	BRIDGE DECK OVERLAY, BUDGET	24634.00	DOL
0098	722-12382	TRANSVERSE GROOVING	5992.00	SYS
0099	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	4861.00	SYS
0100	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	218.00	SFT
0101	722-51874	OVERLAY DAM	399.00	SFT
0102	724-12103	PRE-COMPRESSED FOAM JOINT	529.00	LFT
0103	724-12461	CONCRETE FOR PATCHING STRUCTURAL EXPANSION JOINT	40.00	SFT
0104	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	12.00	EACH
0105	801-03290	CONSTRUCTION SIGN, C	4.00	EACH

0106	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	2428.00	LFT
0107	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	92158.00	LFT
0108	801-06640	CONSTRUCTION SIGN, A	184.00	EACH
0109	801-06645	CONSTRUCTION SIGN, B	4.00	EACH
0110	801-06649	TEMPORARY RAISED PAVEMENT MARKER, GRADE 1	60.00	EACH
0111	801-06710	FLASHING ARROW SIGN	1070.00	DAY
0112	801-06775	MAINTAINING TRAFFIC	1.00	LS
0113	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	3.00	EACH
0114	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	1.00	EACH
0115	801-07118	BARRICADE, III-A	72.00	LFT
0116	801-07119	BARRICADE, III-B	96.00	LFT
0117	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	6327.00	LFT
0118	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	10.00	EACH
0119	802-04893	REFERENCE POST	4.00	EACH
0120	805-02389	SIGNAL CABLE, LOOP DETECTOR LEAD-IN. COPPER, 2C/14 GA	308.00	LFT
0121	805-08214	CONDUIT, PVC, 2 IN. SCHEDULE 40	50.00	LFT
0122	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	100.00	LFT
0123	805-78785	SIGNAL DETECTOR HOUSING	1.00	EACH
0124	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	40.00	LFT
0125	808-06716	LINE, REMOVE	29874.00	LFT
0126	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0127	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	7440.00	LFT
0128	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	14350.00	LFT
0129	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	14770.00	LFT
0130	808-12032	GROOVING FOR PAVEMENT MARKINGS	36560.00	LFT

Call: 581

Contract: B -41213-A

Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED CONCRETE

**Line**

<b>Item No</b>	<b>Item Code</b>	<b>Description</b>	<b>Quantity</b>	<b>Unit</b>
0131	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	5036.00	SYS

Call: 581

Contract: B -41213-A

Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED CONCRETE

**Line**

<b>Item No</b>	<b>Item Code</b>	<b>Description</b>	<b>Quantity</b>	<b>Unit</b>
0132	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	5036.00	SYS

Call: 591

Contract: B -42115-A

Section No.: 1 DEBRIS REMOVAL FROM CHANNEL

**Line**

<b>Item No</b>	<b>Item Code</b>	<b>Description</b>	<b>Quantity</b>	<b>Unit</b>
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	201-90788	DEBRIS, REMOVE STRUCTURE NO.	1.00	LS
0008	205-12108	STORMWATER MANAGEMENT BUDGET	2000.00	DOL
0009	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0010	801-06640	CONSTRUCTION SIGN, A	6.00	EACH
0011	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 601

Contract: B -42217-A

Section No.: 1 BRIDGE MAINTENANCE AND REPAIR

<b>Line</b>			<b>Quantity</b>	<b>Unit</b>
<b>Item No</b>	<b>Item Code</b>	<b>Description</b>		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	602-06729	BARRIER, DELINEATOR	16.00	EACH
0009	628-09409	MOBILE INTERNET SERVICE	5.00	MOS
0010	709-51821	SURFACE SEAL	1.00	LS
0011	709-51821	SURFACE SEAL	1.00	LS
0012	727-90308	EPOXY INJECTION, CRACK PREPARATION	957.00	LFT
0013	727-90309	EPOXY INJECTION, EPOXY MATERIAL	2.00	GAL
0014	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0015	801-06640	CONSTRUCTION SIGN, A	18.00	EACH
0016	801-06710	FLASHING ARROW SIGN	42.00	DAY
0017	801-06775	MAINTAINING TRAFFIC	1.00	LS
0018	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	1.00	EACH
0019	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	6.00	EACH
0020	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	384.00	SFT

Call: 621

Contract: B -42680-A

Section No.: 1 IDIQ, DISTRICT WIDE BRIDGE MAINTENANCE

Line			
Item No	Item Code	Description	Quantity Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0002	109-08360	CONTRACT LIENS	1.00 DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0005	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0007	110-12655	MOBILIZATION AND DEMOBILIZATION, IDIQ	150000.00 DOL
0008	202-02240	PAVEMENT REMOVAL	40.00 SYS
0009	202-51368	SLOPEWALL, REMOVE	450.00 SYS
0010	203-02000	EXCAVATION, COMMON	50.00 CYS
0011	203-02070	BORROW	40.00 CYS
0012	203-08607	LINEAR GRADING	400.00 LFT
0013	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	40.00 CYS
0014	303-01180	COMPACTED AGGREGATE NO. 53	40.00 TON
0015	304-12627	HMA PATCHING FULL DEPTH TYPE D	25.00 TON
0016	503-12173	TERMINAL JOINT, POLYMER MODIFIED ASPHALT	50.00 LFT
0017	506-06333	PCCP PATCHING, FULL DEPTH	50.00 SYS
0018	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	300.00 SYS
0019	616-05688	RIPRAP, CLASS 1	25.00 TON
0020	616-06405	RIPRAP, REVETMENT	25.00 TON
0021	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	50.00 SYS
0022	616-51367	SLOPEWALL, CONCRETE, 4 IN.	450.00 SYS
0023	616-93772	INSPECTION HOLE	10.00 EACH
0024	619-98427	CLEAN DRAINS	8.00 EACH
0025	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 EACH
0026	621-06559	MULCHED SEEDING R	100.00 SYS
0027	703-06029	REINFORCING BARS, EPOXY COATED	250.00 LBS
0028	708-51813	PNEUMATICALLY PLACED MORTAR	30.00 SFT
0029	710-09158	PATCHING CONCRETE STRUCTURES	30.00 SFT
0030	711-11599	REPAIR WELD	24.00 IN
0031	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	300.00 SFT

0032	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	35.00	SFT
0033	724-03276	STRUCTURAL EXPANSION JOINT SEALING SYS	25.00	LFT
0034	724-09626	STRUCTURAL EXPANSION JOINT SEAL, SS, REPLACE	25.00	LFT
0035	724-11063	STRUCTURAL EXPANSION JOINT, SS, REPLACE	25.00	LFT
0036	724-12103	PRE-COMPRESSED FOAM JOINT	50.00	LFT
0037	724-12157	PREFORMED SILICONE JOINT	50.00	LFT
0038	727-90308	EPOXY INJECTION, CRACK PREPARATION	1.00	LFT
0039	727-90309	EPOXY INJECTION, EPOXY MATERIAL	20.00	GAL
0040	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0041	801-06640	CONSTRUCTION SIGN, A	20.00	EACH
0042	801-06645	CONSTRUCTION SIGN, B	10.00	EACH
0043	801-06710	FLASHING ARROW SIGN	30.00	DAY
0044	801-07118	BARRICADE, III-A	80.00	LFT
0045	801-12440	MAINTAINING TRAFFIC, IDIQ	275000.00	DOL

Call: 701

Contract: T -40095-A

Section No.: 1            TRAFFIC SIGNALS MODERNIZATION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	202-01845	CONDUIT, REMOVE	414.00	LFT
0009	202-02278	CURB, CONCRETE, REMOVE	243.00	LFT
0010	202-02279	CURB AND GUTTER, REMOVE	226.00	LFT
0011	202-52710	SIDEWALK CONCRETE, REMOVE	368.00	SYS
0012	304-12624	HMA PATCHING PARTIAL DEPTH TYPE B	1.00	TON
0013	604-02007	SIDEWALK, CONCRETE, RECONSTRUCT	186.00	SYS
0014	604-08086	CURB RAMP, CONCRETE	235.00	SYS
0015	604-12083	DETECTABLE WARNING SURFACES	40.00	SYS
0016	605-06120	CURB, CONCRETE	51.00	LFT
0017	605-06140	CURB AND GUTTER, CONCRETE	232.00	LFT
0018	616-93772	INSPECTION HOLE	1.00	EACH
0019	621-06574	SODDING	5.00	SYS
0020	621-06575	SODDING, NURSERY	3.50	SYS
0021	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0022	801-06206	TEMPORARY PAVEMENT MARKING, 6 IN.	128.00	LFT
0023	801-06640	CONSTRUCTION SIGN, A	7.00	EACH
0024	801-06645	CONSTRUCTION SIGN, B	68.00	EACH
0025	801-06710	FLASHING ARROW SIGN	20.00	DAY
0026	801-06775	MAINTAINING TRAFFIC	1.00	LS
0027	801-07118	BARRICADE, III-A	90.00	LFT
0028	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	200.00	LFT
0029	801-11990	TEMPORARY CURB RAMP	2.00	EACH
0030	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	270.00	SFT
0031	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	47.00	SFT

0032	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	40.00	SFT
0033	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	9.00	EACH
0034	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	15.00	EACH
0035	805-01842	HANDHOLE SIGNAL TYPE 1	13.00	EACH
0036	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00	LS
0037	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	36.00	EACH
0038	805-02445	CONTROLLER AND CABINET, P1	2.00	EACH
0039	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	19.00	EACH
0040	805-04133	SIGNAL POLE, PEDESTAL, 12FT	19.00	EACH
0041	805-04133	SIGNAL POLE, PEDESTAL, 12FT	1.00	EACH
0042	805-06483	CONTROLLER	3.00	EACH
0043	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, 2 CHANNEL	17.00	EACH
0044	805-11374	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 20 FT	1.00	EACH
0045	805-11375	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 25 FT.	1.00	EACH
0046	805-11382	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 60 FT.	2.00	EACH
0047	805-11383	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, A	2.00	EACH
0048	805-11384	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, B	2.00	EACH
0049	805-11813	CONDUIT, PVC, 2 IN. SCHEDULE 80	1010.00	LFT
0050	805-11814	CONDUIT, HDPE, 2 IN. SCHEDULE 40	1000.00	LFT
0051	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	102.00	EACH
0052	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	10.00	EACH
0053	805-78370	PEDESTRIAN PUSH BUTTON, NON-APS	24.00	EACH
0054	805-78415	SPAN, CATENARY, AND TETHER	29.00	EACH
0055	805-78420	DISCONNECT HANGER	33.00	EACH
0056	805-78445	SIGNAL SERVICE	8.00	EACH
0057	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	90.00	LFT
0058	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	4700.00	LFT
0059	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	4000.00	LFT
0060	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	7400.00	LFT
0061	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	8600.00	LFT
0062	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	1100.00	LFT
0063	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	2300.00	LFT
0064	805-78785	SIGNAL DETECTOR HOUSING	10.00	EACH
0065	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1450.00	LFT
0066	805-78925	CONTROLLER CABINET FOUNDATION, P1	2.00	EACH
0067	805-81032	SIGNAL POLE, STEEL STRAIN, 30 FT	14.00	EACH
0068	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	1.00	EACH



0069	805-92504	LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	5.00 EACH
0070	805-96309	PEDESTRIAN PUSH BUTTON, RETROFIT	10.00 EACH
0071	808-06368	TRANSVERSE MARKING, REMOVE	1.00 LFT
0072	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	981.00 LFT
0073	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	2828.00 LFT
0074	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	29.00 EACH
0075	808-75073	PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC, ONLY	23.00 EACH

Call: 711

Contract: T -40358-A

Section No.: 1

SAFETY REVISIONS

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0009	202-02278	CURB, CONCRETE, REMOVE	3016.00	LFT
0010	202-02279	CURB AND GUTTER, REMOVE	675.00	LFT
0011	202-52710	SIDEWALK CONCRETE, REMOVE	2191.00	SYS
0012	202-91385	INLET, REMOVE	1.00	EACH
0013	202-96133	PIPE, REMOVE	7.00	LFT
0014	205-12108	STORMWATER MANAGEMENT BUDGET	17490.00	DOL
0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0016	207-08264	SUBGRADE TREATMENT, TYPE II	24.00	SYS
0017	211-09264	STRUCTURE BACKFILL, TYPE 1	10.00	CYS
0018	304-07494	WIDENING WITH HMA, TYPE C	16.00	TON
0019	304-12625	HMA PATCHING FULL DEPTH TYPE C	90.00	TON
0020	306-08432	MILLING, APPROACH	1454.00	SYS
0021	306-11872	MILLING, PROFILE	145.00	SYS
0022	406-05521	ASPHALT FOR TACK COAT	16.00	SYS
0023	604-06070	SIDEWALK, CONCRETE	917.00	SYS
0024	604-08086	CURB RAMP, CONCRETE	1138.00	SYS
0025	604-12083	DETECTABLE WARNING SURFACES	255.00	SYS
0026	604-12084	DETECTABLE WARNING SURFACES, RETROFIT	4.00	SYS
0027	605-06120	CURB, CONCRETE	132.00	LFT
0028	605-06125	CURB, CONCRETE, MODIFIED	2236.00	LFT
0029	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	684.00	LFT
0030	610-07488	HMA FOR APPROACHES, TYPE C	199.00	TON
0031	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH

0032	621-06560	MULCHED SEEDING U	275.00	SYS
0033	621-06570	TOPSOIL	92.00	CYS
0034	628-09401	FIELD OFFICE, A	12.00	MOS
0035	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0036	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	28.00	LFT
0037	715-09064	VIDEO INSPECTION FOR PIPE	28.00	LFT
0038	720-44000	CASTING, ADJUST TO GRADE	7.00	EACH
0039	720-44296	INLET, CAP	6.00	EACH
0040	720-45010	INLET, A3	7.00	EACH
0041	801-02595	CONTROLLER RESET TIMING	7.00	EACH
0042	801-04092	TEMPORARY PAVEMENT	273.00	SYS
0043	801-04308	ROAD CLOSURE SIGN ASSEMBLY	3.00	EACH
0044	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	10452.00	LFT
0045	801-06625	DETOUR ROUTE MARKER ASSEMBLY	4.00	EACH
0046	801-06640	CONSTRUCTION SIGN, A	91.00	EACH
0047	801-06645	CONSTRUCTION SIGN, B	137.00	EACH
0048	801-06710	FLASHING ARROW SIGN	114.00	DAY
0049	801-06775	MAINTAINING TRAFFIC	1.00	LS
0050	801-07118	BARRICADE, III-A	288.00	LFT
0051	801-07119	BARRICADE, III-B	30.00	LFT
0052	801-11990	TEMPORARY CURB RAMP	11.00	EACH
0053	802-07060	SIGN, SHEET, RELOCATE	2.00	EACH
0054	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	57.00	SFT
0055	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	216.00	SFT
0056	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	47.00	EACH
0057	805-04133	SIGNAL POLE, PEDESTAL, 12FT	12.00	EACH
0058	805-05405	SIGNAL POLE, PEDESTAL, 4FT	35.00	EACH
0059	805-06595	CONDUIT, PVC, 2 IN.	550.00	LFT
0060	805-11799	RECTANGULAR RAPID FLASHING BEACON	12.00	EACH
0061	805-78370	PEDESTRIAN PUSH BUTTON, NON-APS	47.00	EACH
0062	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	7200.00	LFT
0063	805-96309	PEDESTRIAN PUSH BUTTON, RETROFIT	9.00	EACH
0064	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	3952.00	LFT
0065	808-06716	LINE, REMOVE	4144.00	LFT
0066	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	491.00	LFT
0067	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	2683.00	LFT
0068	808-10118	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 24 IN.	32.00	LFT

0069	808-11776	TRANSVERSE MARKING, MULTI-COMPONENT, YIELD LINE, WHITE, 24 IN.	56.00	LFT
0070	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	1120.00	LFT
0071	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	2926.00	LFT

Call: 721

Contract: T -40482-A

Section No.: 1            TRAFFIC SIGNAL VISIBILITY IMPROVEMENTS

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	2.00 EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0004	109-08360	CONTRACT LIENS	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0009	801-06640	CONSTRUCTION SIGN, A	96.00 EACH
0010	801-06775	MAINTAINING TRAFFIC	1.00 LS
0011	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	410.00 SFT
0012	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	112.50 SFT
0013	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	184.50 SFT
0014	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	8.00 EACH
0015	805-01830	CONFLICT MONITOR CHANGEOUT	5.00 EACH
0016	805-01842	HANDHOLE SIGNAL TYPE 1	1.00 EACH
0017	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	20.00 LFT
0018	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00 LS
0019	805-02445	CONTROLLER AND CABINET, P1	1.00 EACH
0020	805-06483	CONTROLLER	1.00 EACH
0021	805-08244	CELLULAR MODEM KIT	8.00 EACH
0022	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	100.00 LFT
0023	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	73.00 EACH
0024	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	9.00 EACH
0025	805-78230	TRAFFIC SIGNAL HEAD, 5 SECTION, 12 IN.	6.00 EACH
0026	805-78415	SPAN, CATENARY, AND TETHER	31.00 EACH
0027	805-78420	DISCONNECT HANGER	31.00 EACH
0028	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	1380.00 LFT
0029	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	3185.00 LFT
0030	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	3785.00 LFT
0031	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	3395.00 LFT

0032	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	1580.00	LFT
0033	805-78785	SIGNAL DETECTOR HOUSING	3.00	EACH
0034	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	445.00	LFT
0035	805-93067	CONTROLLER CABINET, P	1.00	EACH
0036	808-04298	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, R X R	1.00	EACH
0037	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	122.40	SYS
0038	808-06368	TRANSVERSE MARKING, REMOVE	1018.00	LFT
0039	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	70.00	LFT
0040	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1450.00	LFT
0041	808-06716	LINE, REMOVE	2500.00	LFT
0042	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	193.00	LFT
0043	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	16.00	EACH
0044	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1050.00	LFT
0045	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	80.00	LFT
0046	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	825.00	LFT
0047	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	45.00	EACH

Call: 731

Contract: T -41063-A

Section No.: 1 INTERSECTION IMPROVEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	202-02240	PAVEMENT REMOVAL	93.00	SYS
0011	202-02273	CENTER CURB, CONCRETE, REMOVE	509.00	SYS
0012	202-02278	CURB, CONCRETE, REMOVE	17.00	LFT
0013	202-02279	CURB AND GUTTER, REMOVE	800.00	LFT
0014	202-52710	SIDEWALK CONCRETE, REMOVE	24.00	SYS
0015	202-90277	DETECTOR HOUSING, REMOVE	2.00	EACH
0016	202-96133	PIPE, REMOVE	6.00	LFT
0017	207-12151	SUBGRADE TREATMENT, TYPE IVA	803.00	SYS
0018	211-09264	STRUCTURE BACKFILL, TYPE 1	12.00	CYS
0019	302-07455	DENSE GRADED SUBBASE	38.00	CYS
0020	304-12624	HMA PATCHING PARTIAL DEPTH TYPE B	1.20	TON
0021	304-12625	HMA PATCHING FULL DEPTH TYPE C	565.00	TON
0022	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1369.00	SYS
0023	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	116.00	TON
0024	401-10258	JOINT ADHESIVE, SURFACE	1964.00	LFT
0025	401-11785	LIQUID ASPHALT SEALANT	1964.00	LFT
0026	406-05520	ASPHALT FOR TACK COAT	1.00	TON
0027	503-03489	RETROFITTED TIE BARS	512.00	EACH
0028	503-05240	D-1 CONTRACTION JOINT	260.00	LFT
0029	506-06333	PCCP PATCHING, FULL DEPTH	466.00	SYS
0030	604-06070	SIDEWALK, CONCRETE	16.00	SYS
0031	604-08086	CURB RAMP, CONCRETE	8.00	SYS

0032	604-12083	DETECTABLE WARNING SURFACES	4.00	SYS
0033	605-06120	CURB, CONCRETE	17.00	LFT
0034	605-06255	CENTER CURB, D CONCRETE	72.00	SYS
0035	628-09403	FIELD OFFICE, C	8.00	MOS
0036	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0037	715-05032	PIPE, TYPE 2, CIRCULAR, 15 IN.	5.00	LFT
0038	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	227.00	LFT
0039	715-09064	VIDEO INSPECTION FOR PIPE	232.00	LFT
0040	720-44000	CASTING, ADJUST TO GRADE	1.00	EACH
0041	720-45055	INLET, M10	1.00	EACH
0042	720-45155	INLET, M10 MODIFIED	1.00	EACH
0043	720-45235	CATCH BASIN, E7	1.00	EACH
0044	720-45405	MANHOLE, B4	2.00	EACH
0045	720-93409	INLET, B15 MODIFIED	1.00	EACH
0046	720-93411	INLET, C15 MODIFIED	1.00	EACH
0047	720-94847	INLET, R13 MODIFIED	9.00	EACH
0048	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	76.00	EACH
0049	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	61.00	EACH
0050	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	4184.00	LFT
0051	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	30263.00	LFT
0052	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	3820.00	LFT
0053	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	61.00	EACH
0054	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	658.00	LFT
0055	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	658.00	LFT
0056	801-06640	CONSTRUCTION SIGN, A	168.00	EACH
0057	801-06645	CONSTRUCTION SIGN, B	15.00	EACH
0058	801-06710	FLASHING ARROW SIGN	100.00	DAY
0059	801-06775	MAINTAINING TRAFFIC	1.00	LS
0060	801-07118	BARRICADE, III-A	528.00	LFT
0061	801-94295	SIGNAL HEAD RELOCATE	8.00	EACH
0062	802-04089	SIGN, SHEET, REMOVE	1.00	EACH
0063	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	180.00	LFT
0064	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	52.00	LFT
0065	802-07058	SIGN, SHEET, ASSEMBLY RELOCATE	15.00	EACH
0066	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	2.00	EACH
0067	802-07060	SIGN, SHEET, RELOCATE	8.00	EACH
0068	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	48.00	SFT



0069	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	60.00	SFT
0070	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	2.00	EACH
0071	805-01579	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00	LS
0072	805-01842	HANDHOLE SIGNAL TYPE 1	11.00	EACH
0073	805-01842	HANDHOLE SIGNAL TYPE 1	3.00	EACH
0074	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	6.00	EACH
0075	805-02445	CONTROLLER AND CABINET, P1	1.00	EACH
0076	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	4.00	EACH
0077	805-04133	SIGNAL POLE, PEDESTAL, 12FT	4.00	EACH
0078	805-08214	CONDUIT, PVC, 2 IN. SCHEDULE 40	850.00	LFT
0079	805-08244	CELLULAR MODEM KIT	1.00	EACH
0080	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, 2 CHANNEL	6.00	EACH
0081	805-11376	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 30 FT.	2.00	EACH
0082	805-11382	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 60 FT.	2.00	EACH
0083	805-11383	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, A	2.00	EACH
0084	805-11384	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, B	2.00	EACH
0085	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	690.00	LFT
0086	805-11817	PEDESTRIAN PUSH BUTTON, APS	6.00	EACH
0087	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	10.00	EACH
0088	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	5.00	EACH
0089	805-78445	SIGNAL SERVICE	1.00	EACH
0090	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	100.00	LFT
0091	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	6328.00	LFT
0092	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	1100.00	LFT
0093	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	1700.00	LFT
0094	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	1643.00	LFT
0095	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	417.00	LFT
0096	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	5050.00	LFT
0097	805-78785	SIGNAL DETECTOR HOUSING	8.00	EACH
0098	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	2276.00	LFT
0099	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	18.00	SYS
0100	808-06368	TRANSVERSE MARKING, REMOVE	115.00	LFT
0101	808-06716	LINE, REMOVE	8098.00	LFT
0102	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	59.00	LFT
0103	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	4520.00	LFT
0104	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	3978.00	LFT
0105	808-10047	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, WHITE, 12 IN.	614.00	LFT

0106	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	863.00	LFT
0107	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	559.00	LFT
0108	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	22.00	EACH
0109	808-12032	GROOVING FOR PAVEMENT MARKINGS	8098.00	LFT
0110	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	210.00	EACH
0111	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	210.00	EACH