

Schedule of Pay Items Letting Date January 13, 2021 Letting ID 210113

Call: 261

Contract: R -29426-A

Section No.: 1 PAVEMENT REPAIR OR REHABILITATION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-02278	CURB, CONCRETE, REMOVE	6649.00	LFT
0012	202-52710	SIDEWALK CONCRETE, REMOVE	93.00	SYS
0013	202-96022	CONCRETE FOUNDATION, REMOVE	1.00	EACH
0014	202-98370	POLE, REMOVE	1.00	EACH
0015	203-02000	EXCAVATION, COMMON	3889.00	CYS
0016	203-02070	BORROW	1787.00	CYS
0017	205-12108	STORMWATER MANAGEMENT BUDGET	31710.00	DOL
0018	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0019	205-12618	SWQCP PREPARATION	1.00	LS
0020	207-08264	SUBGRADE TREATMENT, TYPE II	2772.00	SYS
0021	207-08266	SUBGRADE TREATMENT, TYPE III	2959.00	SYS
0022	207-09935	SUBGRADE TREATMENT, TYPE IC	77.00	SYS
0023	207-12635	SUBGRADE TREATMENT, TYPE IBC	12562.00	SYS
0024	211-09264	STRUCTURE BACKFILL, TYPE 1	3475.00	CYS
0025	214-11796	GEOGRID, TYPE IB	341.00	SYS
0026	301-12234	COMPACTED AGGREGATE NO. 53	1123.00	CYS
0027	302-07455	DENSE GRADED SUBBASE	519.00	CYS
0028	304-12625	HMA PATCHING FULL DEPTH TYPE C	16.00	TON
0029	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1334.00	TON
0030	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	1249.00	TON
0031	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	1999.00	TON

0032	401-10258	JOINT ADHESIVE, SURFACE	5521.00	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	3069.00	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	5521.00	LFT
0035	406-05520	ASPHALT FOR TACK COAT	7.00	TON
0036	502-03289	QUALITY ASSURANCE ADJUSTMENT	1.00	DOL
0037	502-06999	PCCP, 8 IN.	101.00	SYS
0038	503-05240	D-1 CONTRACTION JOINT	108.00	LFT
0039	604-06070	SIDEWALK, CONCRETE	2824.00	SYS
0040	604-08086	CURB RAMP, CONCRETE	426.00	SYS
0041	604-12083	DETECTABLE WARNING SURFACES	55.00	SYS
0042	605-06140	CURB AND GUTTER, CONCRETE	6237.00	LFT
0043	605-96305	CURB AND GUTTER, CONCRETE DEPRESSED	178.00	LFT
0044	610-07487	HMA FOR APPROACHES, TYPE B	45.00	TON
0045	610-07488	HMA FOR APPROACHES, TYPE C	219.00	TON
0046	610-08446	PCCP FOR APPROACHES, 6 IN.	2689.00	SYS
0047	610-09108	PCCP FOR APPROACHES, 9 IN.	273.00	SYS
0048	611-06497	MAILBOX ASSEMBLY, SINGLE	4.00	EACH
0049	615-06490	RIGHT-OF-WAY MARKER	6.00	EACH
0050	615-06505	MONUMENT, B	29.00	EACH
0051	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0052	621-06545	FERTILIZER	1.00	TON
0053	621-06554	SEED MIXTURE U	141.00	LBS
0054	621-06565	MULCHING MATERIAL	2.00	TON
0055	621-06567	WATER	8.00	KGAL
0056	621-06575	SODDING, NURSERY	1924.00	SYS
0057	628-09403	FIELD OFFICE, C	15.00	MOS
0058	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0059	628-11977	COMPUTER SYSTEM	1.00	EACH
0060	629-12029	PLANT GROWTH LAYER	5333.00	SYS
0061	702-51863	FIELD DRILLED HOLE IN CONCRETE	1.00	EACH
0062	715-01898	WATER MAIN, DUCTILE IRON, 10 IN.	40.00	LFT
0063	715-02531	VALVE, WITH BOX, RESTRAINED GATE, DUCTILE IRON, 6 IN.	2.00	EACH
0064	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	5447.00	LFT
0065	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	93.00	LFT
0066	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	16.00	LFT
0067	715-05408	PIPE, SANITARY SEWER, 8 IN.	1060.00	LFT
0068	715-09064	VIDEO INSPECTION FOR PIPE	6616.00	LFT

0069	715-91742	WATER METER RELOCATE	7.00 EACH
0070	715-92253	SEWER SANITARY LATERAL RECONNECT	12.00 EACH
0071	715-94530	ADJUST WATER VALVE TO GRADE	9.00 EACH
0072	715-94780	WATER MAIN, DUCTILE IRON, 6 IN.	232.00 LFT
0073	715-97873	WATER SERVICE LINE, 1 IN	18.00 EACH
0074	718-04986	CLEANOUT	12.00 EACH
0075	720-01092	MANHOLE, J15 MODIFIED	1.00 EACH
0076	720-02442	PIPE PLUG EXISTING	4.00 EACH
0077	720-04815	DRYWELL	5.00 EACH
0078	720-04815	DRYWELL	6.00 EACH
0079	720-44296	INLET, CAP	1.00 EACH
0080	720-45015	INLET, A8	1.00 EACH
0081	720-45030	INLET, E7	3.00 EACH
0082	720-45035	INLET, F7	1.00 EACH
0083	720-45075	INLET, R13	2.00 EACH
0084	720-45410	MANHOLE, C4	17.00 EACH
0085	720-45410	MANHOLE, C4	4.00 EACH
0086	720-45510	MANHOLE, C4 MODIFIED	7.00 EACH
0087	720-98174	INLET, B15	26.00 EACH
0088	720-98555	INLET, C15	32.00 EACH
0089	801-04308	ROAD CLOSURE SIGN ASSEMBLY	11.00 EACH
0090	801-06625	DETOUR ROUTE MARKER ASSEMBLY	37.00 EACH
0091	801-06640	CONSTRUCTION SIGN, A	35.00 EACH
0092	801-06645	CONSTRUCTION SIGN, B	6.00 EACH
0093	801-06775	MAINTAINING TRAFFIC	1.00 LS
0094	801-07118	BARRICADE, III-A	216.00 LFT
0095	801-07119	BARRICADE, III-B	72.00 LFT
0096	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	324.00 LFT
0097	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	138.00 LFT
0098	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	206.00 SFT
0099	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	57.00 SFT
0100	805-08214	CONDUIT, PVC, 2 IN. SCHEDULE 40	221.00 LFT
0101	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	1034.00 LFT
0102	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	99.00 LFT
0103	808-11482	LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN.	274.00 LFT
0104	808-11691	LINE, THERMOPLASTIC, DOTTED, WHITE, 12 IN.	176.00 LFT
0105	808-12032	GROOVING FOR PAVEMENT MARKINGS	8989.00 LFT

0106	808-12148	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 36 IN.	80.00	LFT
0107	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	8548.00	LFT
0108	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	111.00	LFT
0109	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	677.00	LFT
0110	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	17.00	EACH
0111	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	2.00	EACH

Call: 271

Contract: R -35297-A

Section No.: 1 ROAD RECONSTRUCTION AND WIDENING

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	50.00 EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	10.00 EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0005	109-08360	CONTRACT LIENS	1.00 DOL
0006	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0007	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0008	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0009	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0010	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0011	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0012	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0013	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0014	203-02000	EXCAVATION, COMMON	10420.00 CYS
0015	203-02070	BORROW	8767.00 CYS
0016	205-11626	PUMP AROUND	2.00 EACH
0017	205-12108	STORMWATER MANAGEMENT BUDGET	38294.00 DOL
0018	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0019	205-12618	SWQCP PREPARATION	1.00 LS
0020	207-08264	SUBGRADE TREATMENT, TYPE II	1028.00 SYS
0021	207-08266	SUBGRADE TREATMENT, TYPE III	4907.00 SYS
0022	207-12635	SUBGRADE TREATMENT, TYPE IBC	20861.00 SYS
0023	211-09265	STRUCTURE BACKFILL, TYPE 2	4582.00 CYS
0024	211-09268	STRUCTURE BACKFILL, TYPE 5	98.00 CYS
0025	301-12234	COMPACTED AGGREGATE NO. 53	2453.00 CYS
0026	302-07455	DENSE GRADED SUBBASE	152.00 CYS
0027	303-01180	COMPACTED AGGREGATE NO. 53	10.00 TON
0028	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1329.00 TON
0029	401-07397	QC/QA-HMA, 2, 70, INTERMEDIATE, 19.0 mm	2658.00 TON
0030	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	3101.00 TON
0031	401-10258	JOINT ADHESIVE, SURFACE	11060.00 LFT

0032	401-10259	JOINT ADHESIVE, INTERMEDIATE	11060.00	LFT
0033	401-11785	LIQUID ASPHALT SEALANT	11060.00	LFT
0034	406-05520	ASPHALT FOR TACK COAT	14.00	TON
0035	604-05528	HMA FOR SIDEWALK	661.00	TON
0036	604-06070	SIDEWALK, CONCRETE	2212.00	SYS
0037	604-08086	CURB RAMP, CONCRETE	140.00	SYS
0038	604-12083	DETECTABLE WARNING SURFACES	36.00	SYS
0039	605-06120	CURB, CONCRETE	84.00	LFT
0040	605-06140	CURB AND GUTTER, CONCRETE	6891.00	LFT
0041	605-09131	CURB AND GUTTER, TURNOUT CONCRETE	2.00	LFT
0042	610-07487	HMA FOR APPROACHES, TYPE B	340.00	TON
0043	610-08446	PCCP FOR APPROACHES, 6 IN.	267.00	SYS
0044	610-09108	PCCP FOR APPROACHES, 9 IN.	643.00	SYS
0045	611-06497	MAILBOX ASSEMBLY, SINGLE	5.00	EACH
0046	615-06505	MONUMENT, B	3.00	EACH
0047	615-06527	MONUMENT, SECTION CORNER	1.00	EACH
0048	616-05688	RIPRAP, CLASS 1	366.00	TON
0049	616-06405	RIPRAP, REVETMENT	447.00	TON
0050	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	1200.00	SYS
0051	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0052	621-06545	FERTILIZER	1.00	TON
0053	621-06554	SEED MIXTURE U	483.00	LBS
0054	621-06565	MULCHING MATERIAL	6.00	TON
0055	621-06567	WATER	6.00	KGAL
0056	621-06575	SODDING, NURSERY	1538.00	SYS
0057	628-09402	FIELD OFFICE, B	12.00	MOS
0058	714-11102	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 5 FT. X 2 FT.	83.00	LFT
0059	714-11182	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 10 FT. X 5 FT.	140.00	LFT
0060	715-05019	PIPE, TYPE 1, CIRCULAR, 36 IN.	97.00	LFT
0061	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	6895.00	LFT
0062	715-05119	PIPE, TYPE 1, CIRCULAR, 15 IN.	92.00	LFT
0063	715-05123	PIPE, TYPE 1, CIRCULAR, 24 IN.	33.00	LFT
0064	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	1356.00	LFT
0065	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	465.00	LFT
0066	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	475.00	LFT
0067	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	841.00	LFT
0068	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	134.00	LFT

0069	715-05159	PIPE, TYPE 2, CIRCULAR, 42 IN.	346.00	LFT
0070	715-05162	PIPE, TYPE 2, CIRCULAR, 54 IN.	537.00	LFT
0071	715-08048	STORMWATER TREATMENT SYSTEM	5.00	EACH
0072	715-09064	VIDEO INSPECTION FOR PIPE	10318.00	LFT
0073	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00	EACH
0074	715-46020	PIPE END SECTION, DIAMETER 24 IN.	7.00	EACH
0075	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	6895.00	LFT
0076	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	5746.00	SYS
0077	718-52610	AGGREGATE FOR UNDERDRAINS	622.00	CYS
0078	720-03481	MANHOLE, H4 MODIFIED	3.00	EACH
0079	720-45030	INLET, E7	2.00	EACH
0080	720-45410	MANHOLE, C4	3.00	EACH
0081	720-45605	STRUCTURE, MANHOLE, RECONSTRUCTED	30.00	LFT
0082	720-91973	MANHOLE, H4	7.00	EACH
0083	720-92884	MANHOLE, K4 MODIFIED	2.00	EACH
0084	720-93501	MANHOLE, L4	2.00	EACH
0085	720-98174	INLET, B15	24.00	EACH
0086	720-98555	INLET, C15	26.00	EACH
0087	720-98869	MANHOLE, L4 MODIFIED	2.00	EACH
0088	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0089	801-06625	DETOUR ROUTE MARKER ASSEMBLY	20.00	EACH
0090	801-06640	CONSTRUCTION SIGN, A	10.00	EACH
0091	801-06775	MAINTAINING TRAFFIC	1.00	LS
0092	801-07118	BARRICADE, III-A	48.00	LFT
0093	801-07119	BARRICADE, III-B	120.00	LFT
0094	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	70.00	LFT
0095	802-05705	SIGN POST, SQUARE TYPE 2 UNREINFORCED ANCHOR BASE	40.00	LFT
0096	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	61.00	SFT
0097	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	12.00	SFT
0098	808-02977	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, BIKE SYMBOL	10.00	EACH
0099	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	6436.00	LFT
0100	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	1359.00	LFT
0101	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	5762.00	LFT
0102	808-75274	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 8 IN.	64.00	LFT
0103	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	79.00	LFT
0104	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	487.00	LFT
0105	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	18.00	EACH

0106 808-75340 PAVEMENT MESSAGE MARKING, THERMOPLASTIC R X R

2.00EACH

Call: 281

Contract: R -37908-A

Section No.: 1 INTERSECTION IMPROVEMENT WITH ADDED TURN LANES

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0012	202-02240	PAVEMENT REMOVAL	216.00 SYS
0013	202-02637	PIPE ABANDON AND GROUT FILL	312.00 LFT
0014	202-99187	FENCE, FARM FIELD, REMOVE	488.00 LFT
0015	203-02000	EXCAVATION, COMMON	21619.00 CYS
0016	205-12108	STORMWATER MANAGEMENT BUDGET	168902.00 DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0018	205-12618	SWQCP PREPARATION	1.00 LS
0019	207-12498	SUBGRADE TREATMENT, TYPE ID	167.00 SYS
0020	207-12635	SUBGRADE TREATMENT, TYPE IBC	9919.00 SYS
0021	211-09264	STRUCTURE BACKFILL, TYPE 1	226.00 CYS
0022	211-09265	STRUCTURE BACKFILL, TYPE 2	700.00 CYS
0023	211-09267	STRUCTURE BACKFILL, TYPE 4	22.00 CYS
0024	301-12232	COMPACTED AGGREGATE NO. 5	150.00 CYS
0025	303-01180	COMPACTED AGGREGATE NO. 53	3009.00 TON
0026	304-12625	HMA PATCHING FULL DEPTH TYPE C	105.00 TON
0027	306-08034	MILLING, ASPHALT, 1 1/2 IN.	4996.00 SYS
0028	306-08432	MILLING, APPROACH	73.00 SYS
0029	401-07327	QC/QA-HMA, 2, 70, SURFACE, 9.5 mm	127.00 TON
0030	401-07397	QC/QA-HMA, 2, 70, INTERMEDIATE, 19.0 mm	809.00 TON
0031	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	345.00 TON

0032	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	721.00 TON
0033	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	907.00 TON
0034	401-10258	JOINT ADHESIVE, SURFACE	6315.00 LFT
0035	401-10259	JOINT ADHESIVE, INTERMEDIATE	4865.00 LFT
0036	401-11785	LIQUID ASPHALT SEALANT	6315.00 LFT
0037	406-05520	ASPHALT FOR TACK COAT	9.00 TON
0038	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.00 TON
0039	410-11935	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm - SMA	614.00 TON
0040	410-12672	QC/QA-HMA, 2, 70, SURFACE, 9.5 mm-SMA	355.00 TON
0041	603-98225	FENCE, CHAIN LINK, PVC COATED 48 IN	1264.00 LFT
0042	610-07487	HMA FOR APPROACHES, TYPE B	112.00 TON
0043	610-07488	HMA FOR APPROACHES, TYPE C	46.00 TON
0044	611-06497	MAILBOX ASSEMBLY, SINGLE	3.00EACH
0045	611-06498	MAILBOX ASSEMBLY, DOUBLE	1.00EACH
0046	615-01469	MONUMENT SECTION CORNER INSTALL	1.00EACH
0047	615-06490	RIGHT-OF-WAY MARKER	37.00EACH
0048	615-06500	MONUMENT, A	9.00EACH
0049	616-05688	RIPRAP, CLASS 1	128.00 TON
0050	616-06405	RIPRAP, REVETMENT	16.00 TON
0051	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	141.00 SYS
0052	616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	376.00 SYS
0053	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	1202.00 SYS
0054	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00EACH
0055	621-02318	SEED MIXTURE, PRAIRIE GRASS	8.00 LBS
0056	621-02770	EROSION CONTROL BLANKET	5376.00 SYS
0057	621-03909	SEED MIXTURE, NATIVE	18.00 LBS
0058	621-06545	FERTILIZER	1.00 TON
0059	621-06553	SEED MIXTURE R	44.00 LBS
0060	621-06565	MULCHING MATERIAL	5.00 TON
0061	621-06567	WATER	33.00 kGAL
0062	621-06574	SODDING	351.00 SYS
0063	621-06575	SODDING, NURSERY	1071.00 SYS
0064	621-08161	PERMANENT TURF REINFORCEMENT MAT	2957.00 SYS
0065	621-12613	SEED MIXTURE SHADE	251.00 LBS
0066	622-05641	PLANT, DECIDUOUS SHRUB, 36 TO 48 IN.	25.00EACH
0067	622-05648	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. OR UNDER	50.00EACH
0068	625-09373	GABIONS, METALLIC COATED	207.00 CYS

0069	714-11197	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 3 FT. X 2 FT.	106.00	LFT
0070	715-01471	PIPE END SECTION, PRECAST CONCRETE, 15 IN	1.00	EACH
0071	715-03476	SAFETY METAL END SECTION, 4:1, DIA 24 IN.	2.00	EACH
0072	715-03584	SAFETY METAL END SECTION, 4:1, DIA 18 IN.	1.00	EACH
0073	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	88.00	LFT
0074	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	75.00	LFT
0075	715-05159	PIPE, TYPE 2, CIRCULAR, 42 IN.	210.00	LFT
0076	715-05171	PIPE, TYPE 3, CIRCULAR, 18 IN.	29.00	LFT
0077	715-05173	PIPE, TYPE 3, CIRCULAR, 24 IN.	50.00	LFT
0078	715-05177	PIPE, TYPE 3, CIRCULAR, 36 IN.	106.00	LFT
0079	715-05233	PIPE, TYPE 1, DEFORMED, MIN. AREA 3.3 SFT	74.00	LFT
0080	715-05236	PIPE, TYPE 1, DEFORMED, MIN. AREA 5.0 SFT	106.00	LFT
0081	715-07029	SAFETY METAL END SECTION, 4:1, MIN AREA 3.3 SFT	2.00	EACH
0082	715-07780	SAFETY METAL END SECTION, 4:1, MIN AREA 5.1 SFT	4.00	EACH
0083	715-08306	HMA FOR STRUCTURE INSTALLATION, TYPE C	61.00	TON
0084	715-09064	VIDEO INSPECTION FOR PIPE	593.00	LFT
0085	715-46010	PIPE END SECTION, DIAMETER 18 IN.	1.00	EACH
0086	715-46040	PIPE END SECTION, DIAMETER 36 IN.	4.00	EACH
0087	720-45030	INLET, E7	1.00	EACH
0088	720-92884	MANHOLE, K4 MODIFIED	1.00	EACH
0089	734-10240	CUT-WALL, NO.	10626.00	SFT
0090	801-03290	CONSTRUCTION SIGN, C	6.00	EACH
0091	801-03291	CONSTRUCTION SIGN, D	4.00	EACH
0092	801-04308	ROAD CLOSURE SIGN ASSEMBLY	10.00	EACH
0093	801-06625	DETOUR ROUTE MARKER ASSEMBLY	99.00	EACH
0094	801-06640	CONSTRUCTION SIGN, A	58.00	EACH
0095	801-06645	CONSTRUCTION SIGN, B	10.00	EACH
0096	801-06775	MAINTAINING TRAFFIC	1.00	LS
0097	801-07118	BARRICADE, III-A	120.00	LFT
0098	801-07119	BARRICADE, III-B	64.00	LFT
0099	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	61.00	SFT
0100	802-76065	SIGN POST, B	83.00	LFT
0101	802-91122	SIGN GROUND MOUNTED RESET	1.00	EACH
0102	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	5844.00	LFT
0103	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0104	808-12032	GROOVING FOR PAVEMENT MARKINGS	13818.00	LFT
0105	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	7974.00	LFT

0106	808-75290	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 24 IN.	316.00	LFT
0107	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	38.00	LFT
0108	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	4.00	EACH
0109	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	36.00	EACH
0110	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	78.00	EACH

Call: 291

Contract: R -37942-A

Section No.: 1 ASPHALT RESURFACE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	207-12498	SUBGRADE TREATMENT, TYPE ID	2123.00	SYS
0012	303-01180	COMPACTED AGGREGATE NO. 53	530.00	TON
0013	304-12627	HMA PATCHING FULL DEPTH TYPE D	1460.00	TON
0014	304-12628	HMA PATCHING PARTIAL DEPTH TYPE D	74.00	TON
0015	306-08034	MILLING, ASPHALT, 1 1/2 IN.	192960.00	SYS
0016	306-08432	MILLING, APPROACH	6814.00	SYS
0017	401-06264	PROFILOGRAPH, HMA	1.00	LS
0018	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	13563.00	TON
0019	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	2045.00	TON
0020	401-10258	JOINT ADHESIVE, SURFACE	75546.00	LFT
0021	401-11785	LIQUID ASPHALT SEALANT	75546.00	LFT
0022	406-05520	ASPHALT FOR TACK COAT	52.00	TON
0023	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	6.00	TON
0024	507-08272	JOINTS IN PCCP, SAW AND SEAL	182.00	LFT
0025	610-07487	HMA FOR APPROACHES, TYPE B	565.00	TON
0026	616-06405	RIPRAP, REVETMENT	10.00	TON
0027	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	12.00	SYS
0028	628-09402	FIELD OFFICE, B	12.00	MOS
0029	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0030	628-11977	COMPUTER SYSTEM	1.00	EACH
0031	709-51821	SURFACE SEAL	1.00	LS

0032	709-51821	SURFACE SEAL	1.00	LS
0033	710-09158	PATCHING CONCRETE STRUCTURES	157.00	SFT
0034	718-06529	OUTLET PROTECTOR, 2	3.00	EACH
0035	722-01066	HYDRODEMOLITION	707.00	SYS
0036	722-12380	BRIDGE DECK OVERLAY, BUDGET	11910.00	DOL
0037	722-12382	TRANSVERSE GROOVING	707.00	SYS
0038	722-12463	BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY	707.00	SYS
0039	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	150.00	SFT
0040	722-51874	OVERLAY DAM	182.00	SFT
0041	801-04308	ROAD CLOSURE SIGN ASSEMBLY	7.00	EACH
0042	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	20476.00	LFT
0043	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	1250.00	LFT
0044	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	32.00	LFT
0045	801-06625	DETOUR ROUTE MARKER ASSEMBLY	53.00	EACH
0046	801-06640	CONSTRUCTION SIGN, A	83.00	EACH
0047	801-06645	CONSTRUCTION SIGN, B	7.00	EACH
0048	801-06775	MAINTAINING TRAFFIC	1.00	LS
0049	801-07118	BARRICADE, III-A	72.00	LFT
0050	801-07119	BARRICADE, III-B	76.00	LFT
0051	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	204.00	LFT
0052	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	408.00	LFT
0053	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0054	801-12081	PORTABLE SIGNAL	1.00	LS
0055	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	7880.00	LFT
0056	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	118400.00	LFT
0057	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	72082.00	LFT
0058	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0059	808-12032	GROOVING FOR PAVEMENT MARKINGS	3764.00	LFT
0060	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	639.00	LFT
0061	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	94.00	LFT
0062	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	8.00	EACH
0063	808-75340	PAVEMENT MESSAGE MARKING, THERMOPLASTIC R X R	1.00	EACH
0064	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1463.00	EACH
0065	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1463.00	EACH
0066	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	3764.00	LFT

Call: 291
Contract: R -37942-A
Section No.: 2 BRIDGE DECK OVERLAY LATEX MODIFIED CONCRETE

Line			Quantity Unit	
Item No	Item Code	Description		
0067	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	707.00	SYS

Call: 291
Contract: R -37942-A
Section No.: 3 BRIDGE DECK OVERLAY SILICIA FUME MODIFIED CONCRETE

Line			Quantity Unit	
Item No	Item Code	Description		
0068	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	707.00	SYS

Call: 301

Contract: R -38772-A

Section No.: 1 ASPHALT RESURFACE

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
	0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0012	202-02637	PIPE ABANDON AND GROUT FILL	102.00	LFT
	0013	202-02928	CATCH BASIN, REMOVE	3.00	EACH
	0014	202-74035	SIGN, REMOVE	119.00	EACH
	0015	202-91385	INLET, REMOVE	6.00	EACH
	0016	202-96133	PIPE, REMOVE	3846.00	LFT
	0017	203-02000	EXCAVATION, COMMON	55589.00	CYS
	0018	205-12108	STORMWATER MANAGEMENT BUDGET	482428.00	DOL
	0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0020	205-12618	SWQCP PREPARATION	1.00	LS
	0021	207-08264	SUBGRADE TREATMENT, TYPE II	7892.00	SYS
	0022	207-12151	SUBGRADE TREATMENT, TYPE IVA	3001.00	SYS
	0023	207-12498	SUBGRADE TREATMENT, TYPE ID	18990.00	SYS
	0024	211-09264	STRUCTURE BACKFILL, TYPE 1	2922.00	CYS
	0025	211-09268	STRUCTURE BACKFILL, TYPE 5	56.00	CYS
	0026	214-12237	GEOTEXTILE FOR PAVEMENT TYPE 1B	767.00	SYS
	0027	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	210.00	SYS
	0028	301-12232	COMPACTED AGGREGATE NO. 5	30.00	CYS
	0029	301-12234	COMPACTED AGGREGATE NO. 53	7412.00	CYS
	0030	302-07455	DENSE GRADED SUBBASE	21.00	CYS
	0031	303-08210	COMPACTED AGGREGATE NO. 53 TEMPORARY FOR DRIVEWAYS	1645.00	TON

0032	304-07494	WIDENING WITH HMA, TYPE C	796.00 TON
0033	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	530.00 TON
0034	306-08034	MILLING, ASPHALT, 1 1/2 IN.	4793.00 SYS
0035	306-08036	MILLING, ASPHALT, 2 IN.	125683.00 SYS
0036	306-08043	MILLING, TRANSITION	3400.00 SYS
0037	306-08159	MILLING, ASPHALT	10990.00 SYS
0038	306-11872	MILLING, PROFILE	136795.00 SYS
0039	307-12253	CORRECTIVE AGGREGATE, FDR	2326.00 TON
0040	307-12254	FULL DEPTH RECLAMATION	162349.00 SYS
0041	308-12259	STABILIZING MATERIAL, ASPHALT EMULSION	2138.00 TON
0042	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	14935.00 TON
0043	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	34568.00 TON
0044	401-10259	JOINT ADHESIVE, INTERMEDIATE	77189.00 LFT
0045	401-11785	LIQUID ASPHALT SEALANT	77189.00 LFT
0046	401-12439	VOID REDUCING ASPHALT MEMBRANE	77189.00 LFT
0047	406-05520	ASPHALT FOR TACK COAT	57.00 TON
0048	417-12211	COLD CENTRAL PLANT RECYCLING	35746.00 SYS
0049	417-12213	STABILIZING MATERIAL, ASPHALT EMULSION, CCPR	138.00 TON
0050	601-01740	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 4	1.00EACH
0051	601-02241	GUARDRAIL, REMOVE	875.00 LFT
0052	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	838.00 LFT
0053	601-12287	GUARDRAIL, MGS, LONG SPAN, TYPE 1	4.00EACH
0054	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	1.00EACH
0055	601-94689	GUARDRAIL, END TREATMENT, OS	15.00EACH
0056	605-06145	CURB AND GUTTER, B, CONCRETE	2883.00 LFT
0057	610-07487	HMA FOR APPROACHES, TYPE B	2494.00 TON
0058	610-08446	PCCP FOR APPROACHES, 6 IN.	122.00 SYS
0059	611-06497	MAILBOX ASSEMBLY, SINGLE	38.00EACH
0060	611-06498	MAILBOX ASSEMBLY, DOUBLE	8.00EACH
0061	615-06490	RIGHT-OF-WAY MARKER	298.00EACH
0062	615-06527	MONUMENT, SECTION CORNER	22.00EACH
0063	616-05688	RIPRAP, CLASS 1	99.00 TON
0064	616-05689	RIPRAP, CLASS 2	123.00 TON
0065	616-06405	RIPRAP, REVETMENT	46.00 TON
0066	616-06451	RIPRAP, UNIFORM	791.00 TON
0067	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	1512.00 SYS
0068	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.00EACH

0069	621-06545	FERTILIZER	30.00 TON
0070	621-06553	SEED MIXTURE R	15290.00 LBS
0071	621-06565	MULCHING MATERIAL	150.00 TON
0072	621-06574	SODDING	18669.00 SYS
0073	621-06575	SODDING, NURSERY	6127.00 SYS
0074	628-09403	FIELD OFFICE, C	32.00 MOS
0075	628-11729	CELLULAR TELEPHONE, TYPE A	1.00EACH
0076	628-11730	CELLULAR TELEPHONE, TYPE B	1.00EACH
0077	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00 DOL
0078	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00 DOL
0079	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	64.00 MOS
0080	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00EACH
0081	714-11102	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 5 FT. X 2 FT.	40.00 LFT
0082	714-11193	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 4 FT. X 2 FT.	51.00 LFT
0083	714-96273	HEADWALL RECONSTRUCT	1.00 LS
0084	715-03475	SAFETY METAL END SECTION, 4:1, DIA 15 IN.	148.00EACH
0085	715-03476	SAFETY METAL END SECTION, 4:1, DIA 24 IN.	6.00EACH
0086	715-03584	SAFETY METAL END SECTION, 4:1, DIA 18 IN.	1.00EACH
0087	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	104956.00 LFT
0088	715-05146	PIPE, TYPE 2, CIRCULAR, 6 IN.	5482.00 LFT
0089	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	1097.00 LFT
0090	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	5178.00 LFT
0091	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	161.00 LFT
0092	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	272.00 LFT
0093	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	70.00 LFT
0094	715-09762	GRATED BOX END SECTION, I, 4:1, MIN. AREA 14.14 SFT	4.00EACH
0095	718-06526	HMA FOR UNDERDRAINS	18.00 TON
0096	718-06528	OUTLET PROTECTOR, 1	144.00EACH
0097	718-06528	OUTLET PROTECTOR, 1	187.00EACH
0098	718-12306	GEOTEXTILE FOR UNDERDRAIN, TYPE 1B	98902.00 SYS
0099	718-52610	AGGREGATE FOR UNDERDRAINS	6325.00 CYS
0100	720-08617	INLET, INTAKE RISER	16.00EACH
0101	720-44000	CASTING, ADJUST TO GRADE	1.00EACH
0102	720-45030	INLET, E7	7.00EACH
0103	720-94432	MANHOLE, C7	5.00EACH
0104	801-04308	ROAD CLOSURE SIGN ASSEMBLY	18.00EACH
0105	801-06625	DETOUR ROUTE MARKER ASSEMBLY	42.00EACH

0106	801-06640	CONSTRUCTION SIGN, A	70.00 EACH
0107	801-06775	MAINTAINING TRAFFIC	1.00 LS
0108	801-07119	BARRICADE, III-B	256.00 LFT
0109	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	1243.00 LFT
0110	802-05703	SIGN POST, SQUARE TYPE 3 REINFORCED ANCHOR BASE	372.00 LFT
0111	802-07057	SIGN, PANEL, WITH LEGEND	88.00 SFT
0112	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	523.00 SFT
0113	802-09839	SIGN, DOUBLE-FACED, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	55.00 SFT
0114	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	694.00 LFT
0115	805-78785	SIGNAL DETECTOR HOUSING	2.00 EACH
0116	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	239.00 LFT
0117	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	11053.00 LFT
0118	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	50000.00 LFT
0119	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	46.00 LFT
0120	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS
0121	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	109265.00 LFT
0122	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	806.00 EACH
0123	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	806.00 EACH

Call: 321

Contract: R -39089-A

Section No.: 1 BIKE AND PEDESTRIAN FACILITIES

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0009	202-52710	SIDEWALK CONCRETE, REMOVE	26.00	SYS
0010	202-91840	FENCE, CHAIN. LINK, REMOVE	420.00	LFT
0011	202-99080	CONCRETE, REMOVE	10.00	CYS
0012	203-02000	EXCAVATION, COMMON	3883.00	CYS
0013	203-02070	BORROW	1484.00	CYS
0014	205-12108	STORMWATER MANAGEMENT BUDGET	23300.00	DOL
0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0016	205-12618	SWQCP PREPARATION	1.00	LS
0017	207-08264	SUBGRADE TREATMENT, TYPE II	196.00	SYS
0018	207-08266	SUBGRADE TREATMENT, TYPE III	6217.00	SYS
0019	207-09895	SUBGRADE TREATMENT, TYPE V	124.00	SYS
0020	211-06467	AGGREGATE FOR END BENT BACKFILL	12.00	CYS
0021	301-12234	COMPACTED AGGREGATE NO. 53	1635.00	CYS
0022	406-05520	ASPHALT FOR TACK COAT	2.00	TON
0023	601-02241	GUARDRAIL, REMOVE	26.00	LFT
0024	603-92636	FENCE, CHAIN LINK, 72 IN.	587.00	LFT
0025	604-05528	HMA FOR SIDEWALK	870.00	TON
0026	604-06070	SIDEWALK, CONCRETE	8.00	SYS
0027	604-08086	CURB RAMP, CONCRETE	77.00	SYS
0028	604-12083	DETECTABLE WARNING SURFACES	10.00	SYS
0029	610-07487	HMA FOR APPROACHES, TYPE B	29.00	TON
0030	610-09108	PCCP FOR APPROACHES, 9 IN.	154.00	SYS
0031	616-06405	RIPRAP, REVETMENT	24.00	TON

0032	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	54.00	SYS
0033	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0034	621-06545	FERTILIZER	1.00	TON
0035	621-06553	SEED MIXTURE R	278.00	LBS
0036	621-06565	MULCHING MATERIAL	3.00	TON
0037	621-06570	TOPSOIL	729.00	CYS
0038	622-05645	PLANT, DECIDUOUS TREE, MULTI-STEM, 72 TO 96 IN.	25.00	EACH
0039	712-09730	BOARDWALK	400.00	LFT
0040	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	61.00	LFT
0041	715-05407	PIPE, END BENT DRAIN, 6 IN.	50.00	LFT
0042	715-46000	PIPE END SECTION, DIAMETER 12 IN.	4.00	EACH
0043	718-12308	GEOTEXTILE FOR UNDERDRAIN, TYPE 2B	32.00	SYS
0044	801-06640	CONSTRUCTION SIGN, A	12.00	EACH
0045	801-06645	CONSTRUCTION SIGN, B	15.00	EACH
0046	801-06775	MAINTAINING TRAFFIC	1.00	LS
0047	801-07119	BARRICADE, III-B	204.00	LFT
0048	802-03896	BOLLARD	16.00	EACH
0049	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	116.00	LFT
0050	802-07060	SIGN, SHEET, RELOCATE	3.00	EACH
0051	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	92.00	SFT
0052	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	2.00	EACH
0053	805-11771	SIGNAL POLE, PEDESTAL, 16 FT	2.00	EACH
0054	805-11799	RECTANGULAR RAPID FLASHING BEACON	2.00	EACH
0055	805-78370	PEDESTRIAN PUSH BUTTON, NON-APS	2.00	EACH
0056	808-10099	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 24 IN.	137.00	LFT
0057	808-11516	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, PEDX	4.00	EACH

Call: 331

Contract: R -39110-D

Section No.: 1 BIKE AND PEDESTRIAN FACILITIES

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	1993.00	SYS
0013	205-12108	STORMWATER MANAGEMENT BUDGET	21000.00	DOL
0014	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0015	205-12618	SWQCP PREPARATION	1.00	LS
0016	207-08264	SUBGRADE TREATMENT, TYPE II	666.00	SYS
0017	207-09935	SUBGRADE TREATMENT, TYPE IC	589.00	SYS
0018	211-09265	STRUCTURE BACKFILL, TYPE 2	76.00	CYS
0019	302-06464	SUBBASE FOR PCCP	154.00	CYS
0020	304-12623	HMA PATCHING FULL DEPTH TYPE B	89.00	TON
0021	306-08034	MILLING, ASPHALT, 1 1/2 IN.	8474.00	SYS
0022	306-08039	MILLING, ASPHALT REMOVAL	1159.00	SYS
0023	401-06264	PROFILOGRAPH, HMA	1.00	LS
0024	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	700.00	TON
0025	401-10258	JOINT ADHESIVE, SURFACE	4813.00	LFT
0026	401-11785	LIQUID ASPHALT SEALANT	4813.00	LFT
0027	406-05520	ASPHALT FOR TACK COAT	3.00	TON
0028	503-03489	RETROFITTED TIE BARS	32.00	EACH
0029	503-12476	JOINTED REINFORCED CONCRETE PAVEMENT 12 IN.	300.00	SYS
0030	503-12478	TERMINAL JOINT, TYPE PCCP	109.00	LFT
0031	503-12479	EXPANSION JOINT WITH LOAD TRANSFER	109.00	LFT

0032	604-06070	SIDEWALK, CONCRETE	1132.00	SYS
0033	604-08086	CURB RAMP, CONCRETE	87.00	SYS
0034	604-12083	DETECTABLE WARNING SURFACES	27.00	SYS
0035	604-44251	STEPS, CONCRETE	4.00	CYS
0036	605-06090	CURB, INTEGRAL CONCRETE	104.00	LFT
0037	605-06120	CURB, CONCRETE	1905.00	LFT
0038	605-06205	CENTER CURB, B CONCRETE	8.00	LFT
0039	605-09131	CURB AND GUTTER, TURNOUT CONCRETE	7.00	LFT
0040	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	532.00	SYS
0041	610-08446	PCCP FOR APPROACHES, 6 IN.	153.00	SYS
0042	610-09108	PCCP FOR APPROACHES, 9 IN.	268.00	SYS
0043	611-06497	MAILBOX ASSEMBLY, SINGLE	8.00	EACH
0044	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0045	621-06560	MULCHED SEEDING U	3984.00	SYS
0046	621-06570	TOPSOIL	248.00	CYS
0047	628-09402	FIELD OFFICE, B	9.00	MOS
0048	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0049	628-11977	COMPUTER SYSTEM	1.00	EACH
0050	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	6.00	EACH
0051	702-51863	FIELD DRILLED HOLE IN CONCRETE	534.00	EACH
0052	703-06029	REINFORCING BARS, EPOXY COATED	19814.00	LBS
0053	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	100.00	EACH
0054	704-51002	CONCRETE, C, SUPERSTRUCTURE	24.00	CYS
0055	709-51821	SURFACE SEAL	1.00	LS
0056	715-05146	PIPE, TYPE 2, CIRCULAR, 6 IN.	20.00	LFT
0057	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	212.00	LFT
0058	720-44000	CASTING, ADJUST TO GRADE	3.00	EACH
0059	720-45045	INLET, J10	4.00	EACH
0060	720-45055	INLET, M10	3.00	EACH
0061	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	76.00	SFT
0062	724-12103	PRE-COMPRESSED FOAM JOINT	109.00	LFT
0063	801-04308	ROAD CLOSURE SIGN ASSEMBLY	3.00	EACH
0064	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	6600.00	LFT
0065	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2500.00	LFT
0066	801-06640	CONSTRUCTION SIGN, A	16.00	EACH
0067	801-06645	CONSTRUCTION SIGN, B	9.00	EACH
0068	801-06775	MAINTAINING TRAFFIC	1.00	LS

0069	801-07118	BARRICADE, III-A	280.00	LFT
0070	801-07612	TEMPORARY PAVEMENT MARKING, 24 IN.	28.00	LFT
0071	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	235.00	LFT
0072	801-94295	SIGNAL HEAD RELOCATE	2.00	EACH
0073	802-04089	SIGN, SHEET, REMOVE	4.00	EACH
0074	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	132.00	LFT
0075	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	71.00	SFT
0076	805-08214	CONDUIT, PVC, 2 IN. SCHEDULE 40	1140.00	LFT
0077	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	1440.00	LFT
0078	805-78785	SIGNAL DETECTOR HOUSING	3.00	EACH
0079	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	480.00	LFT
0080	807-02191	HANDHOLE LIGHTING	2.00	EACH
0081	807-04653	LIGHTING FOUNDATION	7.00	EACH
0082	807-04654	LIGHT POLE	11.00	EACH
0083	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	843.00	LFT
0084	807-12203	LUMINAIRE, LOW LUMEN-LOW MOUNTING HEIGHT ROADWAY	11.00	EACH
0085	807-86805	SERVICE POINT, I	1.00	EACH
0086	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	235.00	LFT
0087	807-86910	CONNECTOR KIT, UNFUSED	17.00	EACH
0088	807-86915	CONNECTOR KIT, FUSED	17.00	EACH
0089	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	12.00	EACH
0090	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	24.00	EACH
0091	807-86930	INSULATION LINK, NON-WATERPROOFED	8.00	EACH
0092	807-86935	INSULATION LINK, WATERPROOFED	26.00	EACH
0093	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	8.00	SYS
0094	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	559.00	LFT
0095	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	4350.00	LFT
0096	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	4500.00	LFT
0097	808-06716	LINE, REMOVE	1950.00	LFT
0098	808-06723	PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW	19.00	EACH
0099	808-06724	PAVEMENT MESSAGE MARKING, PAINT, ONLY	2.00	EACH
0100	808-75072	TRANSVERSE MARKING, PAINT, CROSSHATCH LINE, WHITE 24 IN.	475.00	LFT
0101	808-75100	TRANSVERSE MARKING, PAINT, CROSSWALK LINE, WHITE, 6 IN.	500.00	LFT
0102	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	150.00	LFT
0103	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	17.00	EACH
0104	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	2.00	EACH

Call: 341

Contract: R -39293-A

Section No.: 1 PAVEMENT REPLACEMENT

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	201-02245	TREE 6 IN., REMOVE	1.00EACH
0012	201-02255	TREE 18 IN., REMOVE	1.00EACH
0013	201-02260	TREE 30 IN., REMOVE	3.00EACH
0014	201-02265	TREE 48 IN., REMOVE	3.00EACH
0015	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0016	202-02240	PAVEMENT REMOVAL	21892.00 SYS
0017	202-02271	HEADWALL, REMOVE	2.00EACH
0018	202-02278	CURB, CONCRETE, REMOVE	2407.00 LFT
0019	202-02279	CURB AND GUTTER, REMOVE	88.00 LFT
0020	202-02637	PIPE ABANDON AND GROUT FILL	12.00 LFT
0021	202-05545	REGULATED MATERIALS, DISPOSE, TYPE C	272.00 CYS
0022	202-05550	REGULATED MATERIALS, REMOVE, TYPE C	272.00 CYS
0023	202-05555	REGULATED MATERIALS, TRANSPORT, TYPE C	272.00 CYS
0024	202-05571	TESTING FOR WASTES	1.00EACH
0025	202-52710	SIDEWALK CONCRETE, REMOVE	4638.00 SYS
0026	202-86946	HANDHOLE, REMOVE	1.00EACH
0027	202-91385	INLET, REMOVE	11.00EACH
0028	202-93047	MANHOLE, REMOVE	1.00EACH
0029	202-93994	SIGNAL MAST ARM AND POLE, REMOVE	4.00EACH
0030	202-93995	SIGNAL POLE FOUNDATION, REMOVE	4.00EACH
0031	202-96022	CONCRETE FOUNDATION, REMOVE	3.00EACH

0032	202-96133	PIPE, REMOVE	588.00	LFT
0033	203-02000	EXCAVATION, COMMON	19223.00	CYS
0034	204-12510	MONITORING WELL	2.00	EACH
0035	205-12108	STORMWATER MANAGEMENT BUDGET	37093.00	DOL
0036	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0037	205-12618	SWQCP PREPARATION	1.00	LS
0038	207-08264	SUBGRADE TREATMENT, TYPE II	7695.00	SYS
0039	207-12498	SUBGRADE TREATMENT, TYPE ID	19223.00	SYS
0040	211-09264	STRUCTURE BACKFILL, TYPE 1	13191.00	CYS
0041	211-09265	STRUCTURE BACKFILL, TYPE 2	154.00	CYS
0042	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	6.00	CYS
0043	214-11796	GEOGRID, TYPE IB	1512.00	SYS
0044	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	6111.00	SYS
0045	301-12233	COMPACTED AGGREGATE NO. 8	3056.00	CYS
0046	301-12234	COMPACTED AGGREGATE NO. 53	2714.00	CYS
0047	302-07455	DENSE GRADED SUBBASE	563.00	CYS
0048	303-08210	COMPACTED AGGREGATE NO. 53 TEMPORARY FOR DRIVEWAYS	963.00	TON
0049	304-12625	HMA PATCHING FULL DEPTH TYPE C	228.00	TON
0050	306-08034	MILLING, ASPHALT, 1 1/2 IN.	7005.00	SYS
0051	306-08039	MILLING, ASPHALT REMOVAL	83.00	SYS
0052	306-08041	MILLING, PCCP	111.00	SYS
0053	306-08432	MILLING, APPROACH	153.00	SYS
0054	401-06264	PROFILOGRAPH, HMA	1.00	LS
0055	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1734.00	TON
0056	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	1917.00	TON
0057	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	3056.00	TON
0058	401-10258	JOINT ADHESIVE, SURFACE	22229.00	LFT
0059	401-10259	JOINT ADHESIVE, INTERMEDIATE	17723.00	LFT
0060	401-11785	LIQUID ASPHALT SEALANT	22229.00	LFT
0061	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	3478.00	TON
0062	406-05520	ASPHALT FOR TACK COAT	2.10	TON
0063	503-12480	TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT	96.00	SFT
0064	507-08271	JOINTS IN PCCP, FILLED	91.00	LFT
0065	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	1.00	EACH
0066	601-01700	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 1	1.00	EACH
0067	601-02241	GUARDRAIL, REMOVE	969.00	LFT
0068	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	676.00	LFT

0069	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	3.00 EACH
0070	601-94689	GUARDRAIL, END TREATMENT, OS	3.00 EACH
0071	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	19.00 LFT
0072	602-06729	BARRIER, DELINEATOR	10.00 EACH
0073	604-06070	SIDEWALK, CONCRETE	4560.00 SYS
0074	604-08086	CURB RAMP, CONCRETE	382.00 SYS
0075	604-12083	DETECTABLE WARNING SURFACES	72.00 SYS
0076	605-06140	CURB AND GUTTER, CONCRETE	10310.00 LFT
0077	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	2213.00 LFT
0078	610-07487	HMA FOR APPROACHES, TYPE B	841.00 TON
0079	610-08446	PCCP FOR APPROACHES, 6 IN.	1539.00 SYS
0080	610-09108	PCCP FOR APPROACHES, 9 IN.	1824.00 SYS
0081	611-06497	MAILBOX ASSEMBLY, SINGLE	8.00 EACH
0082	611-06498	MAILBOX ASSEMBLY, DOUBLE	3.00 EACH
0083	615-06490	RIGHT-OF-WAY MARKER	10.00 EACH
0084	615-06527	MONUMENT, SECTION CORNER	3.00 EACH
0085	616-05688	RIPRAP, CLASS 1	240.00 TON
0086	616-05689	RIPRAP, CLASS 2	387.00 TON
0087	616-06405	RIPRAP, REVETMENT	145.00 TON
0088	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	639.00 SYS
0089	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	547.00 SYS
0090	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00 EACH
0091	621-06554	SEED MIXTURE U	3.00 LBS
0092	621-06574	SODDING	10392.00 SYS
0093	628-09403	FIELD OFFICE, C	30.00 MOS
0094	702-51015	CONCRETE, B, FOOTINGS	22.00 CYS
0095	703-06028	REINFORCING BARS	612.00 LBS
0096	709-51821	SURFACE SEAL	1.00 LS
0097	714-11191	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 5 FT. X 4 FT.	176.00 LFT
0098	715-05024	PIPE, TYPE 2, CIRCULAR, 36 IN.	22.00 LFT
0099	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	10122.00 LFT
0100	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	3454.00 LFT
0101	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	296.00 LFT
0102	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	312.00 LFT
0103	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	653.00 LFT
0104	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	704.00 LFT
0105	715-05159	PIPE, TYPE 2, CIRCULAR, 42 IN.	649.00 LFT

0106	715-05161	PIPE, TYPE 2, CIRCULAR, 48 IN.	549.00	LFT
0107	715-05163	PIPE, TYPE 2 CIRCULAR 60 IN	2576.00	LFT
0108	715-05168	PIPE, TYPE 3, CIRCULAR, 12 IN.	54.00	LFT
0109	715-05171	PIPE, TYPE 3, CIRCULAR, 18 IN.	45.00	LFT
0110	715-05412	PIPE, SANITARY SEWER, 15 IN.	72.00	LFT
0111	715-09064	VIDEO INSPECTION FOR PIPE	9193.00	LFT
0112	715-09843	BYPASS PUMPING	1.00	LS
0113	715-46000	PIPE END SECTION, DIAMETER 12 IN.	3.00	EACH
0114	715-46005	PIPE END SECTION, DIAMETER 15 IN.	1.00	EACH
0115	715-46010	PIPE END SECTION, DIAMETER 18 IN.	2.00	EACH
0116	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	8361.00	SYS
0117	718-52610	AGGREGATE FOR UNDERDRAINS	1483.00	CYS
0118	720-08241	MANHOLE, K15 MODIFIED	1.00	EACH
0119	720-09768	CATCH BASIN, TYPE HA5	1.00	EACH
0120	720-10114	SANITARY DROP MANHOLE	2.00	EACH
0121	720-44000	CASTING, ADJUST TO GRADE	3.00	EACH
0122	720-44040	CASTING, 7, FURNISH AND ADJUST TO GRADE	1.00	EACH
0123	720-44080	CASTING, 15, FURNISH AND ADJUST TO GRADE	1.00	EACH
0124	720-45030	INLET, E7	2.00	EACH
0125	720-45042	INLET, HA5	5.00	EACH
0126	720-45410	MANHOLE, C4	3.00	EACH
0127	720-93501	MANHOLE, L4	3.00	EACH
0128	720-95335	MANHOLE, M4	15.00	EACH
0129	720-95422	MANHOLE, J4	10.00	EACH
0130	720-98174	INLET, B15	32.00	EACH
0131	720-98555	INLET, C15	21.00	EACH
0132	720-99416	CATCH BASIN, B15	19.00	EACH
0133	720-99417	CATCH BASIN, C15	20.00	EACH
0134	722-01066	HYDRODEMOLITION	949.00	SYS
0135	722-12380	BRIDGE DECK OVERLAY, BUDGET	15505.00	DOL
0136	722-12382	TRANSVERSE GROOVING	1032.00	SYS
0137	722-12463	BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY	839.00	SYS
0138	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	378.00	SFT
0139	801-03290	CONSTRUCTION SIGN, C	2.00	EACH
0140	801-04308	ROAD CLOSURE SIGN ASSEMBLY	47.00	EACH
0141	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	6798.00	LFT
0142	801-06625	DETOUR ROUTE MARKER ASSEMBLY	12.00	EACH

0143	801-06640	CONSTRUCTION SIGN, A	27.00 EACH
0144	801-06645	CONSTRUCTION SIGN, B	23.00 EACH
0145	801-06775	MAINTAINING TRAFFIC	1.00 LS
0146	801-07118	BARRICADE, III-A	400.00 LFT
0147	801-07119	BARRICADE, III-B	128.00 LFT
0148	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00 EACH
0149	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	912.00 LFT
0150	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	473.00 SFT
0151	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	92.00 SFT
0152	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	17.00 SFT
0153	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	4.00 EACH
0154	805-02079	CONTROLLER CABINET FOUNDATION, A	1.00 EACH
0155	805-02445	CONTROLLER AND CABINET, P1	1.00 EACH
0156	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	4.00 EACH
0157	805-05405	SIGNAL POLE, PEDESTAL, 4FT	1.00 EACH
0158	805-11375	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 25 FT.	2.00 EACH
0159	805-11376	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 30 FT.	2.00 EACH
0160	805-11383	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, A	4.00 EACH
0161	805-11744	HANDHOLE SIGNAL TYPE 2	4.00 EACH
0162	805-11813	CONDUIT, PVC, 2 IN. SCHEDULE 80	3844.00 LFT
0163	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	800.00 LFT
0164	805-11817	PEDESTRIAN PUSH BUTTON, APS	8.00 EACH
0165	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	8.00 EACH
0166	805-78412	SIGNAL POLE, PEDESTAL, 9FT	4.00 EACH
0167	805-78445	SIGNAL SERVICE	1.00 EACH
0168	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	18.00 LFT
0169	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	603.00 LFT
0170	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	1210.00 LFT
0171	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	1002.00 LFT
0172	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	122.00 LFT
0173	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	646.00 LFT
0174	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	507.00 LFT
0175	805-78785	SIGNAL DETECTOR HOUSING	2.00 EACH
0176	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	751.00 LFT
0177	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	1097.00 LFT
0178	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	3613.00 LFT
0179	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	65.00 LFT

0180	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	516.00	LFT
0181	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	258.00	LFT
0182	808-12032	GROOVING FOR PAVEMENT MARKINGS	14079.00	LFT
0183	808-12273	TRANSVERSE MARKING, THERMOPLASTIC, PARKING LINE, WHITE 4 IN.	141.00	LFT
0184	808-12274	TRANSVERSE MARKING, THERMOPLASTIC, PARKING LINE, BLUE 4 IN.	44.00	LFT
0185	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	305.00	LFT
0186	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	10161.00	LFT
0187	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	335.00	LFT
0188	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	25.00	EACH
0189	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	141.00	EACH
0190	808-97664	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ADA ACCESSIBLE SYMBOL	2.00	EACH

Call: 341

Contract: R -39293-A

Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED CONCRETE

Line

Item No	Item Code	Description	Quantity	Unit
0191	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	1032.00	SYS

Call: 341

Contract: R -39293-A

Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED CONCRETE

Line

Item No	Item Code	Description	Quantity	Unit
0192	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	1032.00	SYS

Call: 351

Contract: R -39788-A

Section No.: 1

SMALL STRUSTURE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	203-02000	EXCAVATION, COMMON	812.00	CYS
0013	203-02010	EXCAVATION, ROCK	265.00	CYS
0014	205-11626	PUMP AROUND	3.00	EACH
0015	205-12108	STORMWATER MANAGEMENT BUDGET	12518.00	DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	205-12618	SWQCP PREPARATION	1.00	LS
0018	206-51220	EXCAVATION, WET	50.00	CYS
0019	207-12498	SUBGRADE TREATMENT, TYPE ID	1223.00	SYS
0020	211-02050	B BORROW	88.00	CYS
0021	211-09265	STRUCTURE BACKFILL, TYPE 2	64.00	CYS
0022	211-09268	STRUCTURE BACKFILL, TYPE 5	346.00	CYS
0023	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	75.00	SYS
0024	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	51.00	SYS
0025	301-12233	COMPACTED AGGREGATE NO. 8	25.00	CYS
0026	301-12234	COMPACTED AGGREGATE NO. 53	100.00	CYS
0027	303-01180	COMPACTED AGGREGATE NO. 53	246.00	TON
0028	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1195.00	SYS
0029	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	179.00	TON
0030	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	137.00	TON
0031	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	165.00	TON

0032	401-10258	JOINT ADHESIVE, SURFACE	715.00	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	795.00	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	715.00	LFT
0035	402-07451	HMA WEDGE AND LEVEL, TYPE B	19.00	TON
0036	406-05520	ASPHALT FOR TACK COAT	3.00	TON
0037	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	319.00	LFT
0038	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	1.00	EACH
0039	601-94689	GUARDRAIL, END TREATMENT, OS	5.00	EACH
0040	615-06490	RIGHT-OF-WAY MARKER	22.00	EACH
0041	615-06505	MONUMENT, B	11.00	EACH
0042	615-06510	MONUMENT, C	1.00	EACH
0043	616-05688	RIPRAP, CLASS 1	160.00	TON
0044	616-06405	RIPRAP, REVETMENT	301.00	TON
0045	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	591.00	SYS
0046	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0047	621-06559	MULCHED SEEDING R	2450.00	SYS
0048	621-06567	WATER	11.00	KGAL
0049	621-06574	SODDING	517.00	SYS
0050	628-09403	FIELD OFFICE, C	12.00	MOS
0051	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0052	714-11177	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 8 FT. X 4 FT.	37.00	LFT
0053	714-11304	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 7 FT. X 4 FT.	38.00	LFT
0054	714-12520	STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS, 14 FT X 4 FT	84.00	LFT
0055	801-04308	ROAD CLOSURE SIGN ASSEMBLY	12.00	EACH
0056	801-06625	DETOUR ROUTE MARKER ASSEMBLY	30.00	EACH
0057	801-06640	CONSTRUCTION SIGN, A	23.00	EACH
0058	801-06775	MAINTAINING TRAFFIC	1.00	LS
0059	801-07119	BARRICADE, III-B	288.00	LFT
0060	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	61.00	LFT
0061	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	28.00	SFT
0062	802-91122	SIGN GROUND MOUNTED RESET	1.00	EACH
0063	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	77.00	LFT
0064	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1430.00	LFT
0065	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1125.00	LFT
0066	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	8.00	EACH
0067	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	15.00	EACH

Call: 361

Contract: R -39825-A

Section No.: 1 PAVEMENT REPLACEMENT

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	3.00EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	3.00EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0005	109-08360	CONTRACT LIENS	1.00 DOL
0006	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0007	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0008	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0009	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0010	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0011	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0012	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0013	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0014	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0015	202-02240	PAVEMENT REMOVAL	33278.00 SYS
0016	202-02279	CURB AND GUTTER, REMOVE	13450.00 LFT
0017	202-03729	REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	682.00 LFT
0018	202-52710	SIDEWALK CONCRETE, REMOVE	899.00 SYS
0019	202-90747	RETAINING WALL, REMOVE	87.00 LFT
0020	202-91385	INLET, REMOVE	40.00EACH
0021	202-93047	MANHOLE, REMOVE	15.00EACH
0022	202-93741	GUARDRAIL, END TREATMENT, REMOVE	1.00EACH
0023	202-96133	PIPE, REMOVE	2467.00 LFT
0024	202-96328	FOUNDATION, STREET LIGHT, REMOVE	97.00EACH
0025	202-97009	FIRE HYDRANT ASSEMBLY, REMOVE	28.00EACH
0026	202-99080	CONCRETE, REMOVE	6.10 CYS
0027	202-99626	FOUNDATION FOR SIGNING, REMOVE	2.00EACH
0028	203-02000	EXCAVATION, COMMON	3622.00 CYS
0029	203-02070	BORROW	801.00 CYS
0030	205-12108	STORMWATER MANAGEMENT BUDGET	33000.00 DOL
0031	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS

0032	205-12618	SWQCP PREPARATION	1.00	LS
0033	207-08264	SUBGRADE TREATMENT, TYPE II	7767.00	SYS
0034	207-08268	SUBGRADE TREATMENT, TYPE IV	1554.00	SYS
0035	207-09935	SUBGRADE TREATMENT, TYPE IC	39870.00	SYS
0036	211-09264	STRUCTURE BACKFILL, TYPE 1	3333.00	CYS
0037	211-09265	STRUCTURE BACKFILL, TYPE 2	7369.00	CYS
0038	211-09266	STRUCTURE BACKFILL, TYPE 3	93.00	CYS
0039	211-09268	STRUCTURE BACKFILL, TYPE 5	1519.00	CYS
0040	214-11796	GEOGRID, TYPE IB	3088.00	SYS
0041	214-12237	GEOTEXTILE FOR PAVEMENT TYPE 1B	33225.00	SYS
0042	302-07455	DENSE GRADED SUBBASE	3342.00	CYS
0043	303-01180	COMPACTED AGGREGATE NO. 53	6.00	TON
0044	303-08210	COMPACTED AGGREGATE NO. 53 TEMPORARY FOR DRIVEWAYS	1050.00	TON
0045	401-06264	PROFILOGRAPH, HMA	1.00	LS
0046	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	2139.00	TON
0047	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	4278.00	TON
0048	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	10474.00	TON
0049	401-10258	JOINT ADHESIVE, SURFACE	11125.00	LFT
0050	401-10259	JOINT ADHESIVE, INTERMEDIATE	11125.00	LFT
0051	401-11785	LIQUID ASPHALT SEALANT	11125.00	LFT
0052	402-07451	HMA WEDGE AND LEVEL, TYPE B	42.00	TON
0053	402-10086	HMA FOR TEMPORARY PAVEMENT, C	124.00	TON
0054	406-05520	ASPHALT FOR TACK COAT	25.00	TON
0055	601-02241	GUARDRAIL, REMOVE	103.00	LFT
0056	601-02800	GUARDRAIL, TRANSITION, TGT	1.00	EACH
0057	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	69.00	LFT
0058	604-02007	SIDEWALK, CONCRETE, RECONSTRUCT	197.00	SYS
0059	604-04452	LIMESTONE	1000.00	CFT
0060	604-06070	SIDEWALK, CONCRETE	7420.00	SYS
0061	604-08086	CURB RAMP, CONCRETE	752.00	SYS
0062	604-11975	SIDEWALK, CONCRETE, RE-LAY	11.00	SYS
0063	604-12083	DETECTABLE WARNING SURFACES	108.00	SYS
0064	604-44251	STEPS, CONCRETE	3.00	CYS
0065	605-06120	CURB, CONCRETE	83.00	LFT
0066	605-06140	CURB AND GUTTER, CONCRETE	12342.00	LFT
0067	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	466.00	LFT
0068	605-08636	CURB AND GUTTER, TURNOUT COMBINED	7.00	LFT

0069	610-07488	HMA FOR APPROACHES, TYPE C	2859.00 TON
0070	610-08446	PCCP FOR APPROACHES, 6 IN.	357.00 SYS
0071	610-09108	PCCP FOR APPROACHES, 9 IN.	3088.00 SYS
0072	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00 EACH
0073	615-06490	RIGHT-OF-WAY MARKER	44.00 EACH
0074	615-06505	MONUMENT, B	20.00 EACH
0075	615-06510	MONUMENT, C	2.00 EACH
0076	615-06520	MONUMENT, RE-ESTABLISH	1.00 EACH
0077	615-08351	PLAQUE	4.00 EACH
0078	616-06405	RIPRAP, REVETMENT	5.00 TON
0079	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	9.00 SYS
0080	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00 EACH
0081	621-06567	WATER	24.00 KGAL
0082	621-06570	TOPSOIL	720.00 CYS
0083	621-06574	SODDING	379.00 SYS
0084	621-06575	SODDING, NURSERY	6484.00 SYS
0085	622-04648	TREE GRATE	42.00 EACH
0086	622-05650	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 IN. TO 2.5 IN.	110.00 EACH
0087	628-09403	FIELD OFFICE, C	18.00 MOS
0088	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0089	702-51863	FIELD DRILLED HOLE IN CONCRETE	2.00 EACH
0090	710-09158	PATCHING CONCRETE STRUCTURES	735.00 SFT
0091	714-05562	RETAINING WALL	500.00 SFT
0092	715-01898	WATER MAIN, DUCTILE IRON, 10 IN.	16.00 LFT
0093	715-02185	WATER SERVICE LINE, 1.50 IN	11.00 LFT
0094	715-02433	VALVE, WITH BOX, RESTRAINED GATE, DUCTILE IRON, 12 IN.	26.00 EACH
0095	715-02529	VALVE, WITH BOX, RESTRAINED BUTTERFLY, DUCTILE IRON 16 IN.	4.00 EACH
0096	715-02531	VALVE, WITH BOX, RESTRAINED GATE, DUCTILE IRON, 6 IN.	7.00 EACH
0097	715-02532	VALVE, WITH BOX, RESTRAINED GATE, DUCTILE IRON, 8 IN.	6.00 EACH
0098	715-02574	WATER SERVICE CONNECTION, 2 IN.	1.00 EACH
0099	715-02874	CURB STOP AND BOX	14.00 EACH
0100	715-03053	METER PIT	39.00 EACH
0101	715-03053	METER PIT	3.00 EACH
0102	715-03053	METER PIT	93.00 EACH
0103	715-03053	METER PIT	1.00 EACH
0104	715-05024	PIPE, TYPE 2, CIRCULAR, 36 IN.	623.00 LFT
0105	715-05024	PIPE, TYPE 2, CIRCULAR, 36 IN.	312.00 LFT

0106	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	12706.00	LFT
0107	715-05146	PIPE, TYPE 2, CIRCULAR, 6 IN.	3.00	LFT
0108	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	2954.00	LFT
0109	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	1339.00	LFT
0110	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	2024.00	LFT
0111	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	393.00	LFT
0112	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	1260.00	LFT
0113	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	454.00	LFT
0114	715-05161	PIPE, TYPE 2, CIRCULAR, 48 IN.	124.00	LFT
0115	715-05161	PIPE, TYPE 2, CIRCULAR, 48 IN.	34.00	LFT
0116	715-05162	PIPE, TYPE 2, CIRCULAR, 54 IN.	10.00	LFT
0117	715-05165	PIPE, TYPE 2, CIRCULAR, 72 IN.	12.00	LFT
0118	715-05422	PIPE, SLOTTED DRAIN, 12 IN.	146.00	LFT
0119	715-05423	PIPE, SLOTTED DRAIN, 15 IN.	20.00	LFT
0120	715-05711	PIPE, SANITARY SEWER, 6 IN.	1490.00	LFT
0121	715-06651	WATER LINE, 2 IN	106.00	LFT
0122	715-07794	WATER MAIN CONNECTIONS	8.00	EACH
0123	715-07794	WATER MAIN CONNECTIONS	4.00	EACH
0124	715-07794	WATER MAIN CONNECTIONS	3.00	EACH
0125	715-07794	WATER MAIN CONNECTIONS	5.00	EACH
0126	715-07794	WATER MAIN CONNECTIONS	10.00	EACH
0127	715-07794	WATER MAIN CONNECTIONS	6.00	EACH
0128	715-07794	WATER MAIN CONNECTIONS	3.00	EACH
0129	715-09064	VIDEO INSPECTION FOR PIPE	9542.00	LFT
0130	715-09883	VALVE WITH BOX	4.00	EACH
0131	715-11571	WATER MAIN, DUCTILE IRON, 8 IN.	258.00	LFT
0132	715-11896	WATER SERVICE CONNECTION	3.00	EACH
0133	715-11896	WATER SERVICE CONNECTION	2.00	EACH
0134	715-46000	PIPE END SECTION, DIAMETER 12 IN.	1.00	EACH
0135	715-90573	VALVE, WITH BOX, RESTRAINED GATE, DUCTILE IRON, 4 IN.	6.00	EACH
0136	715-91739	WATER SERVICE LINE, 0.75 IN	281.00	LFT
0137	715-92253	SEWER SANITARY LATERAL RECONNECT	149.00	EACH
0138	715-92544	WATER MAIN, DUCTILE IRON, 12 IN.	7064.00	LFT
0139	715-92874	PIPE ENCASEMENT	22.00	LFT
0140	715-92874	PIPE ENCASEMENT	54.00	LFT
0141	715-92874	PIPE ENCASEMENT	175.00	LFT
0142	715-93403	WATER SERVICE CONNECTION, 0.75 IN.	169.00	EACH

0143	715-94530	ADJUST WATER VALVE TO GRADE	5.00 EACH
0144	715-94780	WATER MAIN, DUCTILE IRON, 6 IN.	178.00 LFT
0145	715-96629	WATER SERVICE LINE, 1 IN	137.00 LFT
0146	715-96669	WATER MAIN, DUCTILE IRON, 16 IN.	235.00 LFT
0147	715-98265	WATER MAIN, DUCTILE IRON, 4 IN.	129.00 LFT
0148	716-09396	PIPE INSTALLATION, TRENCHLESS, 2 IN.	109.00 LFT
0149	716-11716	PIPE INSTALLATION, TRENCHLESS,	2375.00 LFT
0150	716-11716	PIPE INSTALLATION, TRENCHLESS,	881.00 LFT
0151	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	3000.00 LFT
0152	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	10196.00 SYS
0153	718-52610	AGGREGATE FOR UNDERDRAINS	1624.00 CYS
0154	720-02442	PIPE PLUG EXISTING	11.00 EACH
0155	720-44025	CASTING, 4, FURNISH AND ADJUST TO GRADE	29.00 EACH
0156	720-45005	INLET, A2	1.00 EACH
0157	720-45205	CATCH BASIN, A2	3.00 EACH
0158	720-45265	PIPE CATCH BASIN, 15 IN.	18.00 EACH
0159	720-45275	PIPE CATCH BASIN, 24 IN.	1.00 EACH
0160	720-45410	MANHOLE, C4	35.00 EACH
0161	720-45415	MANHOLE, D4	3.00 EACH
0162	720-45416	MANHOLE, E4	4.00 EACH
0163	720-45425	MANHOLE, F4	1.00 EACH
0164	720-93409	INLET, B15 MODIFIED	20.00 EACH
0165	720-93411	INLET, C15 MODIFIED	3.00 EACH
0166	720-94432	MANHOLE, C7	1.00 EACH
0167	720-94612	MANHOLE, K4	3.00 EACH
0168	720-94713	CATCH BASIN, C15 MODIFIED	38.00 EACH
0169	720-95164	CATCH BASIN, B15 MODIFIED	4.00 EACH
0170	720-95422	MANHOLE, J4	11.00 EACH
0171	720-96999	FIRE HYDRANT ASSEMBLY	18.00 EACH
0172	720-98174	INLET, B15	11.00 EACH
0173	720-99416	CATCH BASIN, B15	45.00 EACH
0174	720-99417	CATCH BASIN, C15	2.00 EACH
0175	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	1935.00 SFT
0176	732-11770	AGGREGATE FOR DRAINAGE FILL	58.00 CYS
0177	732-11810	MODULAR BLOCK WALL	226.00 SFT
0178	732-11811	MODULAR BLOCK WALL ERECTION	226.00 SFT
0179	801-02595	CONTROLLER RESET TIMING	25.00 EACH

0180	801-04308	ROAD CLOSURE SIGN ASSEMBLY	26.00 EACH
0181	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	48843.00 LFT
0182	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	2.00 EACH
0183	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	467.00 LFT
0184	801-06625	DETOUR ROUTE MARKER ASSEMBLY	19.00 EACH
0185	801-06640	CONSTRUCTION SIGN, A	162.00 EACH
0186	801-06645	CONSTRUCTION SIGN, B	168.00 EACH
0187	801-06710	FLASHING ARROW SIGN	1690.00 DAY
0188	801-06775	MAINTAINING TRAFFIC	1.00 LS
0189	801-07118	BARRICADE, III-A	24.00 LFT
0190	801-07119	BARRICADE, III-B	468.00 LFT
0191	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	775.00 LFT
0192	801-94295	SIGNAL HEAD RELOCATE	6.00 EACH
0193	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	385.00 LFT
0194	802-07058	SIGN, SHEET, ASSEMBLY RELOCATE	153.00 EACH
0195	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	19.00 EACH
0196	802-07060	SIGN, SHEET, RELOCATE	12.00 EACH
0197	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	233.00 SFT
0198	802-09839	SIGN, DOUBLE-FACED, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	42.00 SFT
0199	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	96.00 SFT
0200	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	9.00 SFT
0201	802-74070	OVERHEAD SIGN STRUCTURE, CABLE SPAN, REMOVE	1.00 EACH
0202	802-91122	SIGN GROUND MOUNTED RESET	2.00 EACH
0203	802-93675	MARKER, HISTORIC, RESET	2.00 EACH
0204	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	3.00 EACH
0205	805-01579	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00 LS
0206	805-01842	HANDHOLE SIGNAL TYPE 1	13.00 EACH
0207	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	1765.00 LFT
0208	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00 LS
0209	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	24.00 EACH
0210	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	19.00 EACH
0211	805-08464	RADIO INTERCONNECT	4.00 EACH
0212	805-08493	RADIO INTERCONNECTION SYSTEM TESTING	1.00 LS
0213	805-11373	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 15 FT.	1.00 EACH
0214	805-11374	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 20 FT	1.00 EACH
0215	805-11376	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 30 FT.	2.00 EACH
0216	805-11377	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 35 FT.	3.00 EACH

0217	805-11378	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 40 FT.	1.00 EACH
0218	805-11383	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, A	7.00 EACH
0219	805-11384	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, B	1.00 EACH
0220	805-11570	RADIO ANTENNA	4.00 EACH
0221	805-11817	PEDESTRIAN PUSH BUTTON, APS	24.00 EACH
0222	805-78109	CONTROLLER AND CABINET, SECONDARY MENU DRIVEN, 8 PHASE	3.00 EACH
0223	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	17.00 EACH
0224	805-78412	SIGNAL POLE, PEDESTAL, 9FT	19.00 EACH
0225	805-78445	SIGNAL SERVICE	3.00 EACH
0226	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	110.00 LFT
0227	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	10082.00 LFT
0228	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	2600.00 LFT
0229	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	3645.00 LFT
0230	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	1240.00 LFT
0231	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	2370.00 LFT
0232	805-78785	SIGNAL DETECTOR HOUSING	19.00 EACH
0233	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	3379.00 LFT
0234	805-78925	CONTROLLER CABINET FOUNDATION, P1	3.00 EACH
0235	805-92504	LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	19.00 EACH
0236	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	4170.00 LFT
0237	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	4513.00 LFT
0238	808-06716	LINE, REMOVE	9091.00 LFT
0239	808-06723	PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW	3.00 EACH
0240	808-06724	PAVEMENT MESSAGE MARKING, PAINT, ONLY	3.00 EACH
0241	808-08258	TRANSVERSE MARKING	1552.00 LFT
0242	808-12032	GROOVING FOR PAVEMENT MARKINGS	12491.00 LFT
0243	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	3808.00 LFT
0244	808-75272	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	208.00 LFT
0245	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	633.00 LFT
0246	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	2284.00 LFT
0247	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	6.00 EACH
0248	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	3.00 EACH
0249	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	13.00 EACH
0250	808-97664	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ADA ACCESSIBLE SYMBOL	7.00 EACH

Call: 371

Contract: R -39831-A

Section No.: 1 ASPHALT RESURFACE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-02278	CURB, CONCRETE, REMOVE	736.00	LFT
0014	202-02279	CURB AND GUTTER, REMOVE	64.00	LFT
0015	202-06580	CONTAMINATED SOIL, REMOVE	108.00	CYS
0016	202-07083	REMOVAL	1.00	LS
0017	202-07603	TESTING FOR WASTES, TYPE C	6.00	EACH
0018	202-52710	SIDEWALK CONCRETE, REMOVE	62.00	SYS
0019	202-91385	INLET, REMOVE	6.00	EACH
0020	203-02000	EXCAVATION, COMMON	10.00	CYS
0021	203-02070	BORROW	6.00	CYS
0022	205-12108	STORMWATER MANAGEMENT BUDGET	3100.00	DOL
0023	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0024	205-12618	SWQCP PREPARATION	1.00	LS
0025	207-12498	SUBGRADE TREATMENT, TYPE ID	11031.00	SYS
0026	303-01180	COMPACTED AGGREGATE NO. 53	186.00	TON
0027	304-12625	HMA PATCHING FULL DEPTH TYPE C	3462.00	TON
0028	306-08034	MILLING, ASPHALT, 1 1/2 IN.	111028.00	SYS
0029	306-08038	MILLING, ASPHALT, 4 IN.	35982.00	SYS
0030	306-08432	MILLING, APPROACH	6180.00	SYS
0031	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	12135.00	TON

0032	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	4981.00 TON
0033	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	2594.00 TON
0034	401-10258	JOINT ADHESIVE, SURFACE	110576.00 LFT
0035	401-10259	JOINT ADHESIVE, INTERMEDIATE	22019.00 LFT
0036	401-11785	LIQUID ASPHALT SEALANT	110576.00 LFT
0037	406-05520	ASPHALT FOR TACK COAT	20.00 TON
0038	601-09146	IMPACT ATTENUATOR, CR1-W1, TL-2	1.00EACH
0039	604-06070	SIDEWALK, CONCRETE	82.00 SYS
0040	604-08086	CURB RAMP, CONCRETE	402.00 SYS
0041	604-12083	DETECTABLE WARNING SURFACES	69.00 SYS
0042	604-12084	DETECTABLE WARNING SURFACES, RETROFIT	3.00 SYS
0043	605-06120	CURB, CONCRETE	736.00 LFT
0044	605-06140	CURB AND GUTTER, CONCRETE	64.00 LFT
0045	610-07488	HMA FOR APPROACHES, TYPE C	538.00 TON
0046	615-06520	MONUMENT, RE-ESTABLISH	4.00EACH
0047	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00EACH
0048	621-06559	MULCHED SEEDING R	18.00 SYS
0049	621-06560	MULCHED SEEDING U	17.00 SYS
0050	628-09403	FIELD OFFICE, C	12.00 MOS
0051	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00EACH
0052	720-44000	CASTING, ADJUST TO GRADE	10.00EACH
0053	720-44000	CASTING, ADJUST TO GRADE	2.00EACH
0054	720-98174	INLET, B15	5.00EACH
0055	720-98555	INLET, C15	1.00EACH
0056	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00EACH
0057	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	11080.00 LFT
0058	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	140.00 LFT
0059	801-06640	CONSTRUCTION SIGN, A	82.00EACH
0060	801-06645	CONSTRUCTION SIGN, B	58.00EACH
0061	801-06775	MAINTAINING TRAFFIC	1.00 LS
0062	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	4.00EACH
0063	801-07118	BARRICADE, III-A	112.00 LFT
0064	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	1516.00 LFT
0065	801-11990	TEMPORARY CURB RAMP	2.00EACH
0066	801-12641	TEMPORARY ACCESSIBLE PEDESTRIAN PATH	24.00 SYS
0067	802-07058	SIGN, SHEET, ASSEMBLY RELOCATE	6.00EACH
0068	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	9785.00 LFT

0069	805-78785	SIGNAL DETECTOR HOUSING	28.00 EACH
0070	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	3605.00 LFT
0071	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	8401.00 LFT
0072	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	34359.00 LFT
0073	808-06716	LINE, REMOVE	1913.00 LFT
0074	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS
0075	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	226.00 LFT
0076	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	4645.00 LFT
0077	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	12446.00 LFT
0078	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	139.00 LFT
0079	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	502.00 LFT
0080	808-12032	GROOVING FOR PAVEMENT MARKINGS	93901.00 LFT
0081	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	33824.00 LFT
0082	808-75290	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 24 IN.	505.00 LFT
0083	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	533.00 LFT
0084	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	165.00 LFT
0085	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	15.00 EACH
0086	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	8.00 EACH
0087	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	809.00 EACH
0088	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	809.00 EACH

Call: 381

Contract: R -39882-A

Section No.: 1 INTERSECTION IMPROVEMENT

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0013	202-02240	PAVEMENT REMOVAL	198.00 SYS
0014	202-02279	CURB AND GUTTER, REMOVE	242.00 LFT
0015	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0016	202-52710	SIDEWALK CONCRETE, REMOVE	114.00 SYS
0017	202-86946	HANDHOLE, REMOVE	2.00 EACH
0018	202-90277	DETECTOR HOUSING, REMOVE	4.00 EACH
0019	202-91385	INLET, REMOVE	1.00 EACH
0020	202-93994	SIGNAL MAST ARM AND POLE, REMOVE	1.00 EACH
0021	202-93995	SIGNAL POLE FOUNDATION, REMOVE	1.00 EACH
0022	202-96133	PIPE, REMOVE	106.00 LFT
0023	203-02000	EXCAVATION, COMMON	6189.00 CYS
0024	203-02070	BORROW	1603.00 CYS
0025	205-12108	STORMWATER MANAGEMENT BUDGET	62760.00 DOL
0026	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0027	205-12618	SWQCP PREPARATION	1.00 LS
0028	207-08264	SUBGRADE TREATMENT, TYPE II	2356.00 SYS
0029	207-09935	SUBGRADE TREATMENT, TYPE IC	7103.00 SYS
0030	207-12498	SUBGRADE TREATMENT, TYPE ID	604.00 SYS
0031	211-09264	STRUCTURE BACKFILL, TYPE 1	430.00 CYS

0032	213-09270	FLOWABLE BACKFILL, REMOVABLE	36.00	CYS
0033	214-11796	GEOGRID, TYPE IB	43.00	SYS
0034	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	187.00	SYS
0035	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	143.00	SYS
0036	301-12232	COMPACTED AGGREGATE NO. 5	63.00	CYS
0037	301-12234	COMPACTED AGGREGATE NO. 53	62.00	CYS
0038	302-06464	SUBBASE FOR PCCP	36.00	CYS
0039	302-07455	DENSE GRADED SUBBASE	10.00	CYS
0040	303-01180	COMPACTED AGGREGATE NO. 53	1631.00	TON
0041	303-07449	COMPACTED AGGREGATE NO. 73	3004.00	TON
0042	303-08210	COMPACTED AGGREGATE NO. 53 TEMPORARY FOR DRIVEWAYS	220.00	TON
0043	304-07493	WIDENING WITH HMA, TYPE B	329.00	TON
0044	304-07494	WIDENING WITH HMA, TYPE C	165.00	TON
0045	304-12625	HMA PATCHING FULL DEPTH TYPE C	673.00	TON
0046	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	444.00	TON
0047	306-08034	MILLING, ASPHALT, 1 1/2 IN.	6828.00	SYS
0048	306-08038	MILLING, ASPHALT, 4 IN.	750.00	SYS
0049	306-08043	MILLING, TRANSITION	55.00	SYS
0050	306-08432	MILLING, APPROACH	4150.00	SYS
0051	306-10163	MILLING ASPHALT, 2 1/2 IN	135426.00	SYS
0052	306-11872	MILLING, PROFILE	2188.00	SYS
0053	401-06264	PROFILOGRAPH, HMA	1.00	LS
0054	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	114.00	TON
0055	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	756.00	TON
0056	401-07347	QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	19261.00	TON
0057	401-07356	QC/QA-HMA, 2, 64, INTERMEDIATE, 9.5 mm	30.00	TON
0058	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	943.00	TON
0059	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	963.00	TON
0060	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	1168.00	TON
0061	401-10258	JOINT ADHESIVE, SURFACE	75772.00	LFT
0062	401-10259	JOINT ADHESIVE, INTERMEDIATE	7727.00	LFT
0063	401-11785	LIQUID ASPHALT SEALANT	53279.00	LFT
0064	402-10086	HMA FOR TEMPORARY PAVEMENT, C	241.00	TON
0065	406-05520	ASPHALT FOR TACK COAT	41.20	TON
0066	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	9.10	TON
0067	601-02241	GUARDRAIL, REMOVE	1359.00	LFT
0068	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	907.00	LFT

0069	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00 EACH
0070	601-94689	GUARDRAIL, END TREATMENT, OS	6.00 EACH
0071	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	20.00 LFT
0072	602-06729	BARRIER, DELINEATOR	2.00 EACH
0073	604-06070	SIDEWALK, CONCRETE	60.00 SYS
0074	604-08086	CURB RAMP, CONCRETE	43.00 SYS
0075	604-12083	DETECTABLE WARNING SURFACES	8.00 SYS
0076	605-06120	CURB, CONCRETE	54.00 LFT
0077	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	243.00 LFT
0078	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	58386.00 LFT
0079	610-07487	HMA FOR APPROACHES, TYPE B	336.00 TON
0080	610-07488	HMA FOR APPROACHES, TYPE C	572.00 TON
0081	610-08446	PCCP FOR APPROACHES, 6 IN.	16.00 SYS
0082	610-09108	PCCP FOR APPROACHES, 9 IN.	43.00 SYS
0083	611-06497	MAILBOX ASSEMBLY, SINGLE	4.00 EACH
0084	615-06490	RIGHT-OF-WAY MARKER	10.00 EACH
0085	615-06500	MONUMENT, A	4.00 EACH
0086	615-06505	MONUMENT, B	2.00 EACH
0087	616-05688	RIPRAP, CLASS 1	58.00 TON
0088	616-06405	RIPRAP, REVETMENT	443.00 TON
0089	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	765.00 SYS
0090	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	138.00 SYS
0091	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00 EACH
0092	621-02770	EROSION CONTROL BLANKET	3540.00 SYS
0093	621-06545	FERTILIZER	1.00 TON
0094	621-06554	SEED MIXTURE U	236.00 LBS
0095	621-06559	MULCHED SEEDING R	5006.00 SYS
0096	621-06565	MULCHING MATERIAL	3.00 TON
0097	621-06567	WATER	123.00 kGAL
0098	621-06570	TOPSOIL	366.00 CYS
0099	621-06574	SODDING	110.00 SYS
0100	621-06575	SODDING, NURSERY	3345.00 SYS
0101	622-05625	PLANT, CONIFEROUS EVERGREEN, CONE BROAD UPRIGHT, 48 IN.TO 72 IN.	22.00 EACH
0102	628-09402	FIELD OFFICE, B	18.00 MOS
0103	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0104	702-51863	FIELD DRILLED HOLE IN CONCRETE	38.00 EACH
0105	703-06029	REINFORCING BARS, EPOXY COATED	13109.00 LBS

0106	704-51002	CONCRETE, C, SUPERSTRUCTURE	44.70	CYS
0107	706-09960	RAILING, CONCRETE FC	15.00	LFT
0108	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0109	709-51821	SURFACE SEAL	1.00	LS
0110	710-09158	PATCHING CONCRETE STRUCTURES	55.00	SFT
0111	715-01662	PIPE CLEANING, 12 IN. TO 48 IN. DIA.	78.00	LFT
0112	715-03584	SAFETY METAL END SECTION, 4:1, DIA 18 IN.	2.00	EACH
0113	715-05123	PIPE, TYPE 1, CIRCULAR, 24 IN.	119.00	LFT
0114	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	145.00	LFT
0115	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	8.00	LFT
0116	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	199.00	LFT
0117	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	373.00	LFT
0118	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	77.00	LFT
0119	715-05168	PIPE, TYPE 3, CIRCULAR, 12 IN.	24.00	LFT
0120	715-05171	PIPE, TYPE 3, CIRCULAR, 18 IN.	50.00	LFT
0121	715-08305	HMA FOR STRUCTURE INSTALLATION, TYPE B	46.00	TON
0122	715-09064	VIDEO INSPECTION FOR PIPE	961.00	LFT
0123	715-46000	PIPE END SECTION, DIAMETER 12 IN.	2.00	EACH
0124	715-46005	PIPE END SECTION, DIAMETER 15 IN.	1.00	EACH
0125	715-46010	PIPE END SECTION, DIAMETER 18 IN.	2.00	EACH
0126	715-46020	PIPE END SECTION, DIAMETER 24 IN.	4.00	EACH
0127	715-46030	PIPE END SECTION, DIAMETER 30 IN.	1.00	EACH
0128	715-94530	ADJUST WATER VALVE TO GRADE	2.00	EACH
0129	720-01894	CASTING, FURNISH AND ADJUST TO GRADE	1.00	EACH
0130	720-44000	CASTING, ADJUST TO GRADE	5.00	EACH
0131	720-44000	CASTING, ADJUST TO GRADE	2.00	EACH
0132	720-45410	MANHOLE, C4	3.00	EACH
0133	720-94157	MANHOLE, C	1.00	EACH
0134	720-94840	CASTING, WATER VALVE, ADJUST TO GRADE	3.00	EACH
0135	720-97218	MANHOLE, D7	1.00	EACH
0136	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.00	EACH
0137	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	2.00	EACH
0138	801-03290	CONSTRUCTION SIGN, C	3.00	EACH
0139	801-03291	CONSTRUCTION SIGN, D	4.00	EACH
0140	801-04308	ROAD CLOSURE SIGN ASSEMBLY	10.00	EACH
0141	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	21826.00	LFT
0142	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	9785.00	LFT

0143	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	55.00	LFT
0144	801-06625	DETOUR ROUTE MARKER ASSEMBLY	40.00	EACH
0145	801-06640	CONSTRUCTION SIGN, A	140.00	EACH
0146	801-06645	CONSTRUCTION SIGN, B	30.00	EACH
0147	801-06775	MAINTAINING TRAFFIC	1.00	LS
0148	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	4.00	EACH
0149	801-07118	BARRICADE, III-A	148.00	LFT
0150	801-07119	BARRICADE, III-B	282.00	LFT
0151	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	1410.00	LFT
0152	802-03821	SIGN, SHEET, WITH LEGEND,	2.00	EACH
0153	802-04893	REFERENCE POST	2.00	EACH
0154	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	237.50	LFT
0155	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	52.00	LFT
0156	802-07058	SIGN, SHEET, ASSEMBLY RELOCATE	7.00	EACH
0157	802-07060	SIGN, SHEET, RELOCATE	3.00	EACH
0158	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	109.80	SFT
0159	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	8.00	SFT
0160	802-91122	SIGN GROUND MOUNTED RESET	5.00	EACH
0161	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.00	EACH
0162	805-01842	HANDHOLE SIGNAL TYPE 1	2.00	EACH
0163	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	8.00	EACH
0164	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	3.00	EACH
0165	805-06595	CONDUIT, PVC, 2 IN.	105.00	LFT
0166	805-10107	WIRELESS MAGNETOMETER DETECTOR	8.00	EACH
0167	805-11386	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, F	1.00	EACH
0168	805-11396	SIGNAL CANTILEVER STRUCTURE, DUAL ARM 45 FT	1.00	EACH
0169	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	7.00	EACH
0170	805-78230	TRAFFIC SIGNAL HEAD, 5 SECTION, 12 IN.	2.00	EACH
0171	805-78370	PEDESTRIAN PUSH BUTTON, NON-APS	8.00	EACH
0172	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	3053.00	LFT
0173	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	277.00	LFT
0174	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	619.00	LFT
0175	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	208.00	LFT
0176	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	558.00	LFT
0177	805-78785	SIGNAL DETECTOR HOUSING	6.00	EACH
0178	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1066.00	LFT
0179	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	3.00	EACH

0180	808-04298	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, R X R	2.00EACH
0181	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	3470.00 LFT
0182	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	74541.00 LFT
0183	808-06716	LINE, REMOVE	14597.00 LFT
0184	808-06723	PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW	2.00EACH
0185	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS
0186	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	185.00 LFT
0187	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	739.00 LFT
0188	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	35.00 LFT
0189	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	205.00 LFT
0190	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	4.00EACH
0191	808-12032	GROOVING FOR PAVEMENT MARKINGS	61647.00 LFT
0192	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	6790.00 LFT
0193	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	19256.00 LFT
0194	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	420.00 LFT
0195	808-75290	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 24 IN.	166.00 LFT
0196	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	426.00 LFT
0197	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	20.00EACH
0198	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	2.00EACH
0199	808-75340	PAVEMENT MESSAGE MARKING, THERMOPLASTIC R X R	1.00EACH
0200	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	747.00EACH
0201	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	5431.00 LFT

Call: 391

Contract: R -39902-A

Section No.: 1

SMALL STRUCTURE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0013	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0014	202-74045	SIGN AND SUPPORTS, CHANNEL POSTS, REMOVE	3.00	EACH
0015	202-93741	GUARDRAIL, END TREATMENT, REMOVE	4.00	EACH
0016	202-96133	PIPE, REMOVE	174.00	LFT
0017	203-02000	EXCAVATION, COMMON	300.00	CYS
0018	203-02070	BORROW	935.00	CYS
0019	205-11626	PUMP AROUND	1.00	EACH
0020	205-12108	STORMWATER MANAGEMENT BUDGET	19265.00	DOL
0021	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0022	205-12618	SWQCP PREPARATION	1.00	LS
0023	206-51220	EXCAVATION, WET	90.00	CYS
0024	207-08264	SUBGRADE TREATMENT, TYPE II	144.00	SYS
0025	207-09935	SUBGRADE TREATMENT, TYPE IC	210.00	SYS
0026	207-12498	SUBGRADE TREATMENT, TYPE ID	417.00	SYS
0027	211-09265	STRUCTURE BACKFILL, TYPE 2	265.00	CYS
0028	211-09268	STRUCTURE BACKFILL, TYPE 5	564.00	CYS
0029	213-09270	FLOWABLE BACKFILL, REMOVABLE	85.00	CYS
0030	214-12237	GEOTEXTILE FOR PAVEMENT TYPE 1B	109.00	SYS
0031	301-12232	COMPACTED AGGREGATE NO. 5	30.00	CYS

0032	301-12233	COMPACTED AGGREGATE NO. 8	60.00	CYS
0033	301-12234	COMPACTED AGGREGATE NO. 53	144.00	CYS
0034	303-01180	COMPACTED AGGREGATE NO. 53	126.00	TON
0035	306-08034	MILLING, ASPHALT, 1 1/2 IN.	367.00	SYS
0036	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	32.00	TON
0037	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	47.00	TON
0038	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	53.00	TON
0039	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	26.00	TON
0040	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	87.00	TON
0041	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	130.00	TON
0042	401-10258	JOINT ADHESIVE, SURFACE	305.00	LFT
0043	401-10259	JOINT ADHESIVE, INTERMEDIATE	185.00	LFT
0044	401-11785	LIQUID ASPHALT SEALANT	305.00	LFT
0045	406-05521	ASPHALT FOR TACK COAT	1657.00	SYS
0046	601-02241	GUARDRAIL, REMOVE	307.00	LFT
0047	601-06035	GUARDRAIL, RESET	50.00	LFT
0048	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	240.00	LFT
0049	610-07487	HMA FOR APPROACHES, TYPE B	32.00	TON
0050	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00	EACH
0051	615-06490	RIGHT-OF-WAY MARKER	21.00	EACH
0052	615-06505	MONUMENT, B	2.00	EACH
0053	616-05688	RIPRAP, CLASS 1	245.00	TON
0054	616-06405	RIPRAP, REVETMENT	139.00	TON
0055	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	1064.00	SYS
0056	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0057	621-06559	MULCHED SEEDING R	3214.00	SYS
0058	621-06567	WATER	1.10	KGAL
0059	621-06574	SODDING	265.00	SYS
0060	628-09402	FIELD OFFICE, B	12.00	MOS
0061	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0062	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0063	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0064	628-11781	CELLULAR TELEPHONE SERVICE, 750 MIN.	12.00	MOS
0065	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0066	713-07661	GUARDRAIL, END TREATMENT, OS, TEMP BRIDGE APPROACH	1.00	EACH
0067	713-11199	TEMPORARY PIPE	85.00	LFT
0068	713-51334	TEMPORARY PIPE AND APPROACHES	1.00	LS

0069	713-99365	GUARDRAIL, W BEAM 6.3 FT SPACING TEMPORARY BRIDGE APPROACHES	131.00	LFT
0070	714-11181	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 8 FT. X 8 FT.	128.00	LFT
0071	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	48.00	LFT
0072	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	10.00	LFT
0073	715-05121	PIPE, TYPE 1, CIRCULAR, 18 IN.	89.00	LFT
0074	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	334.00	LFT
0075	715-09992	PIPE, TYPE 1, DEFORMED, MIN. AREA 29.5 SFT	65.00	LFT
0076	715-46005	PIPE END SECTION, DIAMETER 15 IN.	4.00	EACH
0077	715-46010	PIPE END SECTION, DIAMETER 18 IN.	4.00	EACH
0078	718-06531	OUTLET PROTECTOR, 3	1.00	EACH
0079	720-45410	MANHOLE, C4	2.00	EACH
0080	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.00	EACH
0081	801-04092	TEMPORARY PAVEMENT	551.00	SYS
0082	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	EACH
0083	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	14291.00	LFT
0084	801-06625	DETOUR ROUTE MARKER ASSEMBLY	39.00	EACH
0085	801-06640	CONSTRUCTION SIGN, A	63.00	EACH
0086	801-06645	CONSTRUCTION SIGN, B	15.00	EACH
0087	801-06649	TEMPORARY RAISED PAVEMENT MARKER, GRADE 1	56.00	EACH
0088	801-06775	MAINTAINING TRAFFIC	1.00	LS
0089	801-07118	BARRICADE, III-A	48.00	LFT
0090	801-07119	BARRICADE, III-B	168.00	LFT
0091	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	384.00	LFT
0092	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	70.00	LFT
0093	801-12348	TEMPORARY WORKSITE SPEED DISPLAY ASSEMBLY	2.00	EACH
0094	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	30.00	LFT
0095	802-91122	SIGN GROUND MOUNTED RESET	3.00	EACH
0096	804-06740	DELINEATOR WITH POST, D2	29.00	EACH
0097	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1750.00	LFT
0098	808-06716	LINE, REMOVE	2910.00	LFT
0099	808-12032	GROOVING FOR PAVEMENT MARKINGS	6325.00	LFT
0100	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	861.00	LFT
0101	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	3777.00	LFT

Call: 401

Contract: R -39903-A

Section No.: 1

SMALL STRUCTURE PIPE LINING

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0009	203-02070	BORROW	40.00 CYS
0010	205-11626	PUMP AROUND	1.00EACH
0011	205-12108	STORMWATER MANAGEMENT BUDGET	542.00 DOL
0012	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0013	205-12618	SWQCP PREPARATION	1.00 LS
0014	211-09268	STRUCTURE BACKFILL, TYPE 5	80.00 CYS
0015	616-05689	RIPRAP, CLASS 2	152.00 TON
0016	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	213.00 SYS
0017	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00EACH
0018	621-06559	MULCHED SEEDING R	405.00 SYS
0019	621-06565	MULCHING MATERIAL	1.00 TON
0020	621-12612	SEED MIXTURE FLOODPLAIN	1.00 LBS
0021	628-09403	FIELD OFFICE, C	6.00 MOS
0022	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00EACH
0023	702-51005	CONCRETE, A, SUBSTRUCTURE	9.60 CYS
0024	702-51015	CONCRETE, B, FOOTINGS	33.60 CYS
0025	703-06028	REINFORCING BARS	3342.00 LBS
0026	709-51821	SURFACE SEAL	1.00 LS
0027	725-11038	LINER PIPE, THERMOPLASTIC, CIRCULAR, 15.9-16.0 SFT	65.00 LFT
0028	801-06640	CONSTRUCTION SIGN, A	8.00EACH
0029	801-06775	MAINTAINING TRAFFIC	1.00 LS

Call: 411

Contract: R -39912-A

Section No.: 1 ASPHALT RESURFACE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	2.00	EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0010	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0011	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0012	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	1783.00	SYS
0014	202-06312	REMOVE	185.00	SFT
0015	202-91385	INLET, REMOVE	1.00	EACH
0016	202-93741	GUARDRAIL, END TREATMENT, REMOVE	10.00	EACH
0017	202-96133	PIPE, REMOVE	184.00	LFT
0018	203-02000	EXCAVATION, COMMON	769.00	CYS
0019	205-11626	PUMP AROUND	4.00	EACH
0020	205-12108	STORMWATER MANAGEMENT BUDGET	8339.00	DOL
0021	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0022	205-12618	SWQCP PREPARATION	1.00	LS
0023	207-09935	SUBGRADE TREATMENT, TYPE IC	264.00	SYS
0024	207-12498	SUBGRADE TREATMENT, TYPE ID	3807.00	SYS
0025	211-09265	STRUCTURE BACKFILL, TYPE 2	380.00	CYS
0026	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	67.00	SYS
0027	214-12456	GEOTEXTILE FOR PAVEMENT, INTERLAYER	20414.00	SYS
0028	301-12232	COMPACTED AGGREGATE NO. 5	743.00	CYS
0029	301-12234	COMPACTED AGGREGATE NO. 53	30.00	CYS
0030	303-01180	COMPACTED AGGREGATE NO. 53	3088.00	TON
0031	304-12625	HMA PATCHING FULL DEPTH TYPE C	748.00	TON

0032	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	13.00 TON
0033	304-12627	HMA PATCHING FULL DEPTH TYPE D	651.00 TON
0034	304-12627	HMA PATCHING FULL DEPTH TYPE D	372.00 TON
0035	304-12628	HMA PATCHING PARTIAL DEPTH TYPE D	1349.00 TON
0036	306-08034	MILLING, ASPHALT, 1 1/2 IN.	79908.00 SYS
0037	306-08036	MILLING, ASPHALT, 2 IN.	70008.00 SYS
0038	306-08038	MILLING, ASPHALT, 4 IN.	20414.00 SYS
0039	306-08043	MILLING, TRANSITION	6383.00 SYS
0040	306-08432	MILLING, APPROACH	15924.00 SYS
0041	401-06264	PROFILOGRAPH, HMA	1.00 LS
0042	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	6593.00 TON
0043	401-07329	QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	24953.00 TON
0044	401-07372	QC/QA-HMA, 3, 64, INTERMEDIATE, 12.5 mm	10988.00 TON
0045	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	2807.00 TON
0046	401-10258	JOINT ADHESIVE, SURFACE	124382.00 LFT
0047	401-10259	JOINT ADHESIVE, INTERMEDIATE	7414.00 LFT
0048	401-11785	LIQUID ASPHALT SEALANT	124382.00 LFT
0049	401-11785	LIQUID ASPHALT SEALANT	29027.00 LFT
0050	406-05520	ASPHALT FOR TACK COAT	92.00 TON
0051	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	6.00 TON
0052	601-02241	GUARDRAIL, REMOVE	3727.00 LFT
0053	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	3400.00 LFT
0054	601-12282	GUARDRAIL, MGS W-BEAM, 3 FT 1.5 IN SPACING	50.00 LFT
0055	601-12287	GUARDRAIL, MGS, LONG SPAN, TYPE 1	2.00 EACH
0056	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	5.00 EACH
0057	601-94689	GUARDRAIL, END TREATMENT, OS	5.00 EACH
0058	604-03643	BRICK PAVERS	59.00 SYS
0059	604-06070	SIDEWALK, CONCRETE	540.00 SYS
0060	604-08086	CURB RAMP, CONCRETE	950.00 SYS
0061	604-12083	DETECTABLE WARNING SURFACES	126.00 SYS
0062	605-06120	CURB, CONCRETE	2050.00 LFT
0063	605-06140	CURB AND GUTTER, CONCRETE	115.00 LFT
0064	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	103515.00 LFT
0065	610-07488	HMA FOR APPROACHES, TYPE C	742.00 TON
0066	610-07788	HMA FOR APPROACHES, TYPE D	1920.00 TON
0067	610-08446	PCCP FOR APPROACHES, 6 IN.	75.00 SYS
0068	615-01469	MONUMENT SECTION CORNER INSTALL	1.00 EACH

0069	615-06525	CASTING ADJUST TO GRADE, MONUMENT	12.00 EACH
0070	615-06525	CASTING ADJUST TO GRADE, MONUMENT	6.00 EACH
0071	616-05688	RIPRAP, CLASS 1	52.00 TON
0072	616-05689	RIPRAP, CLASS 2	44.00 TON
0073	616-06405	RIPRAP, REVETMENT	187.00 TON
0074	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	336.00 SYS
0075	616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	17.00 SYS
0076	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00 EACH
0077	621-06559	MULCHED SEEDING R	513.00 SYS
0078	621-06567	WATER	3.00 kGAL
0079	621-06570	TOPSOIL	386.00 CYS
0080	621-06575	SODDING, NURSERY	723.00 SYS
0081	628-09403	FIELD OFFICE, C	15.00 MOS
0082	628-11729	CELLULAR TELEPHONE, TYPE A	1.00 EACH
0083	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00 DOL
0084	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00 DOL
0085	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	10.00 MOS
0086	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00 EACH
0087	628-11977	COMPUTER SYSTEM	1.00 EACH
0088	714-96273	HEADWALL RECONSTRUCT	1.00 LS
0089	715-04522	PIPE END SECTION, DIA 42 IN.	1.00 EACH
0090	715-05024	PIPE, TYPE 2, CIRCULAR, 36 IN.	44.00 LFT
0091	715-05049	PIPE, TYPE 4, CIRCULAR, 8 IN.	25.00 LFT
0092	715-05052	PIPE, TYPE 4, CIRCULAR, 12 IN.	25.00 LFT
0093	715-05119	PIPE, TYPE 1, CIRCULAR, 15 IN.	42.00 LFT
0094	715-05127	PIPE, TYPE 1, CIRCULAR, 42 IN.	51.00 LFT
0095	715-05148	PIPE, TYPE 2, CIRCULAR, 10 IN.	10.00 LFT
0096	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	144.00 LFT
0097	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	58.00 LFT
0098	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	48.00 LFT
0099	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	48.00 LFT
0100	715-08306	HMA FOR STRUCTURE INSTALLATION, TYPE C	175.00 TON
0101	715-46005	PIPE END SECTION, DIAMETER 15 IN.	1.00 EACH
0102	715-46020	PIPE END SECTION, DIAMETER 24 IN.	1.00 EACH
0103	715-46040	PIPE END SECTION, DIAMETER 36 IN.	1.00 EACH
0104	720-44000	CASTING, ADJUST TO GRADE	1.00 EACH
0105	720-44000	CASTING, ADJUST TO GRADE	6.00 EACH

0106	720-44015	CASTING, 2, FURNISH AND ADJUST TO GRADE	1.00 EACH
0107	720-45040	INLET, G7	2.00 EACH
0108	720-45045	INLET, J10	1.00 EACH
0109	720-45240	CATCH BASIN, J10	4.00 EACH
0110	720-94157	MANHOLE, C	3.00 EACH
0111	720-94840	CASTING, WATER VALVE, ADJUST TO GRADE	3.00 EACH
0112	801-04308	ROAD CLOSURE SIGN ASSEMBLY	7.00 EACH
0113	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	167753.00 LFT
0114	801-06213	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, (RXR)	5.00 EACH
0115	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	1386.00 LFT
0116	801-06625	DETOUR ROUTE MARKER ASSEMBLY	48.00 EACH
0117	801-06640	CONSTRUCTION SIGN, A	129.00 EACH
0118	801-06645	CONSTRUCTION SIGN, B	104.00 EACH
0119	801-06775	MAINTAINING TRAFFIC	1.00 LS
0120	801-07118	BARRICADE, III-A	88.00 LFT
0121	801-07119	BARRICADE, III-B	750.00 LFT
0122	801-12324	LAW ENFORCEMENT OFFICER	850.00 HRS
0123	801-12647	LAW ENFORCEMENT OFFICER TRAINING	3.00 DOL
0124	801-12647	LAW ENFORCEMENT OFFICER TRAINING	1.00 DOL
0125	801-92448	CONSTRUCTION SIGNS MOBILE	480.00 DAY
0126	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	207.00 LFT
0127	802-07060	SIGN, SHEET, RELOCATE	16.00 EACH
0128	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	31.00 SFT
0129	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	72.00 SFT
0130	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	216.00 LFT
0131	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	10.00 EACH
0132	805-05405	SIGNAL POLE, PEDESTAL, 4FT	10.00 EACH
0133	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, 2 CHANNEL	1.00 EACH
0134	805-78370	PEDESTRIAN PUSH BUTTON, NON-APS	10.00 EACH
0135	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	17244.00 LFT
0136	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	1207.00 LFT
0137	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	778.00 LFT
0138	805-78785	SIGNAL DETECTOR HOUSING	2.00 EACH
0139	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	5657.00 LFT
0140	805-92951	SIGNAL DETECTOR HOUSING ADJUST TO GRADE	2.00 EACH
0141	808-02977	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, BIKE SYMBOL	6.00 EACH
0142	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	145597.00 LFT

0143	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0144	808-12032	GROOVING FOR PAVEMENT MARKINGS	140071.00	LFT
0145	808-12273	TRANSVERSE MARKING, THERMOPLASTIC, PARKING LINE, WHITE 4 IN.	1250.00	LFT
0146	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	594.00	LFT
0147	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	20825.00	LFT
0148	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	54098.00	LFT
0149	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	152.00	LFT
0150	808-75290	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 24 IN.	124.00	LFT
0151	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	1386.00	LFT
0152	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	5907.00	LFT
0153	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	75.00	EACH
0154	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	6.00	EACH
0155	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	2.00	EACH
0156	808-75340	PAVEMENT MESSAGE MARKING, THERMOPLASTIC R X R	5.00	EACH
0157	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	341.00	EACH
0158	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	341.00	EACH
0159	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	1113.00	LFT

Call: 421

Contract: R -39913-A

Section No.: 1

SMALL STRUCTURE REPLACEMENT

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	6.00	EACH
	0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0004	109-08360	CONTRACT LIENS	1.00	DOL
	0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0012	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
	0013	202-96133	PIPE, REMOVE	146.00	LFT
	0014	203-02000	EXCAVATION, COMMON	610.00	CYS
	0015	205-11626	PUMP AROUND	1.00	EACH
	0016	205-12108	STORMWATER MANAGEMENT BUDGET	5600.00	DOL
	0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0018	205-12618	SWQCP PREPARATION	1.00	LS
	0019	207-08264	SUBGRADE TREATMENT, TYPE II	84.00	SYS
	0020	207-12498	SUBGRADE TREATMENT, TYPE ID	1434.00	SYS
	0021	211-09265	STRUCTURE BACKFILL, TYPE 2	566.00	CYS
	0022	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	441.00	SYS
	0023	301-12232	COMPACTED AGGREGATE NO. 5	14.00	CYS
	0024	301-12233	COMPACTED AGGREGATE NO. 8	23.00	CYS
	0025	301-12234	COMPACTED AGGREGATE NO. 53	14.00	CYS
	0026	303-01180	COMPACTED AGGREGATE NO. 53	277.00	TON
	0027	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1285.00	SYS
	0028	401-07329	QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	219.00	TON
	0029	401-07399	QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm	183.00	TON
	0030	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	730.00	TON
	0031	401-10258	JOINT ADHESIVE, SURFACE	1257.00	LFT

0032	401-10259	JOINT ADHESIVE, INTERMEDIATE	357.00	LFT
0033	401-11785	LIQUID ASPHALT SEALANT	1257.00	LFT
0034	406-05521	ASPHALT FOR TACK COAT	4017.00	SYS
0035	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	169.00	LFT
0036	601-12288	GUARDRAIL, MGS, LONG SPAN, TYPE 2	1.00	EACH
0037	601-94689	GUARDRAIL, END TREATMENT, OS	2.00	EACH
0038	610-07487	HMA FOR APPROACHES, TYPE B	24.00	TON
0039	611-08232	MAILBOX ASSEMBLY, RESET SINGLE	1.00	EACH
0040	615-06510	MONUMENT, C	1.00	EACH
0041	616-06405	RIPRAP, REVETMENT	77.00	TON
0042	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	140.00	SYS
0043	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0044	621-12612	SEED MIXTURE FLOODPLAIN	7.00	LBS
0045	628-09402	FIELD OFFICE, B	8.00	MOS
0046	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0047	702-04325	TEMPORARY SHORING	1.00	LS
0048	714-12158	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 15 FT. X 7 FT.	70.00	LFT
0049	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	137.00	LFT
0050	715-46000	PIPE END SECTION, DIAMETER 12 IN.	1.00	EACH
0051	720-45410	MANHOLE, C4	1.00	EACH
0052	801-04746	ENERGY ABSORBING TERMINAL, CZ, TL-	2.00	EACH
0053	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4820.00	LFT
0054	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	1120.00	LFT
0055	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	24.00	LFT
0056	801-06640	CONSTRUCTION SIGN, A	26.00	EACH
0057	801-06645	CONSTRUCTION SIGN, B	7.00	EACH
0058	801-06775	MAINTAINING TRAFFIC	1.00	LS
0059	801-07118	BARRICADE, III-A	48.00	LFT
0060	801-07119	BARRICADE, III-B	24.00	LFT
0061	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	743.00	LFT
0062	801-12082	FIXED TEMPORARY SIGNAL	1.00	LS
0063	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	100.00	LFT
0064	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	800.00	LFT

Call: 431

Contract: R -39933-A

Section No.: 1 PAVEMENT REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	8610.00	SYS
0014	202-02272	PAVED SIDE DITCH, REMOVE	1123.00	LFT
0015	202-02274	CURB, CONCRETE INTEGRAL, REMOVE	51.00	LFT
0016	202-02278	CURB, CONCRETE, REMOVE	763.00	LFT
0017	202-02279	CURB AND GUTTER, REMOVE	272.00	LFT
0018	202-03875	CONCRETE STEPS, REMOVE	3.00	EACH
0019	202-52710	SIDEWALK CONCRETE, REMOVE	1944.00	SYS
0020	202-90277	DETECTOR HOUSING, REMOVE	2.00	EACH
0021	202-90747	RETAINING WALL, REMOVE	444.00	LFT
0022	202-91385	INLET, REMOVE	1.00	EACH
0023	203-02000	EXCAVATION, COMMON	8313.00	CYS
0024	205-11626	PUMP AROUND	1.00	EACH
0025	205-12108	STORMWATER MANAGEMENT BUDGET	42848.00	DOL
0026	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0027	205-12618	SWQCP PREPARATION	1.00	LS
0028	207-08264	SUBGRADE TREATMENT, TYPE II	2790.00	SYS
0029	207-12498	SUBGRADE TREATMENT, TYPE ID	8980.00	SYS
0030	207-12635	SUBGRADE TREATMENT, TYPE IBC	33195.00	SYS
0031	211-09264	STRUCTURE BACKFILL, TYPE 1	1.00	CYS

0032	211-09265	STRUCTURE BACKFILL, TYPE 2	9706.00	CYS
0033	211-09267	STRUCTURE BACKFILL, TYPE 4	1.00	CYS
0034	214-11796	GEOGRID, TYPE IB	1834.00	SYS
0035	214-12237	GEOTEXTILE FOR PAVEMENT TYPE 1B	33195.00	SYS
0036	302-07455	DENSE GRADED SUBBASE	482.00	CYS
0037	303-01180	COMPACTED AGGREGATE NO. 53	1430.00	TON
0038	304-07493	WIDENING WITH HMA, TYPE B	46.00	TON
0039	304-12623	HMA PATCHING FULL DEPTH TYPE B	73.00	TON
0040	304-12625	HMA PATCHING FULL DEPTH TYPE C	4873.00	TON
0041	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	1476.00	TON
0042	306-08034	MILLING, ASPHALT, 1 1/2 IN.	126018.00	SYS
0043	306-08432	MILLING, APPROACH	6400.00	SYS
0044	401-06264	PROFILOGRAPH, HMA	1.00	LS
0045	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	9077.00	TON
0046	401-07329	QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	1525.00	TON
0047	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	281.00	TON
0048	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	335.00	TON
0049	401-10258	JOINT ADHESIVE, SURFACE	64833.00	LFT
0050	401-11785	LIQUID ASPHALT SEALANT	64833.00	LFT
0051	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	392.00	TON
0052	406-05520	ASPHALT FOR TACK COAT	50.00	TON
0053	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	4.00	TON
0054	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.00	TON
0055	601-05999	CURVED TERMINAL END	2.00	EACH
0056	601-06035	GUARDRAIL, RESET	160.00	LFT
0057	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	12.50	LFT
0058	603-98225	FENCE, CHAIN LINK, PVC COATED 48 IN	102.00	LFT
0059	604-06070	SIDEWALK, CONCRETE	4453.00	SYS
0060	604-08086	CURB RAMP, CONCRETE	357.00	SYS
0061	604-12083	DETECTABLE WARNING SURFACES	91.00	SYS
0062	604-44251	STEPS, CONCRETE	7.00	CYS
0063	604-92237	HAND RAIL, STEEL	3.00	LFT
0064	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	2105.00	LFT
0065	610-07487	HMA FOR APPROACHES, TYPE B	537.00	TON
0066	610-08446	PCCP FOR APPROACHES, 6 IN.	879.00	SYS
0067	610-09108	PCCP FOR APPROACHES, 9 IN.	1915.00	SYS
0068	611-06497	MAILBOX ASSEMBLY, SINGLE	8.00	EACH

0069	615-06490	RIGHT-OF-WAY MARKER	32.00 EACH
0070	615-06500	MONUMENT, A	2.00 EACH
0071	615-06520	MONUMENT, RE-ESTABLISH	17.00 EACH
0072	616-05689	RIPRAP, CLASS 2	10.00 TON
0073	616-06405	RIPRAP, REVETMENT	138.00 TON
0074	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	274.00 SYS
0075	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00 EACH
0076	621-06567	WATER	34.00 KGAL
0077	621-06575	SODDING, NURSERY	9196.00 SYS
0078	628-09402	FIELD OFFICE, B	24.00 MOS
0079	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0080	702-51863	FIELD DRILLED HOLE IN CONCRETE	2.00 EACH
0081	703-06028	REINFORCING BARS	216.00 LBS
0082	715-02181	SANITARY SEWER SERVICE ADJUSTMENT	224.00 LFT
0083	715-05024	PIPE, TYPE 2, CIRCULAR, 36 IN.	477.00 LFT
0084	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	9092.00 LFT
0085	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	336.00 LFT
0086	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	19.00 LFT
0087	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	4171.00 LFT
0088	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	1587.00 LFT
0089	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	657.00 LFT
0090	715-05161	PIPE, TYPE 2, CIRCULAR, 48 IN.	451.00 LFT
0091	715-05422	PIPE, SLOTTED DRAIN, 12 IN.	461.00 LFT
0092	715-08283	PCCP FOR STRUCTURE INSTALLATION	36.00 SYS
0093	715-08305	HMA FOR STRUCTURE INSTALLATION, TYPE B	108.00 TON
0094	715-09064	VIDEO INSPECTION FOR PIPE	7548.00 LFT
0095	715-12676	PIPE END SECTION, PRECAST CONCRETE, 48 IN	1.00 EACH
0096	715-46010	PIPE END SECTION, DIAMETER 18 IN.	1.00 EACH
0097	715-46020	PIPE END SECTION, DIAMETER 24 IN.	1.00 EACH
0098	716-07635	PIPE INSTALLATION, TRENCHLESS, 36 IN.	186.00 LFT
0099	718-06529	OUTLET PROTECTOR, 2	3.00 EACH
0100	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	3000.00 LFT
0101	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	9443.00 SYS
0102	718-52610	AGGREGATE FOR UNDERDRAINS	507.00 CYS
0103	720-01092	MANHOLE, J15 MODIFIED	2.00 EACH
0104	720-02442	PIPE PLUG EXISTING	5.00 EACH
0105	720-08241	MANHOLE, K15 MODIFIED	7.00 EACH

0106	720-09079	INLET, HA5 MODIFIED	1.00 EACH
0107	720-12659	MANHOLE, G2 MODIFIED	2.00 EACH
0108	720-12660	MANHOLE, H15	4.00 EACH
0109	720-44000	CASTING, ADJUST TO GRADE	15.00 EACH
0110	720-45042	INLET, HA5	1.00 EACH
0111	720-45105	INLET, A2 MODIFIED	1.00 EACH
0112	720-45130	INLET, E7 MODIFIED	9.00 EACH
0113	720-45270	PIPE CATCH BASIN, 18 IN.	25.00 EACH
0114	720-45400	MANHOLE, A4	1.00 EACH
0115	720-45405	MANHOLE, B4	3.00 EACH
0116	720-93409	INLET, B15 MODIFIED	20.00 EACH
0117	720-93411	INLET, C15 MODIFIED	47.00 EACH
0118	720-95422	MANHOLE, J4	1.00 EACH
0119	732-11770	AGGREGATE FOR DRAINAGE FILL	59.00 CYS
0120	732-11810	MODULAR BLOCK WALL	1229.00 SFT
0121	732-11811	MODULAR BLOCK WALL ERECTION	1229.00 SFT
0122	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.00 EACH
0123	801-03290	CONSTRUCTION SIGN, C	4.00 EACH
0124	801-04308	ROAD CLOSURE SIGN ASSEMBLY	15.00 EACH
0125	801-06625	DETOUR ROUTE MARKER ASSEMBLY	32.00 EACH
0126	801-06640	CONSTRUCTION SIGN, A	82.00 EACH
0127	801-06645	CONSTRUCTION SIGN, B	9.00 EACH
0128	801-06710	FLASHING ARROW SIGN	10.00 DAY
0129	801-06775	MAINTAINING TRAFFIC	1.00 LS
0130	801-07118	BARRICADE, III-A	54.00 LFT
0131	801-07119	BARRICADE, III-B	312.00 LFT
0132	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00 EACH
0133	801-11990	TEMPORARY CURB RAMP	4.00 EACH
0134	801-12042	TRUCK MOUNTED ATTENUATOR	264.00 DAY
0135	802-04089	SIGN, SHEET, REMOVE	66.00 EACH
0136	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	729.00 LFT
0137	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	39.00 LFT
0138	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	416.00 SFT
0139	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	15.00 SFT
0140	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	25.00 SFT
0141	805-06595	CONDUIT, PVC, 2 IN.	87.00 LFT
0142	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	946.00 LFT

0143	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	99.00	LFT
0144	805-78785	SIGNAL DETECTOR HOUSING	2.00	EACH
0145	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	319.00	LFT
0146	808-04298	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, R X R	1.00	EACH
0147	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2426.00	LFT
0148	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	8010.00	LFT
0149	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	87371.00	LFT
0150	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	36024.00	LFT
0151	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	60.00	LFT
0152	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0153	808-12032	GROOVING FOR PAVEMENT MARKINGS	19479.00	LFT
0154	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2182.00	LFT
0155	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	51.00	LFT
0156	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	142.00	LFT
0157	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	880.00	EACH
0158	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	880.00	EACH

Call: 431

Contract: R -39933-A

Section No.: 2 PAVEMENT REPLACEMENT, HMA

Line			
Item No	Item Code	Description	Quantity Unit
0159	303-01180	COMPACTED AGGREGATE NO. 53	4384.00 TON
0160	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1000.00 TON
0161	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	1666.00 TON
0162	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	1999.00 TON
0163	401-10258	JOINT ADHESIVE, SURFACE	5193.00 LFT
0164	401-10259	JOINT ADHESIVE, INTERMEDIATE	5193.00 LFT
0165	401-11785	LIQUID ASPHALT SEALANT	5193.00 LFT
0166	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	2534.00 TON
0167	406-05520	ASPHALT FOR TACK COAT	9.00 TON
0168	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	6592.00 LFT
0169	615-06505	MONUMENT, B	11.00 EACH
0170	808-04298	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, R X R	1.00 EACH
0171	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	8017.00 LFT
0172	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	7003.00 LFT
0173	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	230.00 LFT
0174	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	1271.00 LFT
0175	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	2.00 EACH
0176	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	1.00 EACH

Call: 431

Contract: R -39933-A

Section No.: 3 PAVEMENT REPLACEMENT, PCCP

Line			Quantity	Unit
Item No	Item Code	Description		
0177	302-06464	SUBBASE FOR PCCP	3870.00	CYS
0178	501-09107	QC/QA-PCCP, 9 IN.	13507.00	SYS
0179	503-05240	D-1 CONTRACTION JOINT	7789.00	LFT
0180	605-06090	CURB, INTEGRAL CONCRETE	6592.00	LFT
0181	615-06515	MONUMENT, D	11.00	EACH
0182	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	7767.00	LFT
0183	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	7003.00	LFT
0184	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	230.00	LFT
0185	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	1.00	EACH
0186	808-10053	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	1.00	EACH
0187	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	1271.00	LFT
0188	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	2.00	EACH

Call: 441

Contract: R -39995-A

Section No.: 1 ASPHALT RESURFACE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	325.00	SYS
0013	202-06580	CONTAMINATED SOIL, REMOVE	10.00	CYS
0014	202-51133	RAILING, REMOVE	162.00	LFT
0015	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0016	202-52710	SIDEWALK CONCRETE, REMOVE	2131.00	SYS
0017	202-90277	DETECTOR HOUSING, REMOVE	56.00	EACH
0018	203-02000	EXCAVATION, COMMON	118.00	CYS
0019	205-12108	STORMWATER MANAGEMENT BUDGET	18500.00	DOL
0020	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0021	205-12618	SWQCP PREPARATION	1.00	LS
0022	206-51235	COFFERDAM	1.00	LS
0023	207-08264	SUBGRADE TREATMENT, TYPE II	1148.00	SYS
0024	207-09935	SUBGRADE TREATMENT, TYPE IC	646.00	SYS
0025	207-12498	SUBGRADE TREATMENT, TYPE ID	3923.00	SYS
0026	214-11796	GEOGRID, TYPE IB	140.00	SYS
0027	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	332.00	SYS
0028	301-12234	COMPACTED AGGREGATE NO. 53	289.00	CYS
0029	302-06464	SUBBASE FOR PCCP	83.00	CYS
0030	302-07455	DENSE GRADED SUBBASE	398.00	CYS
0031	303-01180	COMPACTED AGGREGATE NO. 53	1076.00	TON

0032	304-07789	WIDENING WITH HMA, TYPE D	433.00 TON
0033	304-12627	HMA PATCHING FULL DEPTH TYPE D	49.00 TON
0034	304-12628	HMA PATCHING PARTIAL DEPTH TYPE D	5715.00 TON
0035	306-08034	MILLING, ASPHALT, 1 1/2 IN.	327914.00 SYS
0036	306-08043	MILLING, TRANSITION	1174.00 SYS
0037	306-08432	MILLING, APPROACH	23576.00 SYS
0038	401-06264	PROFILOGRAPH, HMA	1.00 LS
0039	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	4142.00 TON
0040	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	23171.00 TON
0041	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	106.00 TON
0042	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	106.00 TON
0043	401-10258	JOINT ADHESIVE, SURFACE	172313.00 LFT
0044	401-10259	JOINT ADHESIVE, INTERMEDIATE	1358.00 LFT
0045	401-11785	LIQUID ASPHALT SEALANT	230152.00 LFT
0046	406-05520	ASPHALT FOR TACK COAT	98.00 TON
0047	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	4.00 TON
0048	503-03489	RETROFITTED TIE BARS	87.00 EACH
0049	503-05240	D-1 CONTRACTION JOINT	696.00 LFT
0050	506-06333	PCCP PATCHING, FULL DEPTH	2388.00 SYS
0051	507-12191	JOINT REPAIR, PARTIAL DEPTH	1692.00 SFT
0052	507-12192	JOINT REPAIR, BOTTOM-HALF	144.00 SFT
0053	601-01839	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 6	1.00 EACH
0054	601-02241	GUARDRAIL, REMOVE	560.00 LFT
0055	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	244.00 LFT
0056	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00 EACH
0057	601-94689	GUARDRAIL, END TREATMENT, OS	3.00 EACH
0058	602-06729	BARRIER, DELINEATOR	8.00 EACH
0059	604-03643	BRICK PAVERS	2.00 SYS
0060	604-03643	BRICK PAVERS	2.00 SYS
0061	604-06070	SIDEWALK, CONCRETE	764.00 SYS
0062	604-08086	CURB RAMP, CONCRETE	1337.00 SYS
0063	604-12083	DETECTABLE WARNING SURFACES	235.00 SYS
0064	605-06120	CURB, CONCRETE	1089.00 LFT
0065	605-06140	CURB AND GUTTER, CONCRETE	2303.00 LFT
0066	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	112134.00 LFT
0067	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	332.00 SYS
0068	610-07487	HMA FOR APPROACHES, TYPE B	2245.00 TON

0069	610-08446	PCCP FOR APPROACHES, 6 IN.	12.00	SYS
0070	615-06505	MONUMENT, B	90.00	EACH
0071	616-05689	RIPRAP, CLASS 2	584.00	TON
0072	616-06405	RIPRAP, REVETMENT	36.00	TON
0073	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	50.00	SYS
0074	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	366.00	SYS
0075	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0076	619-12507	CLEAN AND PAINT STEEL PILING BRIDGE NO.	1.00	LS
0077	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0078	621-06560	MULCHED SEEDING U	222.00	SYS
0079	621-06567	WATER	5.00	KGAL
0080	621-06570	TOPSOIL	147.00	CYS
0081	621-06574	SODDING	18.00	SYS
0082	621-06575	SODDING, NURSERY	881.00	SYS
0083	621-12612	SEED MIXTURE FLOODPLAIN	1.00	LBS
0084	621-52448	SIGN, DO NOT SPRAY	4.00	EACH
0085	628-09403	FIELD OFFICE, C	15.00	MOS
0086	628-11977	COMPUTER SYSTEM	1.00	EACH
0087	702-90915	CONCRETE, CLASS, A	1.00	CYS
0088	703-06029	REINFORCING BARS, EPOXY COATED	31900.00	LBS
0089	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	134.00	EACH
0090	704-51002	CONCRETE, C, SUPERSTRUCTURE	29.60	CYS
0091	706-11600	RAILING, CONCRETE FC	17.00	CYS
0092	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0093	709-51821	SURFACE SEAL	1.00	LS
0094	710-09158	PATCHING CONCRETE STRUCTURES	164.00	SFT
0095	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0096	720-01355	INLET, CLEAN EXISTING	97.00	EACH
0097	720-01894	CASTING, FURNISH AND ADJUST TO GRADE	1.00	EACH
0098	720-44000	CASTING, ADJUST TO GRADE	18.00	EACH
0099	720-44000	CASTING, ADJUST TO GRADE	79.00	EACH
0100	720-44000	CASTING, ADJUST TO GRADE	96.00	EACH
0101	720-44070	CASTING, 13, FURNISH AND ADJUST TO GRADE	12.00	EACH
0102	720-45605	STRUCTURE, MANHOLE, RECONSTRUCTED	60.00	LFT
0103	720-45615	STRUCTURE, INLET, RECONSTRUCTED	60.00	LFT
0104	722-01066	HYDRODEMOLITION	368.00	SYS
0105	722-12380	BRIDGE DECK OVERLAY, BUDGET	6500.00	DOL

0106	722-12382	TRANSVERSE GROOVING	395.00	SYS
0107	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	368.00	SYS
0108	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	50.00	SFT
0109	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.00	EACH
0110	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1800.00	LFT
0111	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	24.00	LFT
0112	801-06640	CONSTRUCTION SIGN, A	274.00	EACH
0113	801-06645	CONSTRUCTION SIGN, B	112.00	EACH
0114	801-06775	MAINTAINING TRAFFIC	1.00	LS
0115	801-07118	BARRICADE, III-A	24.00	LFT
0116	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	350.00	LFT
0117	801-12082	FIXED TEMPORARY SIGNAL	1.00	LS
0118	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	383.00	LFT
0119	802-07060	SIGN, SHEET, RELOCATE	34.00	EACH
0120	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	154.00	SFT
0121	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	32.00	EACH
0122	805-01842	HANDHOLE SIGNAL TYPE 1	6.00	EACH
0123	805-01843	SIGNAL HANDHOLE ADJUST TO GRADE	12.00	EACH
0124	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	4.00	EACH
0125	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	17.00	EACH
0126	805-05405	SIGNAL POLE, PEDESTAL, 4FT	14.00	EACH
0127	805-05405	SIGNAL POLE, PEDESTAL, 4FT	1.00	EACH
0128	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, 2 CHANNEL	1.00	EACH
0129	805-11813	CONDUIT, PVC, 2 IN. SCHEDULE 80	1935.00	LFT
0130	805-11817	PEDESTRIAN PUSH BUTTON, APS	28.00	EACH
0131	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	15212.00	LFT
0132	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	2850.00	LFT
0133	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	1810.00	LFT
0134	805-78785	SIGNAL DETECTOR HOUSING	43.00	EACH
0135	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	5122.00	LFT
0136	805-99162	SIGNAL POLE, PEDESTAL, 11 FT	2.00	EACH
0137	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	68.00	LFT
0138	808-04298	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, R X R	2.00	EACH
0139	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	7450.00	LFT
0140	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	101870.00	LFT
0141	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	250.00	LFT
0142	808-06716	LINE, REMOVE	450.00	LFT

0143	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0144	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	4073.00	LFT
0145	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	4212.00	LFT
0146	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	344.00	LFT
0147	808-10047	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, WHITE, 12 IN.	57.00	LFT
0148	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	1.00	EACH
0149	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	2.00	EACH
0150	808-10118	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 24 IN.	16.00	LFT
0151	808-12032	GROOVING FOR PAVEMENT MARKINGS	246985.00	LFT
0152	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	5410.00	LFT
0153	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	118139.00	LFT
0154	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	482.00	LFT
0155	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	1030.00	LFT
0156	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	1704.00	LFT
0157	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	6551.00	LFT
0158	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	85.00	EACH
0159	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	43.00	EACH
0160	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2653.00	EACH
0161	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	2658.00	EACH
0162	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	5837.00	LFT

Call: 441

Contract: R -39995-A

Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED CONCRETE

Line

Item No	Item Code	Description	Quantity	Unit
0163	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	395.00	SYS

Call: 441

Contract: R -39995-A

Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED

Line

Item No	Item Code	Description	Quantity	Unit
0164	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	395.00	SYS

Call: 451

Contract: R -40125-A

Section No.: 1

NEW ROAD CONSTRUCTION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-02240	PAVEMENT REMOVAL	1481.00	SYS
0012	202-99187	FENCE, FARM FIELD, REMOVE	221.00	LFT
0013	203-02000	EXCAVATION, COMMON	4350.00	CYS
0014	205-12108	STORMWATER MANAGEMENT BUDGET	14253.15	DOL
0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0016	205-12618	SWQCP PREPARATION	1.00	LS
0017	207-08266	SUBGRADE TREATMENT, TYPE III	717.00	SYS
0018	207-12498	SUBGRADE TREATMENT, TYPE ID	12888.00	SYS
0019	211-09264	STRUCTURE BACKFILL, TYPE 1	418.00	CYS
0020	301-12234	COMPACTED AGGREGATE NO. 53	563.00	CYS
0021	302-06464	SUBBASE FOR PCCP	900.00	CYS
0022	303-01180	COMPACTED AGGREGATE NO. 53	187.00	TON
0023	306-08034	MILLING, ASPHALT, 1 1/2 IN.	214.00	SYS
0024	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	340.00	TON
0025	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	536.00	TON
0026	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	1347.00	TON
0027	401-10258	JOINT ADHESIVE, SURFACE	2205.00	LFT
0028	401-10259	JOINT ADHESIVE, INTERMEDIATE	2085.00	LFT
0029	401-11785	LIQUID ASPHALT SEALANT	2205.00	LFT
0030	406-05520	ASPHALT FOR TACK COAT	3.00	TON
0031	502-03289	QUALITY ASSURANCE ADJUSTMENT	1.00	DOL

0032	502-06327	PCCP, 10 IN.	3673.00	SYS
0033	503-03489	RETROFITTED TIE BARS	567.00	EACH
0034	503-05240	D-1 CONTRACTION JOINT	1663.00	LFT
0035	603-06040	FENCE, FARM FIELD, 47 IN.	98.00	LFT
0036	604-05528	HMA FOR SIDEWALK	131.00	TON
0037	604-06070	SIDEWALK, CONCRETE	347.00	SYS
0038	604-08086	CURB RAMP, CONCRETE	47.00	SYS
0039	604-12083	DETECTABLE WARNING SURFACES	9.00	SYS
0040	605-06090	CURB, INTEGRAL CONCRETE	217.00	LFT
0041	605-06125	CURB, CONCRETE, MODIFIED	153.00	LFT
0042	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	1295.00	LFT
0043	610-07487	HMA FOR APPROACHES, TYPE B	400.00	TON
0044	615-06490	RIGHT-OF-WAY MARKER	7.00	EACH
0045	615-06505	MONUMENT, B	3.00	EACH
0046	615-06510	MONUMENT, C	1.00	EACH
0047	616-11736	DECORATIVE STONE	60.00	TON
0048	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0049	621-02770	EROSION CONTROL BLANKET	160.00	SYS
0050	621-06545	FERTILIZER	1.00	TON
0051	621-06553	SEED MIXTURE R	63.00	LBS
0052	621-06565	MULCHING MATERIAL	1.00	TON
0053	621-06570	TOPSOIL	1613.00	CYS
0054	621-06570	TOPSOIL	75.00	CYS
0055	621-06574	SODDING	454.00	SYS
0056	621-06574	SODDING	3399.00	SYS
0057	621-98038	MULCH HARDWOOD SHREDDED BARK	120.00	CYS
0058	622-05623	PLANT, CONIFEROUS EVERGREEN, CONE BROAD UPRIGHT, 36 IN.OR UNDER	340.00	EACH
0059	622-05639	PLANT, DECIDUOUS SHRUB, 18 TO 24 IN.	92.00	EACH
0060	622-05645	PLANT, DECIDUOUS TREE, MULTI-STEM, 72 TO 96 IN.	11.00	EACH
0061	622-05648	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. OR UNDER	20.00	EACH
0062	622-05650	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 IN. TO 2.5 IN.	33.00	EACH
0063	622-05654	PLANT, PERENNIAL	191.00	EACH
0064	622-05654	PLANT, PERENNIAL	555.00	EACH
0065	622-05654	PLANT, PERENNIAL	205.00	EACH
0066	622-07764	IRRIGATION SYSTEM	1.00	LS
0067	628-09402	FIELD OFFICE, B	7.00	MOS
0068	702-51863	FIELD DRILLED HOLE IN CONCRETE	567.00	EACH

0069	715-02532	VALVE, WITH BOX, RESTRAINED GATE, DUCTILE IRON, 8 IN.	2.00 EACH
0070	715-04837	PLUG	2.00 EACH
0071	715-05024	PIPE, TYPE 2, CIRCULAR, 36 IN.	77.00 LFT
0072	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	1327.00 LFT
0073	715-05121	PIPE, TYPE 1, CIRCULAR, 18 IN.	70.00 LFT
0074	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	969.00 LFT
0075	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	233.00 LFT
0076	715-05159	PIPE, TYPE 2, CIRCULAR, 42 IN.	22.00 LFT
0077	715-07794	WATER MAIN CONNECTIONS	1.00 EACH
0078	715-07806	PIPE STEEL CASING	100.00 LFT
0079	715-09064	VIDEO INSPECTION FOR PIPE	1301.00 LFT
0080	715-11571	WATER MAIN, DUCTILE IRON, 8 IN.	236.00 LFT
0081	715-11849	RESTRAIN EXISTING JOINT	7.00 EACH
0082	715-46000	PIPE END SECTION, DIAMETER 12 IN.	1.00 EACH
0083	715-46010	PIPE END SECTION, DIAMETER 18 IN.	2.00 EACH
0084	715-46040	PIPE END SECTION, DIAMETER 36 IN.	1.00 EACH
0085	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	3000.00 LFT
0086	718-12306	GEOTEXTILE FOR UNDERDRAIN, TYPE 1B	1195.00 SYS
0087	718-52610	AGGREGATE FOR UNDERDRAINS	120.00 CYS
0088	720-01092	MANHOLE, J15 MODIFIED	2.00 EACH
0089	720-45069	INLET, P12	2.00 EACH
0090	720-45410	MANHOLE, C4	4.00 EACH
0091	720-94612	MANHOLE, K4	1.00 EACH
0092	720-96999	FIRE HYDRANT ASSEMBLY	1.00 EACH
0093	720-98174	INLET, B15	4.00 EACH
0094	720-98555	INLET, C15	4.00 EACH
0095	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.00 EACH
0096	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2400.00 LFT
0097	801-06640	CONSTRUCTION SIGN, A	8.00 EACH
0098	801-06645	CONSTRUCTION SIGN, B	2.00 EACH
0099	801-06710	FLASHING ARROW SIGN	90.00 DAY
0100	801-06775	MAINTAINING TRAFFIC	1.00 LS
0101	801-07118	BARRICADE, III-A	48.00 LFT
0102	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	72.00 LFT
0103	802-07058	SIGN, SHEET, ASSEMBLY RELOCATE	2.00 EACH
0104	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	80.00 SFT
0105	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	20.00 SFT

0106	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	21.00	SFT
0107	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	4.00	EACH
0108	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	164.00	LFT
0109	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	4.00	EACH
0110	805-02445	CONTROLLER AND CABINET, P1	1.00	EACH
0111	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	4.00	EACH
0112	805-05405	SIGNAL POLE, PEDESTAL, 4FT	4.00	EACH
0113	805-08214	CONDUIT, PVC, 2 IN. SCHEDULE 40	759.00	LFT
0114	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, 2 CHANNEL	5.00	EACH
0115	805-11744	HANDHOLE SIGNAL TYPE 2	10.00	EACH
0116	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	615.00	LFT
0117	805-11817	PEDESTRIAN PUSH BUTTON, APS	4.00	EACH
0118	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	8.00	EACH
0119	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	2.00	EACH
0120	805-78415	SPAN, CATENARY, AND TETHER	4.00	EACH
0121	805-78420	DISCONNECT HANGER	4.00	EACH
0122	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	19.00	LFT
0123	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	2220.00	LFT
0124	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	1267.00	LFT
0125	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	11.00	LFT
0126	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	789.00	LFT
0127	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	2993.00	LFT
0128	805-78785	SIGNAL DETECTOR HOUSING	9.00	EACH
0129	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	680.00	LFT
0130	805-78925	CONTROLLER CABINET FOUNDATION, P1	1.00	EACH
0131	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	4.00	EACH
0132	807-02191	HANDHOLE LIGHTING	1.00	EACH
0133	807-02782	LUMINAIRE MAST ARM 12 FT	4.00	EACH
0134	807-03950	LUMINAIRE ORNAMENTAL	6.00	EACH
0135	807-03950	LUMINAIRE ORNAMENTAL	5.00	EACH
0136	807-04654	LIGHT POLE	5.00	EACH
0137	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	1254.00	LFT
0138	807-11848	LIGHTING FOUNDATION, CONCRETE WITH GROUNDING 24 IN. DIA X 96 IN.	11.00	EACH
0139	807-12202	LUMINAIRE, LOW LUMEN ROADWAY	4.00	EACH
0140	807-85488	LIGHT POLE, 30 FT. E.M.H. 8.0 FT. MAST ARM, BREAKAWAY BASE	6.00	EACH
0141	807-86810	SERVICE POINT, II	2.00	EACH
0142	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	2296.00	LFT

0143	807-86910	CONNECTOR KIT, UNFUSED	15.00 EACH
0144	807-86915	CONNECTOR KIT, FUSED	15.00 EACH
0145	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	35.00 EACH
0146	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	4.00 EACH
0147	807-86930	INSULATION LINK, NON-WATERPROOFED	27.00 EACH
0148	807-86935	INSULATION LINK, WATERPROOFED	4.00 EACH
0149	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	299.00 LFT
0150	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	352.00 LFT
0151	808-06716	LINE, REMOVE	576.00 LFT
0152	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	586.00 LFT
0153	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	1733.00 LFT
0154	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	572.00 LFT
0155	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	123.00 LFT
0156	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	2.00 EACH
0157	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	208.00 LFT
0158	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	6.00 EACH
0159	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	474.00 LFT
0160	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	218.00 LFT
0161	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	2.00 EACH
0162	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1.00 EACH
0163	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	821.00 LFT

Call: 481

Contract: R -40650-A

Section No.: 1 ASPHALT RESURFACE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	3084.00	SYS
0013	203-02000	EXCAVATION, COMMON	3470.00	CYS
0014	205-11626	PUMP AROUND	4.00	EACH
0015	205-12108	STORMWATER MANAGEMENT BUDGET	25918.00	DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	205-12618	SWQCP PREPARATION	1.00	LS
0018	207-09935	SUBGRADE TREATMENT, TYPE IC	920.00	SYS
0019	207-09935	SUBGRADE TREATMENT, TYPE IC	204.00	SYS
0020	207-12498	SUBGRADE TREATMENT, TYPE ID	5236.00	SYS
0021	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	920.00	SYS
0022	301-12234	COMPACTED AGGREGATE NO. 53	245.00	CYS
0023	302-06464	SUBBASE FOR PCCP	236.00	CYS
0024	302-07455	DENSE GRADED SUBBASE	12.00	CYS
0025	303-01180	COMPACTED AGGREGATE NO. 53	326.00	TON
0026	303-07449	COMPACTED AGGREGATE NO. 73	2248.00	TON
0027	304-12627	HMA PATCHING FULL DEPTH TYPE D	3.00	TON
0028	304-12628	HMA PATCHING PARTIAL DEPTH TYPE D	2132.00	TON
0029	306-08034	MILLING, ASPHALT, 1 1/2 IN.	273483.00	SYS
0030	306-08043	MILLING, TRANSITION	2856.00	SYS
0031	306-08432	MILLING, APPROACH	5783.00	SYS

0032	401-06264	PROFILOGRAPH, HMA	1.00	LS
0033	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	5343.00	TON
0034	401-07399	QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm	1013.00	TON
0035	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	2894.00	TON
0036	401-10258	JOINT ADHESIVE, SURFACE	137012.00	LFT
0037	401-10259	JOINT ADHESIVE, INTERMEDIATE	5499.00	LFT
0038	401-11785	LIQUID ASPHALT SEALANT	196593.00	LFT
0039	406-05520	ASPHALT FOR TACK COAT	28.00	TON
0040	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	0.70	TON
0041	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	28.00	TON
0042	410-09530	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm - SMA	16646.00	TON
0043	410-12665	SMA SPRAY PAVER EMULSION	110.00	TON
0044	503-12477	TERMINAL JOINT, TYPE HMA	168.00	LFT
0045	506-06333	PCCP PATCHING, FULL DEPTH	200.00	SYS
0046	601-02241	GUARDRAIL, REMOVE	3573.00	LFT
0047	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	1465.00	LFT
0048	601-12284	GUARDRAIL, MGS W-BEAM, DOUBLE FACED 6 FT 3 IN SPACING	556.00	LFT
0049	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	1.00	EACH
0050	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	10.00	EACH
0051	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	2.00	EACH
0052	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0053	601-94690	GUARDRAIL, END TREATMENT, MS	4.00	EACH
0054	602-06729	BARRIER, DELINEATOR	32.00	EACH
0055	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	121027.00	LFT
0056	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	920.00	SYS
0057	610-07487	HMA FOR APPROACHES, TYPE B	478.00	TON
0058	616-06405	RIPRAP, REVETMENT	1423.00	TON
0059	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	1423.00	SYS
0060	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0061	621-06545	FERTILIZER	0.16	TON
0062	621-06559	MULCHED SEEDING R	1303.00	SYS
0063	621-12612	SEED MIXTURE FLOODPLAIN	2.98	LBS
0064	628-09402	FIELD OFFICE, B	10.00	MOS
0065	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0066	702-51863	FIELD DRILLED HOLE IN CONCRETE	92.00	EACH
0067	703-06029	REINFORCING BARS, EPOXY COATED	63410.00	LBS
0068	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	392.00	EACH

0069	704-51002	CONCRETE, C, SUPERSTRUCTURE	8.00	CYS
0070	706-09960	RAILING, CONCRETE FC	8.00	LFT
0071	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	16.00	EACH
0072	708-51813	PNEUMATICALLY PLACED MORTAR	31.00	SFT
0073	708-51814	WELDED STEEL WIRE REINFORCEMENT	31.00	SFT
0074	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0075	709-51821	SURFACE SEAL	1.00	LS
0076	709-51821	SURFACE SEAL	1.00	LS
0077	709-51821	SURFACE SEAL	1.00	LS
0078	709-51821	SURFACE SEAL	1.00	LS
0079	710-09158	PATCHING CONCRETE STRUCTURES	224.00	SFT
0080	715-01354	CLEAN EXISTING PIPE	4370.00	LFT
0081	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	5250.00	LFT
0082	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	28.00	EACH
0083	718-06526	HMA FOR UNDERDRAINS	114.00	TON
0084	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	3310.00	SYS
0085	718-52610	AGGREGATE FOR UNDERDRAINS	308.00	CYS
0086	722-01066	HYDRODEMOLITION	2278.00	SYS
0087	722-12380	BRIDGE DECK OVERLAY, BUDGET	55578.00	DOL
0088	722-12382	TRANSVERSE GROOVING	3154.00	SYS
0089	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	2278.00	SYS
0090	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	2050.00	SFT
0091	722-51874	OVERLAY DAM	364.00	SFT
0092	724-12103	PRE-COMPRESSED FOAM JOINT	364.00	LFT
0093	727-90308	EPOXY INJECTION, CRACK PREPARATION	35.00	LFT
0094	727-90309	EPOXY INJECTION, EPOXY MATERIAL	3.00	GAL
0095	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0096	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0097	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	30.00	EACH
0098	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	10.00	EACH
0099	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	31137.00	LFT
0100	801-06640	CONSTRUCTION SIGN, A	107.00	EACH
0101	801-06710	FLASHING ARROW SIGN	244.00	DAY
0102	801-06775	MAINTAINING TRAFFIC	1.00	LS
0103	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	4.00	EACH
0104	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	2372.00	LFT
0105	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	784.00	LFT

0106	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	111.00	LFT
0107	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	11.00	EACH
0108	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	89.00	SFT
0109	808-03179	PAVEMENT MESSAGE MARKING PREFORMED PLASTIC, WORD ONLY	6.00	EACH
0110	808-06716	LINE, REMOVE	12588.00	LFT
0111	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0112	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	573.00	LFT
0113	808-12032	GROOVING FOR PAVEMENT MARKINGS	154725.00	LFT
0114	808-75051	LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	70819.00	LFT
0115	808-75054	LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN.	66106.00	LFT
0116	808-75059	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 4 IN.	16029.00	LFT
0117	808-75067	TRANSVERSE MARKING, PREFORMED PLASTIC, STOP LINE, WHITE, 24 IN.	135.00	LFT
0118	808-75071	PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC, LANE INDICATION ARROW	10.00	EACH
0119	808-75340	PAVEMENT MESSAGE MARKING, THERMOPLASTIC R X R	3.00	EACH
0120	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	915.00	EACH
0121	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	919.00	EACH
0122	808-91662	TRANSVERSE MARKING, PREFORMED PLASTIC, CROSSHATCH LINE, WHITE 12 IN.	144.00	LFT

Call: 481

Contract: R -40650-A

Section No.: 2 BRIDGE DECK OVERLAY LATEX MODIFIED CONCRETE

Line

Item No	Item Code	Description	Quantity	Unit
0123	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	2278.00	SYS

Call: 481

Contract: R -40650-A

Section No.: 3 BRIDGE DECK OVERLAY SILICA FUME MODIFIED

Line

Item No	Item Code	Description	Quantity	Unit
0124	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	2278.00	SYS

Call: 491

Contract: R -40894-A

Section No.: 1 ROAD RECONSTRUCTION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-01261	TESTING FOR ASBESTOS	2.00	EACH
0013	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00	LS
0014	202-93741	GUARDRAIL, END TREATMENT, REMOVE	4.00	EACH
0015	202-96133	PIPE, REMOVE	772.00	LFT
0016	203-02000	EXCAVATION, COMMON	42310.00	CYS
0017	203-02070	BORROW	28345.00	CYS
0018	203-11340	REINFORCED SOIL SLOPE	19184.00	SFT
0019	203-51223	EXCAVATION, WATERWAY	40.00	CYS
0020	205-11626	PUMP AROUND	2.00	EACH
0021	205-12108	STORMWATER MANAGEMENT BUDGET	206499.00	DOL
0022	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0023	205-12618	SWQCP PREPARATION	1.00	LS
0024	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	70.00	CYS
0025	206-51235	COFFERDAM	1.00	LS
0026	207-09935	SUBGRADE TREATMENT, TYPE IC	5500.00	SYS
0027	207-12635	SUBGRADE TREATMENT, TYPE IBC	43986.00	SYS
0028	211-09264	STRUCTURE BACKFILL, TYPE 1	920.00	CYS
0029	211-09265	STRUCTURE BACKFILL, TYPE 2	158.00	CYS
0030	211-09268	STRUCTURE BACKFILL, TYPE 5	1175.00	CYS
0031	301-12232	COMPACTED AGGREGATE NO. 5	69.00	CYS

0032	301-12234	COMPACTED AGGREGATE NO. 53	6472.00	CYS
0033	303-01180	COMPACTED AGGREGATE NO. 53	7708.00	TON
0034	303-08210	COMPACTED AGGREGATE NO. 53 TEMPORARY FOR DRIVEWAYS	2625.00	TON
0035	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	3040.00	TON
0036	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	5150.00	TON
0037	401-10258	JOINT ADHESIVE, SURFACE	16909.00	LFT
0038	401-10259	JOINT ADHESIVE, INTERMEDIATE	16909.00	LFT
0039	401-11785	LIQUID ASPHALT SEALANT	16909.00	LFT
0040	406-05520	ASPHALT FOR TACK COAT	10.00	TON
0041	601-02241	GUARDRAIL, REMOVE	466.00	LFT
0042	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	2143.00	LFT
0043	601-12287	GUARDRAIL, MGS, LONG SPAN, TYPE 1	1.00	EACH
0044	601-12288	GUARDRAIL, MGS, LONG SPAN, TYPE 2	4.00	EACH
0045	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	1.00	EACH
0046	601-94689	GUARDRAIL, END TREATMENT, OS	8.00	EACH
0047	603-06040	FENCE, FARM FIELD, 47 IN.	1141.00	LFT
0048	610-07487	HMA FOR APPROACHES, TYPE B	26.00	TON
0049	611-06497	MAILBOX ASSEMBLY, SINGLE	8.00	EACH
0050	615-06505	MONUMENT, B	52.00	EACH
0051	615-06510	MONUMENT, C	18.00	EACH
0052	615-06520	MONUMENT, RE-ESTABLISH	11.00	EACH
0053	616-05688	RIPRAP, CLASS 1	526.00	TON
0054	616-05689	RIPRAP, CLASS 2	188.00	TON
0055	616-06405	RIPRAP, REVETMENT	2810.00	TON
0056	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	2791.00	SYS
0057	616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	1498.00	SYS
0058	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.00	EACH
0059	621-03909	SEED MIXTURE, NATIVE	412.00	LBS
0060	621-06545	FERTILIZER	5.00	TON
0061	621-06553	SEED MIXTURE R	1458.00	LBS
0062	621-06565	MULCHING MATERIAL	24.00	TON
0063	621-06567	WATER	17.00	KGAL
0064	621-06574	SODDING	4233.00	SYS
0065	622-52436	SIGN, DO NOT MOW OR SPRAY	60.00	EACH
0066	628-09402	FIELD OFFICE, B	18.00	MOS
0067	702-04325	TEMPORARY SHORING	1.00	LS
0068	714-11177	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 8 FT. X 4 FT.	47.00	LFT

0069	714-11309	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 9 FT. X 5 FT.	73.00	LFT
0070	715-05019	PIPE, TYPE 1, CIRCULAR, 36 IN.	42.00	LFT
0071	715-05119	PIPE, TYPE 1, CIRCULAR, 15 IN.	110.00	LFT
0072	715-05121	PIPE, TYPE 1, CIRCULAR, 18 IN.	233.00	LFT
0073	715-05123	PIPE, TYPE 1, CIRCULAR, 24 IN.	166.00	LFT
0074	715-05125	PIPE, TYPE 1, CIRCULAR, 30 IN.	129.00	LFT
0075	715-05128	PIPE, TYPE 1, CIRCULAR, 48 IN.	115.00	LFT
0076	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	152.00	LFT
0077	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	54.00	LFT
0078	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	38.00	LFT
0079	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	190.00	LFT
0080	715-05242	PIPE, TYPE 1, DEFORMED, MIN AREA, 8.9 SFT	42.00	LFT
0081	715-05248	PIPE, TYPE 1, DEFORMED, MIN. AREA 16.6 SFT	64.00	LFT
0082	715-06004	CONCRETE ANCHOR, 48 IN.	4.00	EACH
0083	715-06501	CONCRETE ANCHOR, MIN. AREA 8.9 SFT	2.00	EACH
0084	715-07303	CONCRETE ANCHOR, MIN. AREA 16.7 SFT	2.00	EACH
0085	715-46005	PIPE END SECTION, DIAMETER 15 IN.	22.00	EACH
0086	715-46010	PIPE END SECTION, DIAMETER 18 IN.	12.00	EACH
0087	715-46020	PIPE END SECTION, DIAMETER 24 IN.	10.00	EACH
0088	715-46030	PIPE END SECTION, DIAMETER 30 IN.	6.00	EACH
0089	715-46040	PIPE END SECTION, DIAMETER 36 IN.	2.00	EACH
0090	720-45035	INLET, F7	1.00	EACH
0091	720-45130	INLET, E7 MODIFIED	1.00	EACH
0092	720-45235	CATCH BASIN, E7	1.00	EACH
0093	720-45410	MANHOLE, C4	4.00	EACH
0094	723-11233	STRUCTURE, REINFORCED CONCRETE, THREE-SIDED SECTIONS, 216 IN.X 84 IN.	51.00	LFT
0095	723-11239	STRUCTURE, REINFORCED CONCRETE, THREE-SIDED SECTIONS, 144 IN.X 60 IN.	46.00	LFT
0096	734-10240	CUT-WALL, NO.	1812.00	SFT
0097	734-10240	CUT-WALL, NO.	1760.00	SFT
0098	734-10240	CUT-WALL, NO.	2112.00	SFT
0099	734-10240	CUT-WALL, NO.	2385.00	SFT
0100	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0101	801-06625	DETOUR ROUTE MARKER ASSEMBLY	12.00	EACH
0102	801-06640	CONSTRUCTION SIGN, A	4.00	EACH
0103	801-06775	MAINTAINING TRAFFIC	1.00	LS
0104	801-07118	BARRICADE, III-A	68.00	LFT
0105	801-07119	BARRICADE, III-B	62.00	LFT

0106	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	421.00	LFT
0107	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	30.00	EACH
0108	802-07060	SIGN, SHEET, RELOCATE	6.00	EACH
0109	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	189.50	SFT
0110	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	31343.00	LFT
0111	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	32317.00	LFT
0112	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	45.00	LFT
0113	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS

Call: 501

Contract: R -40964-A

Section No.: 1 CONCRETE PAVEMENT PRESERVATION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	10.00 EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0004	109-08360	CONTRACT LIENS	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	109-12573	SPECIAL MAINTENANCE	25000.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	202-02240	PAVEMENT REMOVAL	165.00 SYS
0012	202-02274	CURB, CONCRETE INTEGRAL, REMOVE	1139.00 LFT
0013	202-52710	SIDEWALK CONCRETE, REMOVE	734.00 SYS
0014	202-90277	DETECTOR HOUSING, REMOVE	12.00 EACH
0015	202-96022	CONCRETE FOUNDATION, REMOVE	11.00 EACH
0016	205-12108	STORMWATER MANAGEMENT BUDGET	31527.50 DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0018	207-12498	SUBGRADE TREATMENT, TYPE ID	1089.00 SYS
0019	302-06464	SUBBASE FOR PCCP	559.00 CYS
0020	303-01180	COMPACTED AGGREGATE NO. 53	286.00 TON
0021	503-03489	RETROFITTED TIE BARS	428.00 EACH
0022	503-05240	D-1 CONTRACTION JOINT	72.00 LFT
0023	506-06333	PCCP PATCHING, FULL DEPTH	1021.00 SYS
0024	506-06334	PCCP PATCHING, PARTIAL DEPTH	139.00 SYS
0025	507-07480	PROFILING, PCCP	12431.00 SYS
0026	507-08272	JOINTS IN PCCP, SAW AND SEAL	95009.00 LFT
0027	507-12191	JOINT REPAIR, PARTIAL DEPTH	11626.00 SFT
0028	507-12192	JOINT REPAIR, BOTTOM-HALF	600.00 SFT
0029	604-06070	SIDEWALK, CONCRETE	123.00 SYS
0030	604-08086	CURB RAMP, CONCRETE	717.00 SYS
0031	604-12083	DETECTABLE WARNING SURFACES	93.00 SYS

0032	605-06090	CURB, INTEGRAL CONCRETE	1179.00	LFT
0033	605-06255	CENTER CURB, D CONCRETE	179.00	SYS
0034	615-06515	MONUMENT, D	18.00	EACH
0035	615-06527	MONUMENT, SECTION CORNER	2.00	EACH
0036	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0037	621-06567	WATER	2.00	KGAL
0038	621-06575	SODDING, NURSERY	448.00	SYS
0039	628-09403	FIELD OFFICE, C	9.00	MOS
0040	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0041	628-11730	CELLULAR TELEPHONE, TYPE B	1.00	EACH
0042	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0043	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0044	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	18.00	MOS
0045	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0046	720-44000	CASTING, ADJUST TO GRADE	3.00	EACH
0047	720-44000	CASTING, ADJUST TO GRADE	9.00	EACH
0048	720-44025	CASTING, 4, FURNISH AND ADJUST TO GRADE	15.00	EACH
0049	720-44055	CASTING, 10, FURNISH AND ADJUST TO GRADE	12.00	EACH
0050	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	10000.00	LFT
0051	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	450.00	LFT
0052	801-06640	CONSTRUCTION SIGN, A	52.00	EACH
0053	801-06710	FLASHING ARROW SIGN	100.00	DAY
0054	801-06775	MAINTAINING TRAFFIC	1.00	LS
0055	801-06775	MAINTAINING TRAFFIC	1.00	LS
0056	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0057	801-12042	TRUCK MOUNTED ATTENUATOR	100.00	DAY
0058	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	1850.00	LFT
0059	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	28.00	EACH
0060	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	28.00	EACH
0061	805-11817	PEDESTRIAN PUSH BUTTON, APS	28.00	EACH
0062	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	5650.00	LFT
0063	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	8000.00	LFT
0064	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	4000.00	LFT
0065	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	3600.00	LFT
0066	805-78785	SIGNAL DETECTOR HOUSING	12.00	EACH
0067	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1890.00	LFT
0068	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	28.00	EACH

0069	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	25.00	SYS
0070	808-05929	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 8 IN.	2494.00	LFT
0071	808-06716	LINE, REMOVE	15000.00	LFT
0072	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0073	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	900.00	LFT
0074	808-10118	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 24 IN.	28.00	LFT
0075	808-11482	LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN.	525.00	LFT
0076	808-11493	LINE, THERMOPLASTIC, DOTTED, YELLOW, 4 IN.	422.00	LFT
0077	808-12032	GROOVING FOR PAVEMENT MARKINGS	31215.00	LFT
0078	808-75051	LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	8260.00	LFT
0079	808-75054	LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN.	16764.00	LFT
0080	808-75059	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 4 IN.	5584.00	LFT
0081	808-75063	LINE, PREFORMED PLASTIC, BROKEN, YELLOW, 4 IN.	608.00	LFT
0082	808-75071	PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC, LANE INDICATION ARROW	68.00	EACH
0083	808-75256	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 8 IN.	1058.00	LFT
0084	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	6.00	EACH
0085	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	543.00	EACH
0086	808-95638	CENTER CURB PAINTING	696.00	SFT

Call: 511

Contract: R -41102-A

Section No.: 1 ASPHALT RESURFACE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	6.00EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0004	109-08360	CONTRACT LIENS	1.00 DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	202-02279	CURB AND GUTTER, REMOVE	27.00 LFT
0012	202-52710	SIDEWALK CONCRETE, REMOVE	24.00 SYS
0013	202-93741	GUARDRAIL, END TREATMENT, REMOVE	6.00EACH
0014	203-02000	EXCAVATION, COMMON	9.00 CYS
0015	203-02070	BORROW	43.00 CYS
0016	207-12498	SUBGRADE TREATMENT, TYPE ID	4637.00 SYS
0017	303-01180	COMPACTED AGGREGATE NO. 53	1055.00 TON
0018	304-12623	HMA PATCHING FULL DEPTH TYPE B	2551.00 TON
0019	304-12624	HMA PATCHING PARTIAL DEPTH TYPE B	345.00 TON
0020	306-08036	MILLING, ASPHALT, 2 IN.	117767.00 SYS
0021	306-08432	MILLING, APPROACH	1297.00 SYS
0022	401-06264	PROFILOGRAPH, HMA	1.00 LS
0023	401-07340	QC/QA-HMA, 3, 64, SURFACE, 12.5 mm	12955.00 TON
0024	401-10258	JOINT ADHESIVE, SURFACE	47055.00 LFT
0025	401-11785	LIQUID ASPHALT SEALANT	47055.00 LFT
0026	406-05520	ASPHALT FOR TACK COAT	31.00 TON
0027	601-02241	GUARDRAIL, REMOVE	113.00 LFT
0028	601-06035	GUARDRAIL, RESET	1332.00 LFT
0029	601-06053	GUARDRAIL	4.00EACH
0030	601-92948	GUARDRAIL, ADJUST HEIGHT	675.00 LFT
0031	601-94689	GUARDRAIL, END TREATMENT, OS	6.00EACH

0032	604-06070	SIDEWALK, CONCRETE	8.00	SYS
0033	604-08086	CURB RAMP, CONCRETE	14.00	SYS
0034	604-12083	DETECTABLE WARNING SURFACES	4.00	SYS
0035	605-06140	CURB AND GUTTER, CONCRETE	27.00	LFT
0036	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	40407.00	LFT
0037	610-07487	HMA FOR APPROACHES, TYPE B	143.00	TON
0038	615-06520	MONUMENT, RE-ESTABLISH	7.00	EACH
0039	621-06574	SODDING	7.00	SYS
0040	628-09403	FIELD OFFICE, C	9.00	MOS
0041	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	20619.00	LFT
0042	801-06640	CONSTRUCTION SIGN, A	52.00	EACH
0043	801-06645	CONSTRUCTION SIGN, B	15.00	EACH
0044	801-06775	MAINTAINING TRAFFIC	1.00	LS
0045	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	8640.00	LFT
0046	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	83520.00	LFT
0047	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	31460.00	LFT
0048	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	208.00	LFT
0049	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0050	808-75100	TRANSVERSE MARKING, PAINT, CROSSWALK LINE, WHITE, 6 IN.	88.00	LFT

Call: 521

Contract: R -41107-A

Section No.: 1

SMALL STRUCTURE REPLACEMENT

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	3.00EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	3.00EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0005	109-08360	CONTRACT LIENS	1.00 DOL
0006	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0007	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0008	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0009	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0010	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0011	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0012	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0013	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0014	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0015	202-51330	PRESENT STRUCTURE, REMOVE	1.00 LS
0016	202-51330	PRESENT STRUCTURE, REMOVE	1.00 LS
0017	203-02000	EXCAVATION, COMMON	995.00 CYS
0018	203-02070	BORROW	730.00 CYS
0019	203-08607	LINEAR GRADING	1920.00 LFT
0020	205-11626	PUMP AROUND	1.00EACH
0021	205-12108	STORMWATER MANAGEMENT BUDGET	50000.00 DOL
0022	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0023	205-12618	SWQCP PREPARATION	1.00 LS
0024	207-08264	SUBGRADE TREATMENT, TYPE II	147.00 SYS
0025	207-12498	SUBGRADE TREATMENT, TYPE ID	2373.00 SYS
0026	211-09268	STRUCTURE BACKFILL, TYPE 5	244.00 CYS
0027	214-12237	GEOTEXTILE FOR PAVEMENT TYPE 1B	34.00 SYS
0028	301-12233	COMPACTED AGGREGATE NO. 8	27.00 CYS
0029	301-12234	COMPACTED AGGREGATE NO. 53	3.00 CYS
0030	302-07455	DENSE GRADED SUBBASE	6.00 CYS
0031	303-01180	COMPACTED AGGREGATE NO. 53	218.00 TON

0032	304-07494	WIDENING WITH HMA, TYPE C	10.00 TON
0033	304-12623	HMA PATCHING FULL DEPTH TYPE B	442.00 TON
0034	304-12624	HMA PATCHING PARTIAL DEPTH TYPE B	36.00 TON
0035	304-12628	HMA PATCHING PARTIAL DEPTH TYPE D	195.00 TON
0036	306-08034	MILLING, ASPHALT, 1 1/2 IN.	59783.00 SYS
0037	306-08038	MILLING, ASPHALT, 4 IN.	886.00 SYS
0038	306-08432	MILLING, APPROACH	4208.00 SYS
0039	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	95.00 TON
0040	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	4955.60 TON
0041	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	121.00 TON
0042	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	98.00 TON
0043	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	289.00 TON
0044	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	311.00 TON
0045	401-10258	JOINT ADHESIVE, SURFACE	23529.00 LFT
0046	401-10259	JOINT ADHESIVE, INTERMEDIATE	1665.00 LFT
0047	401-11785	LIQUID ASPHALT SEALANT	22719.00 LFT
0048	406-05520	ASPHALT FOR TACK COAT	18.00 TON
0049	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	2.00 TON
0050	601-01700	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 1	1.00EACH
0051	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	185.00 LFT
0052	601-94689	GUARDRAIL, END TREATMENT, OS	3.00EACH
0053	604-06070	SIDEWALK, CONCRETE	117.00 SYS
0054	604-08086	CURB RAMP, CONCRETE	89.00 SYS
0055	604-12083	DETECTABLE WARNING SURFACES	19.00 SYS
0056	605-06120	CURB, CONCRETE	171.00 LFT
0057	610-07487	HMA FOR APPROACHES, TYPE B	220.00 TON
0058	610-07488	HMA FOR APPROACHES, TYPE C	293.00 TON
0059	610-09108	PCCP FOR APPROACHES, 9 IN.	33.00 SYS
0060	615-06505	MONUMENT, B	6.00EACH
0061	616-05688	RIPRAP, CLASS 1	49.00 TON
0062	616-06405	RIPRAP, REVETMENT	76.00 TON
0063	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	143.00 SYS
0064	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00EACH
0065	621-06559	MULCHED SEEDING R	2293.00 SYS
0066	621-06574	SODDING	60.00 SYS
0067	628-09403	FIELD OFFICE, C	12.00 MOS
0068	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00EACH

0069	714-11175	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 6 FT. X 5 FT.	84.00	LFT
0070	714-11192	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 4 FT X 3 FT	60.00	LFT
0071	720-44000	CASTING, ADJUST TO GRADE	15.00	EACH
0072	720-44000	CASTING, ADJUST TO GRADE	8.00	EACH
0073	720-96995	CLEAN INLET	15.00	EACH
0074	801-04308	ROAD CLOSURE SIGN ASSEMBLY	10.00	EACH
0075	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	28836.00	LFT
0076	801-06625	DETOUR ROUTE MARKER ASSEMBLY	64.00	EACH
0077	801-06640	CONSTRUCTION SIGN, A	107.00	EACH
0078	801-06645	CONSTRUCTION SIGN, B	38.00	EACH
0079	801-06710	FLASHING ARROW SIGN	2.00	DAY
0080	801-06775	MAINTAINING TRAFFIC	1.00	LS
0081	801-07118	BARRICADE, III-A	240.00	LFT
0082	801-07119	BARRICADE, III-B	48.00	LFT
0083	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	30.00	LFT
0084	802-91122	SIGN GROUND MOUNTED RESET	3.00	EACH
0085	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	39519.00	LFT
0086	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0087	808-12032	GROOVING FOR PAVEMENT MARKINGS	72231.00	LFT
0088	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	1933.00	LFT
0089	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	30779.00	LFT
0090	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	143.00	LFT
0091	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	450.00	LFT
0092	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	417.00	EACH

Call: 531

Contract: R -41123-A

Section No.: 1

SMALL STRUCTURE PAVED INVERT

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0008	205-11626	PUMP AROUND	1.00EACH
0009	205-12108	STORMWATER MANAGEMENT BUDGET	775.00 DOL
0010	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0011	205-12618	SWQCP PREPARATION	1.00 LS
0012	615-06527	MONUMENT, SECTION CORNER	1.00EACH
0013	616-05689	RIPRAP, CLASS 2	80.00 TON
0014	616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	80.00 SYS
0015	628-09402	FIELD OFFICE, B	6.00 MOS
0016	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00EACH
0017	703-08247	EMBEDDED GALVANIC ANODE	68.00EACH
0018	715-95325	INVERT, CONCRETE PAVED	126.00 LFT
0019	801-06645	CONSTRUCTION SIGN, B	4.00EACH
0020	801-06775	MAINTAINING TRAFFIC	1.00 LS

Call: 541

Contract: R -41126-A

Section No.: 1

SMALL STRUCTURE PIPE LINING

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0009	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0010	205-11626	PUMP AROUND	3.00 EACH
0011	205-12108	STORMWATER MANAGEMENT BUDGET	15871.00 DOL
0012	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0013	205-12618	SWQCP PREPARATION	1.00 LS
0014	301-12232	COMPACTED AGGREGATE NO. 5	1.00 CYS
0015	301-12234	COMPACTED AGGREGATE NO. 53	1.00 CYS
0016	601-06035	GUARDRAIL, RESET	25.00 LFT
0017	615-06490	RIGHT-OF-WAY MARKER	4.00 EACH
0018	616-05688	RIPRAP, CLASS 1	87.00 TON
0019	616-05689	RIPRAP, CLASS 2	518.00 TON
0020	616-06405	RIPRAP, REVETMENT	18.00 TON
0021	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	500.00 SYS
0022	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	160.00 SYS
0023	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00 EACH
0024	621-02770	EROSION CONTROL BLANKET	200.00 SYS
0025	621-06559	MULCHED SEEDING R	1399.00 SYS
0026	628-09402	FIELD OFFICE, B	11.00 MOS
0027	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0028	714-96273	HEADWALL RECONSTRUCT	1.00 LS
0029	725-10203	PIPE LINER, CURED-IN-PLACE, 72 IN	341.00 LFT
0030	725-11288	PIPE LINER, CURED-IN-PLACE, 60"	141.00 LFT
0031	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4500.00 LFT

0032	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	75.00	LFT
0033	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	24.00	LFT
0034	801-06640	CONSTRUCTION SIGN, A	53.00	EACH
0035	801-06645	CONSTRUCTION SIGN, B	10.00	EACH
0036	801-06775	MAINTAINING TRAFFIC	1.00	LS
0037	801-12042	TRUCK MOUNTED ATTENUATOR	30.00	DAY
0038	801-12081	PORTABLE SIGNAL	1.00	LS

Call: 551

Contract: R -41128-A

Section No.: 1 HMA OVERLAY

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
	0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0010	207-12498	SUBGRADE TREATMENT, TYPE ID	181.00	SYS
	0011	303-01180	COMPACTED AGGREGATE NO. 53	67.00	TON
	0012	304-12625	HMA PATCHING FULL DEPTH TYPE C	160.00	TON
	0013	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	340.00	TON
	0014	306-08034	MILLING, ASPHALT, 1 1/2 IN.	112524.00	SYS
	0015	306-08432	MILLING, APPROACH	6008.00	SYS
	0016	401-06264	PROFILOGRAPH, HMA	1.00	LS
	0017	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	9283.00	TON
	0018	401-10258	JOINT ADHESIVE, SURFACE	112880.00	LFT
	0019	401-12483	RAPID PENETRATING EMULSION	112880.00	LFT
	0020	406-05520	ASPHALT FOR TACK COAT	30.00	TON
	0021	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	7.80	TON
	0022	412-09355	FOG SEAL	72650.00	SYS
	0023	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	56773.00	LFT
	0024	610-07487	HMA FOR APPROACHES, TYPE B	496.00	TON
	0025	628-09402	FIELD OFFICE, B	10.00	MOS
	0026	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
	0027	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	3300.00	LFT
	0028	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3300.00	LFT
	0029	801-06640	CONSTRUCTION SIGN, A	44.00	EACH
	0030	801-06775	MAINTAINING TRAFFIC	1.00	LS
	0031	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH

0032	801-12042	TRUCK MOUNTED ATTENUATOR	45.00	DAY
0033	805-09471	SIGNAL CABLE PREFORMED PAVE-OVER LOOP	10.00	EACH
0034	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	420.00	LFT
0035	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	950.00	LFT
0036	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	4514.00	LFT
0037	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	75549.00	LFT
0038	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	42257.00	LFT
0039	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0040	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	100.00	LFT
0041	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	16.00	EACH
0042	808-75350	PAVEMENT MESSAGE MARKING, THERMOPLASTIC SCHOOL	2.00	EACH
0043	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	863.00	EACH
0044	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	766.00	EACH

Call: 561

Contract: R -41187-A

Section No.: 1 BIKE AND PEDESTRIAN FACILITIES

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-02240	PAVEMENT REMOVAL	213.00	SYS
0012	202-02278	CURB, CONCRETE, REMOVE	900.00	LFT
0013	202-52710	SIDEWALK CONCRETE, REMOVE	779.00	SYS
0014	203-02000	EXCAVATION, COMMON	1045.00	CYS
0015	205-12108	STORMWATER MANAGEMENT BUDGET	17554.00	DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	207-08264	SUBGRADE TREATMENT, TYPE II	2577.00	SYS
0018	211-09264	STRUCTURE BACKFILL, TYPE 1	6.00	CYS
0019	211-09265	STRUCTURE BACKFILL, TYPE 2	143.00	CYS
0020	302-07455	DENSE GRADED SUBBASE	117.00	CYS
0021	303-01180	COMPACTED AGGREGATE NO. 53	528.00	TON
0022	304-12623	HMA PATCHING FULL DEPTH TYPE B	165.00	TON
0023	304-12624	HMA PATCHING PARTIAL DEPTH TYPE B	56.00	TON
0024	306-08034	MILLING, ASPHALT, 1 1/2 IN.	667.00	SYS
0025	406-05520	ASPHALT FOR TACK COAT	2.00	TON
0026	604-06070	SIDEWALK, CONCRETE	2375.00	SYS
0027	604-08086	CURB RAMP, CONCRETE	132.00	SYS
0028	604-12083	DETECTABLE WARNING SURFACES	22.00	SYS
0029	605-06120	CURB, CONCRETE	2533.00	LFT
0030	605-06121	CURB, CONCRETE B	137.00	LFT
0031	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	83.00	LFT

0032	610-07487	HMA FOR APPROACHES, TYPE B	279.00 TON
0033	610-08446	PCCP FOR APPROACHES, 6 IN.	354.00 SYS
0034	610-09108	PCCP FOR APPROACHES, 9 IN.	346.00 SYS
0035	611-08232	MAILBOX ASSEMBLY, RESET SINGLE	7.00 EACH
0036	621-06570	TOPSOIL	374.00 CYS
0037	621-06574	SODDING	3363.00 SYS
0038	622-05651	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2.5 TO 3.5 IN.	14.00 EACH
0039	628-09402	FIELD OFFICE, B	8.00 MOS
0040	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0041	715-05147	PIPE, TYPE 2, CIRCULAR, 8 IN.	29.00 LFT
0042	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	152.00 LFT
0043	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	109.00 LFT
0044	715-09064	VIDEO INSPECTION FOR PIPE	264.00 LFT
0045	720-01091	MANHOLE, C10 MODIFIED	4.00 EACH
0046	720-45015	INLET, A8	1.00 EACH
0047	720-45045	INLET, J10	8.00 EACH
0048	720-45410	MANHOLE, C4	1.00 EACH
0049	720-90984	MANHOLE, C2	1.00 EACH
0050	801-03290	CONSTRUCTION SIGN, C	5.00 EACH
0051	801-04308	ROAD CLOSURE SIGN ASSEMBLY	3.00 EACH
0052	801-06625	DETOUR ROUTE MARKER ASSEMBLY	14.00 EACH
0053	801-06640	CONSTRUCTION SIGN, A	50.00 EACH
0054	801-06775	MAINTAINING TRAFFIC	1.00 LS
0055	801-07118	BARRICADE, III-A	24.00 LFT
0056	801-07119	BARRICADE, III-B	24.00 LFT
0057	802-91122	SIGN GROUND MOUNTED RESET	20.00 EACH
0058	805-90267	CONDUIT, STEEL, GALVANIZED, 3 IN.	25.00 LFT
0059	807-02191	HANDHOLE LIGHTING	1.00 EACH
0060	807-02194	SERVICE POINT II MODIFIED	1.00 EACH
0061	807-03950	LUMINAIRE ORNAMENTAL	12.00 EACH
0062	807-03951	LIGHT POLE ORNAMENTAL	12.00 EACH
0063	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	1440.00 LFT
0064	807-12184	LIGHTING FOUNDATION, CONCRETE WITH GROUNDING 24 IN. DIA X 72 IN.	12.00 EACH
0065	808-06716	LINE, REMOVE	1213.00 LFT
0066	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	1420.00 LFT
0067	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	68.00 LFT
0068	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	321.00 LFT

0069	808-12032	GROOVING FOR PAVEMENT MARKINGS	1420.00	LFT
0070	808-12273	TRANSVERSE MARKING, THERMOPLASTIC, PARKING LINE, WHITE 4 IN.	1105.00	LFT

Call: 581

Contract: R -41871-A

Section No.: 1 ASPHALT RESURFACE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02279	CURB AND GUTTER, REMOVE	69.00	LFT
0013	202-52710	SIDEWALK CONCRETE, REMOVE	465.00	SYS
0014	203-08607	LINEAR GRADING	3160.00	LFT
0015	205-12108	STORMWATER MANAGEMENT BUDGET	23950.00	DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	207-12498	SUBGRADE TREATMENT, TYPE ID	2552.00	SYS
0018	303-07449	COMPACTED AGGREGATE NO. 73	4353.00	TON
0019	304-12623	HMA PATCHING FULL DEPTH TYPE B	1136.00	TON
0020	304-12624	HMA PATCHING PARTIAL DEPTH TYPE B	150.00	TON
0021	306-08034	MILLING, ASPHALT, 1 1/2 IN.	2512.00	SYS
0022	306-08036	MILLING, ASPHALT, 2 IN.	16908.00	SYS
0023	306-08042	MILLING, SCARIFICATION	160525.00	SYS
0024	306-08043	MILLING, TRANSITION	3400.00	SYS
0025	306-08432	MILLING, APPROACH	5550.00	SYS
0026	401-06264	PROFILOGRAPH, HMA	1.00	LS
0027	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	15614.00	TON
0028	401-10258	JOINT ADHESIVE, SURFACE	66220.00	LFT
0029	401-11785	LIQUID ASPHALT SEALANT	66220.00	LFT
0030	406-05520	ASPHALT FOR TACK COAT	49.00	TON
0031	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	14.00	TON

0032	604-06070	SIDEWALK, CONCRETE	208.00	SYS
0033	604-08086	CURB RAMP, CONCRETE	257.00	SYS
0034	604-12083	DETECTABLE WARNING SURFACES	59.00	SYS
0035	605-06120	CURB, CONCRETE	119.00	LFT
0036	605-97937	CURB AND GUTTER, ROLL CURB	69.00	LFT
0037	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	55282.00	LFT
0038	610-07487	HMA FOR APPROACHES, TYPE B	513.00	TON
0039	611-08232	MAILBOX ASSEMBLY, RESET SINGLE	4.00	EACH
0040	615-06505	MONUMENT, B	6.00	EACH
0041	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0042	621-06559	MULCHED SEEDING R	1060.00	SYS
0043	621-06575	SODDING, NURSERY	297.00	SYS
0044	628-09402	FIELD OFFICE, B	9.00	MOS
0045	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0046	628-11730	CELLULAR TELEPHONE, TYPE B	1.00	EACH
0047	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0048	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0049	628-11780	CELLULAR TELEPHONE SERVICE, 500 MIN.	18.00	MOS
0050	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0051	628-11977	COMPUTER SYSTEM	1.00	EACH
0052	720-44000	CASTING, ADJUST TO GRADE	10.00	EACH
0053	720-44000	CASTING, ADJUST TO GRADE	10.00	EACH
0054	801-04308	ROAD CLOSURE SIGN ASSEMBLY	14.00	EACH
0055	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	6168.00	LFT
0056	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	262.00	LFT
0057	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	97.00	LFT
0058	801-06640	CONSTRUCTION SIGN, A	78.00	EACH
0059	801-06645	CONSTRUCTION SIGN, B	44.00	EACH
0060	801-06775	MAINTAINING TRAFFIC	1.00	LS
0061	801-07119	BARRICADE, III-B	280.00	LFT
0062	801-12042	TRUCK MOUNTED ATTENUATOR	60.00	DAY
0063	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	22.00	LFT
0064	802-07060	SIGN, SHEET, RELOCATE	2.00	EACH
0065	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	13810.00	LFT
0066	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	122929.00	LFT
0067	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	32271.00	LFT
0068	808-06716	LINE, REMOVE	2781.00	LFT

0069	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	97.00	LFT
0070	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0071	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	1834.00	LFT
0072	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	787.00	LFT
0073	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	160.00	LFT
0074	808-75100	TRANSVERSE MARKING, PAINT, CROSSWALK LINE, WHITE, 6 IN.	1067.00	LFT
0075	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1120.00	EACH

Call: 601

Contract: R -42106-A

Section No.: 1 ASPHALT RESURFACE

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
	0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0012	201-02255	TREE 18 IN., REMOVE	1.00	EACH
	0013	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0014	202-02278	CURB, CONCRETE, REMOVE	1300.00	LFT
	0015	202-52710	SIDEWALK CONCRETE, REMOVE	2555.00	SYS
	0016	202-86946	HANDHOLE, REMOVE	2.00	EACH
	0017	202-90277	DETECTOR HOUSING, REMOVE	30.00	EACH
	0018	203-02000	EXCAVATION, COMMON	165.00	CYS
	0019	205-12108	STORMWATER MANAGEMENT BUDGET	11972.00	DOL
	0020	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0021	207-12498	SUBGRADE TREATMENT, TYPE ID	180.00	SYS
	0022	303-07449	COMPACTED AGGREGATE NO. 73	440.00	TON
	0023	304-12625	HMA PATCHING FULL DEPTH TYPE C	100.00	TON
	0024	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	1101.00	TON
	0025	306-08036	MILLING, ASPHALT, 2 IN.	98880.00	SYS
	0026	306-08432	MILLING, APPROACH	12200.00	SYS
	0027	401-07347	QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	10950.00	TON
	0028	401-10258	JOINT ADHESIVE, SURFACE	67860.00	LFT
	0029	401-11785	LIQUID ASPHALT SEALANT	67860.00	LFT
	0030	406-05520	ASPHALT FOR TACK COAT	30.00	TON
	0031	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	6.00	TON

0032	604-03643	BRICK PAVERS	190.00	SYS
0033	604-08086	CURB RAMP, CONCRETE	1770.00	SYS
0034	604-12083	DETECTABLE WARNING SURFACES	185.00	SYS
0035	604-12084	DETECTABLE WARNING SURFACES, RETROFIT	17.00	SYS
0036	605-02493	CURB, ISLAND CONCRETE	35.00	SYS
0037	605-06120	CURB, CONCRETE	2745.00	LFT
0038	605-06140	CURB AND GUTTER, CONCRETE	270.00	LFT
0039	610-07488	HMA FOR APPROACHES, TYPE C	1280.00	TON
0040	615-06520	MONUMENT, RE-ESTABLISH	1.00	EACH
0041	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0042	621-06575	SODDING, NURSERY	440.00	SYS
0043	628-09403	FIELD OFFICE, C	12.00	MOS
0044	628-11976	COMPUTER SYSTEM EQUIPMENT	4.00	EACH
0045	720-01894	CASTING, FURNISH AND ADJUST TO GRADE	3.00	EACH
0046	720-44000	CASTING, ADJUST TO GRADE	14.00	EACH
0047	720-44000	CASTING, ADJUST TO GRADE	50.00	EACH
0048	720-44000	CASTING, ADJUST TO GRADE	33.00	EACH
0049	720-94840	CASTING, WATER VALVE, ADJUST TO GRADE	12.00	EACH
0050	801-03290	CONSTRUCTION SIGN, C	2.00	EACH
0051	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	8010.00	LFT
0052	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	8010.00	LFT
0053	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	2230.00	LFT
0054	801-06640	CONSTRUCTION SIGN, A	104.00	EACH
0055	801-06775	MAINTAINING TRAFFIC	1.00	LS
0056	802-04089	SIGN, SHEET, REMOVE	4.00	EACH
0057	802-07060	SIGN, SHEET, RELOCATE	2.00	EACH
0058	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	414.50	SFT
0059	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	57.00	SFT
0060	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	484.00	SFT
0061	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	10.00	EACH
0062	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	25.00	EACH
0063	805-01824	SPAN, CATENARY, AND TETHER, TIGHTEN	22.00	EACH
0064	805-01842	HANDHOLE SIGNAL TYPE 1	2.00	EACH
0065	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	680.00	LFT
0066	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00	LS
0067	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	64.00	EACH
0068	805-02445	CONTROLLER AND CABINET, P1	5.00	EACH

0069	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	14.00 EACH
0070	805-03372	TETHER FOR SIGNAL	22.00 EACH
0071	805-04133	SIGNAL POLE, PEDESTAL, 12FT	14.00 EACH
0072	805-06364	FIBER OPTIC BREAKOUT KIT	5.00 EACH
0073	805-06483	CONTROLLER	7.00 EACH
0074	805-10107	WIRELESS MAGNETOMETER DETECTOR	193.00 EACH
0075	805-11373	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 15 FT.	1.00 EACH
0076	805-11374	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 20 FT	4.00 EACH
0077	805-11375	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 25 FT.	3.00 EACH
0078	805-11377	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 35 FT.	2.00 EACH
0079	805-11378	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 40 FT.	1.00 EACH
0080	805-11384	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, B	11.00 EACH
0081	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	3160.00 LFT
0082	805-11817	PEDESTRIAN PUSH BUTTON, APS	64.00 EACH
0083	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	134.00 EACH
0084	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	9.00 EACH
0085	805-78230	TRAFFIC SIGNAL HEAD, 5 SECTION, 12 IN.	1.00 EACH
0086	805-78415	SPAN, CATENARY, AND TETHER	31.00 EACH
0087	805-78420	DISCONNECT HANGER	53.00 EACH
0088	805-78445	SIGNAL SERVICE	10.00 EACH
0089	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	1440.00 LFT
0090	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	12570.00 LFT
0091	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	3590.00 LFT
0092	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	5190.00 LFT
0093	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	5280.00 LFT
0094	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	1060.00 LFT
0095	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	5770.00 LFT
0096	805-78785	SIGNAL DETECTOR HOUSING	30.00 EACH
0097	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	4235.00 LFT
0098	805-81032	SIGNAL POLE, STEEL STRAIN, 30 FT	24.00 EACH
0099	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	1.00 EACH
0100	805-92504	LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	37.00 EACH
0101	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	6860.00 LFT
0102	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	11950.00 LFT
0103	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	150.00 LFT
0104	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS
0105	808-12032	GROOVING FOR PAVEMENT MARKINGS	44170.00 LFT

0106	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	25360.00	LFT
0107	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	105.00	LFT
0108	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	1490.00	LFT
0109	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	2230.00	LFT
0110	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	7890.00	LFT
0111	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	41.00	EACH
0112	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	1.00	EACH
0113	808-75340	PAVEMENT MESSAGE MARKING, THERMOPLASTIC R X R	4.00	EACH

Call: 611

Contract: R -42136-A

Section No.: 1

REPLACE SUPERSTRUCTURE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	6608.00	SYS
0014	202-02278	CURB, CONCRETE, REMOVE	38.00	LFT
0015	202-02279	CURB AND GUTTER, REMOVE	569.00	LFT
0016	202-02928	CATCH BASIN, REMOVE	4.00	EACH
0017	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0018	202-74035	SIGN, REMOVE	1.00	EACH
0019	202-74055	OVERHEAD SIGN STRUCTURE, BOX TRUSS, REMOVE	1.00	EACH
0020	202-91385	INLET, REMOVE	3.00	EACH
0021	202-93741	GUARDRAIL, END TREATMENT, REMOVE	1.00	EACH
0022	202-94954	BARRIER WALL, CONCRETE, REMOVE	83.00	LFT
0023	202-95027	IMPACT ATTENUATOR, REMOVE	4.00	EACH
0024	202-96133	PIPE, REMOVE	884.00	LFT
0025	202-99626	FOUNDATION FOR SIGNING, REMOVE	2.00	EACH
0026	203-02000	EXCAVATION, COMMON	9450.00	CYS
0027	203-02070	BORROW	4750.00	CYS
0028	205-11626	PUMP AROUND	1.00	EACH
0029	205-12108	STORMWATER MANAGEMENT BUDGET	55990.00	DOL
0030	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0031	205-12618	SWQCP PREPARATION	1.00	LS

0032	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	40.00	CYS
0033	207-08264	SUBGRADE TREATMENT, TYPE II	168.00	SYS
0034	207-09935	SUBGRADE TREATMENT, TYPE IC	3002.00	SYS
0035	207-12498	SUBGRADE TREATMENT, TYPE ID	7600.00	SYS
0036	211-06467	AGGREGATE FOR END BENT BACKFILL	38.00	CYS
0037	211-09264	STRUCTURE BACKFILL, TYPE 1	612.00	CYS
0038	211-09265	STRUCTURE BACKFILL, TYPE 2	211.00	CYS
0039	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	3002.00	SYS
0040	301-12231	COMPACTED AGGREGATE NO. 2	15.00	CYS
0041	301-12234	COMPACTED AGGREGATE NO. 53	30.00	CYS
0042	302-06464	SUBBASE FOR PCCP	52.00	CYS
0043	303-01180	COMPACTED AGGREGATE NO. 53	3041.00	TON
0044	304-12625	HMA PATCHING FULL DEPTH TYPE C	888.00	TON
0045	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	599.00	TON
0046	306-08034	MILLING, ASPHALT, 1 1/2 IN.	57837.00	SYS
0047	401-06264	PROFILOGRAPH, HMA	1.00	LS
0048	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	206.00	TON
0049	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	5313.00	TON
0050	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	318.00	TON
0051	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	1289.00	TON
0052	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	591.00	TON
0053	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	3753.00	TON
0054	401-10258	JOINT ADHESIVE, SURFACE	62773.00	LFT
0055	401-10259	JOINT ADHESIVE, INTERMEDIATE	6586.00	LFT
0056	401-11785	LIQUID ASPHALT SEALANT	62773.00	LFT
0057	406-05520	ASPHALT FOR TACK COAT	26.00	TON
0058	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	1.00	TON
0059	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	2.00	TON
0060	503-12477	TERMINAL JOINT, TYPE HMA	68.00	LFT
0061	601-01740	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 4	2.00	EACH
0062	601-02241	GUARDRAIL, REMOVE	1154.00	LFT
0063	601-06233	IMPACT ATTENUATOR, ED-W1, TL-3	2.00	EACH
0064	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	932.00	LFT
0065	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	3.00	EACH
0066	601-12291	GUARDRAIL MGS TRANSITION WITH CURB	2.00	EACH
0067	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	2.00	EACH
0068	601-94689	GUARDRAIL, END TREATMENT, OS	2.00	EACH

0069	601-94690	GUARDRAIL, END TREATMENT, MS	1.00 EACH
0070	602-06729	BARRIER, DELINEATOR	36.00 EACH
0071	602-11938	CONCRETE BARRIER, MODIFIED SECTION	420.00 CYS
0072	605-06120	CURB, CONCRETE	38.00 LFT
0073	605-06145	CURB AND GUTTER, B, CONCRETE	569.00 LFT
0074	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	30590.00 LFT
0075	607-06335	PAVED SIDE DITCH, A	676.00 LFT
0076	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	233.00 SYS
0077	610-07487	HMA FOR APPROACHES, TYPE B	37.00 TON
0078	615-06490	RIGHT-OF-WAY MARKER	2.00 EACH
0079	616-05688	RIPRAP, CLASS 1	139.00 TON
0080	616-06405	RIPRAP, REVETMENT	1557.00 TON
0081	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	1813.00 SYS
0082	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00 EACH
0083	621-02770	EROSION CONTROL BLANKET	4467.00 SYS
0084	621-06545	FERTILIZER	2.00 TON
0085	621-06553	SEED MIXTURE R	546.00 LBS
0086	621-06559	MULCHED SEEDING R	1398.00 SYS
0087	621-06565	MULCHING MATERIAL	6.00 TON
0088	621-06567	WATER	16.00 kGAL
0089	621-06574	SODDING	3902.00 SYS
0090	628-09402	FIELD OFFICE, B	16.00 MOS
0091	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0092	702-51863	FIELD DRILLED HOLE IN CONCRETE	360.00 EACH
0093	702-92857	CONCRETE, C, SUBSTRUCTURE	43.20 CYS
0094	703-06029	REINFORCING BARS, EPOXY COATED	116005.00 LBS
0095	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	38.00 EACH
0096	704-51002	CONCRETE, C, SUPERSTRUCTURE	257.20 CYS
0097	706-11600	RAILING, CONCRETE FC	44.60 CYS
0098	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00 EACH
0099	709-51821	SURFACE SEAL	1.00 LS
0100	710-09158	PATCHING CONCRETE STRUCTURES	100.00 SFT
0101	715-01354	CLEAN EXISTING PIPE	57.00 LFT
0102	715-04809	PIPE, PVC, 3"	104.00 LFT
0103	715-05024	PIPE, TYPE 2, CIRCULAR, 36 IN.	668.00 LFT
0104	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	612.00 LFT
0105	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	54.00 LFT

0106	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	464.00	LFT
0107	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	49.00	LFT
0108	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	103.00	LFT
0109	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	162.00	LFT
0110	715-05407	PIPE, END BENT DRAIN, 6 IN.	132.00	LFT
0111	715-09064	VIDEO INSPECTION FOR PIPE	1496.00	LFT
0112	715-46005	PIPE END SECTION, DIAMETER 15 IN.	1.00	EACH
0113	715-46040	PIPE END SECTION, DIAMETER 36 IN.	1.00	EACH
0114	718-12306	GEOTEXTILE FOR UNDERDRAIN, TYPE 1B	128.00	SYS
0115	718-12307	GEOTEXTILE FOR UNDERDRAIN, TYPE 2A	1167.00	SYS
0116	718-52610	AGGREGATE FOR UNDERDRAINS	186.00	CYS
0117	720-01355	INLET, CLEAN EXISTING	1.00	EACH
0118	720-08239	MANHOLE, J7 MODIFIED	1.00	EACH
0119	720-09079	INLET, HA5 MODIFIED	2.00	EACH
0120	720-44000	CASTING, ADJUST TO GRADE	1.00	EACH
0121	720-44000	CASTING, ADJUST TO GRADE	1.00	EACH
0122	720-45025	INLET, D6	1.00	EACH
0123	720-45030	INLET, E7	1.00	EACH
0124	720-45035	INLET, F7	1.00	EACH
0125	720-45042	INLET, HA5	2.00	EACH
0126	720-45065	INLET, N12	4.00	EACH
0127	720-45070	INLET, P12A	3.00	EACH
0128	720-45510	MANHOLE, C4 MODIFIED	1.00	EACH
0129	720-95409	MANHOLE, J4 MODIFIED	1.00	EACH
0130	720-95422	MANHOLE, J4	3.00	EACH
0131	720-99315	CATCH BASIN, CLEAN EXISTING	1.00	EACH
0132	724-12103	PRE-COMPRESSED FOAM JOINT	68.00	LFT
0133	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.00	EACH
0134	801-03290	CONSTRUCTION SIGN, C	4.00	EACH
0135	801-03291	CONSTRUCTION SIGN, D	7.00	EACH
0136	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00	EACH
0137	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	15952.00	LFT
0138	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	3029.00	LFT
0139	801-06625	DETOUR ROUTE MARKER ASSEMBLY	26.00	EACH
0140	801-06640	CONSTRUCTION SIGN, A	104.00	EACH
0141	801-06645	CONSTRUCTION SIGN, B	19.00	EACH
0142	801-06710	FLASHING ARROW SIGN	420.00	DAY

0143	801-06775	MAINTAINING TRAFFIC	1.00	LS
0144	801-07118	BARRICADE, III-A	96.00	LFT
0145	801-07119	BARRICADE, III-B	144.00	LFT
0146	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	4646.00	LFT
0147	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0148	801-12042	TRUCK MOUNTED ATTENUATOR	60.00	DAY
0149	802-03783	SIGN, PANEL, REMOVE	7.00	EACH
0150	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	93.00	LFT
0151	802-07057	SIGN, PANEL, WITH LEGEND	1700.00	SFT
0152	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	7.00	EACH
0153	802-09225	OVERHEAD SIGN STRUCTURE, BOX TRUSS, TYPE E	1.00	EACH
0154	802-09537	BOX TRUSS SIGN STRUCTURE FOUNDATION, 36 IN. MEDIAN OR SHOULDER	2.00	EACH
0155	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	36.00	SFT
0156	802-12222	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, A	4.00	EACH
0157	802-12224	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, C	6.00	EACH
0158	802-76095	STRUCTURAL STEEL, BREAKAWAY	10400.00	LBS
0159	804-06770	DELINEATOR POST	7.00	EACH
0160	805-09722	CONDUIT, STEEL, GALVANIZED, 1.25 IN. UNDERGROUND	113.00	LFT
0161	807-02191	HANDHOLE LIGHTING	2.00	EACH
0162	807-04653	LIGHTING FOUNDATION	4.00	EACH
0163	807-12199	LUMINAIRE, HIGH LUMEN ROADWAY	26.00	EACH
0164	807-12201	LUMINAIRE, HIGH MAST	42.00	EACH
0165	807-12206	LUMINAIRE, UNDERPASS	8.00	EACH
0166	807-12343	CABLE, POLE CIRCUIT, XHHW, NO 10 COPPER, STRANDED, 1/C	440.00	LFT
0167	807-85740	LIGHT POLE, 40 FT. E.M.H. 5.0 FT. MAST ARM, BREAKAWAY BASE	3.00	EACH
0168	807-85762	LIGHT POLE, 40 FT. E.M.H. 15.0 FT. MAST ARM, BREAKAWAY BASE	1.00	EACH
0169	807-86805	SERVICE POINT, I	1.00	EACH
0170	807-86910	CONNECTOR KIT, UNFUSED	4.00	EACH
0171	807-86915	CONNECTOR KIT, FUSED	4.00	EACH
0172	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	9.00	EACH
0173	807-86930	INSULATION LINK, NON-WATERPROOFED	8.00	EACH
0174	807-86935	INSULATION LINK, WATERPROOFED	8.00	EACH
0175	807-97237	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, 4 1/C	1067.00	LFT
0176	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	17120.00	LFT
0177	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	17070.00	LFT
0178	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0179	808-12046	LINE, PAINT, DOTTED, WHITE, 4 IN.	351.00	LFT

0180	808-75001	LINE, PAINT, BROKEN, WHITE, 5 IN.	3800.00	LFT
0181	808-75008	LINE, PAINT, SOLID, WHITE, 8 IN.	358.00	LFT
0182	808-75072	TRANSVERSE MARKING, PAINT, CROSSHATCH LINE, WHITE 24 IN.	42.00	LFT
0183	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	203.00	EACH
0184	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	210.00	EACH

Call: 611

Contract: R -42136-A

Section No.: 2 REPLACE SUPERSTRUCTURE, STRUCTURAL STEEL, GALVANIZED

Line

Item No	Item Code	Description	Quantity	Unit
0185	711-51038	STRUCTURAL STEEL	1.00	LS

Call: 611

Contract: R -42136-A

Section No.: 3 REPLACE SUPERSTRUCTURE, STRUCTURAL STEEL, METALLIZED

Line

Item No	Item Code	Description	Quantity	Unit
0186	711-51038	STRUCTURAL STEEL	1.00	LS

Call: 615

Contract: R -42670-B

Section No.: 1 IDIQ, PAVEMENT PATCHING

Line			Quantity	Unit
Item No	Item Code	Description		
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0005	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0007	110-12655	MOBILIZATION AND DEMOBILIZATION, IDIQ	96000.00	DOL
0008	304-12625	HMA PATCHING FULL DEPTH TYPE C	750.00	TON
0009	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	1150.00	TON
0010	304-12627	HMA PATCHING FULL DEPTH TYPE D	500.00	TON
0011	304-12628	HMA PATCHING PARTIAL DEPTH TYPE D	500.00	TON
0012	406-05520	ASPHALT FOR TACK COAT	20.00	TON
0013	506-06333	PCCP PATCHING, FULL DEPTH	250.00	SYS
0014	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1000.00	LFT
0015	801-06640	CONSTRUCTION SIGN, A	84.00	EACH
0016	801-06645	CONSTRUCTION SIGN, B	12.00	EACH
0017	801-12440	MAINTAINING TRAFFIC, IDIQ	96000.00	DOL
0018	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	1000.00	LFT
0019	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	2000.00	LFT
0020	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	2000.00	LFT

Call: 621

Contract: R -42988-A

Section No.: 1

SMALL STRUCTURE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-01000	STRUCTURES AND OBSTRUCTIONS, REMOVE	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	790.00	SYS
0013	202-99187	FENCE, FARM FIELD, REMOVE	125.00	LFT
0014	203-02000	EXCAVATION, COMMON	28.00	CYS
0015	205-11626	PUMP AROUND	1.00	EACH
0016	205-12108	STORMWATER MANAGEMENT BUDGET	15556.00	DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0018	205-12618	SWQCP PREPARATION	1.00	LS
0019	207-09935	SUBGRADE TREATMENT, TYPE IC	872.00	SYS
0020	211-09265	STRUCTURE BACKFILL, TYPE 2	3326.00	CYS
0021	214-12237	GEOTEXTILE FOR PAVEMENT TYPE 1B	4056.00	SYS
0022	303-01180	COMPACTED AGGREGATE NO. 53	56.00	TON
0023	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1074.00	SYS
0024	401-07329	QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	156.00	TON
0025	401-07399	QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm	111.00	TON
0026	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	448.00	TON
0027	401-10258	JOINT ADHESIVE, SURFACE	366.00	LFT
0028	401-10259	JOINT ADHESIVE, INTERMEDIATE	366.00	LFT
0029	401-11785	LIQUID ASPHALT SEALANT	366.00	LFT
0030	402-10087	HMA FOR TEMPORARY PAVEMENT, D	3558.00	TON
0031	406-05520	ASPHALT FOR TACK COAT	5.00	TON

0032	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.00 TON
0033	603-06040	FENCE, FARM FIELD, 47 IN.	125.00 LFT
0034	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	1166.00 LFT
0035	616-06405	RIPRAP, REVETMENT	140.00 TON
0036	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	230.00 SYS
0037	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.00EACH
0038	621-06559	MULCHED SEEDING R	9495.00 SYS
0039	628-09402	FIELD OFFICE, B	8.00 MOS
0040	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00EACH
0041	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	366.00 LFT
0042	715-05052	PIPE, TYPE 4, CIRCULAR, 12 IN.	10.00 LFT
0043	715-06816	CONCRETE ANCHOR, 120 IN.	2.00EACH
0044	715-09457	PIPE, TYPE 1, CIRCULAR, 120 IN.	408.00 LFT
0045	718-52610	AGGREGATE FOR UNDERDRAINS	33.00 CYS
0046	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00EACH
0047	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	17320.00 LFT
0048	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	7504.00 LFT
0049	801-06625	DETOUR ROUTE MARKER ASSEMBLY	12.00EACH
0050	801-06640	CONSTRUCTION SIGN, A	59.00EACH
0051	801-06645	CONSTRUCTION SIGN, B	17.00EACH
0052	801-06710	FLASHING ARROW SIGN	240.00 DAY
0053	801-06775	MAINTAINING TRAFFIC	1.00 LS
0054	801-07118	BARRICADE, III-A	80.00 LFT
0055	801-07119	BARRICADE, III-B	200.00 LFT
0056	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	710.00 LFT
0057	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00EACH
0058	801-52817	TEMPORARY CROSSOVER, B	2.00EACH
0059	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	62.00 LFT
0060	802-07060	SIGN, SHEET, RELOCATE	6.00EACH
0061	808-01226	SNOWPLOWABLE RAISED PAVEMENT MARKER CASTING INSTALL	6.00EACH
0062	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	3386.00 LFT
0063	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	583.00 LFT
0064	808-06716	LINE, REMOVE	8440.00 LFT
0065	808-12032	GROOVING FOR PAVEMENT MARKINGS	9752.00 LFT
0066	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	5783.00 LFT
0067	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	6.00EACH

Call: 631

Contract: R -43024-A

Section No.: 1 DEMOLITION, REMOVE BUILDINGS

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0008	202-01261	TESTING FOR ASBESTOS	2.00 EACH
0009	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00 LS
0010	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00 LS
0011	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00 LS
0012	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00 LS
0013	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00 LS
0014	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00 LS
0015	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00 LS
0016	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00 LS
0017	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00 LS
0018	202-03135	REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	1794.00 SFT
0019	202-03729	REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	6.00 LFT
0020	202-04890	WELL	4.00 EACH
0021	202-05547	REGULATED MATERIALS, DISPOSE, TYPE C	24.00 DRU
0022	202-05552	REGULATED MATERIALS, REMOVE, TYPE C	24.00 DRU
0023	202-05557	REGULATED MATERIALS, TRANSPORT, TYPE C	24.00 DRU
0024	202-06541	REMOVE	4.00 EACH
0025	202-07603	TESTING FOR WASTES, TYPE C	2.00 EACH
0026	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0027	203-02000	EXCAVATION, COMMON	120.00 CYS
0028	205-12108	STORMWATER MANAGEMENT BUDGET	12920.00 DOL
0029	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0030	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00 EACH
0031	621-06545	FERTILIZER	1.00 TON

0032	621-06553	SEED MIXTURE R	193.00	LBS
0033	621-06565	MULCHING MATERIAL	2.00	TON
0034	801-06640	CONSTRUCTION SIGN, A	3.00	EACH
0035	801-06645	CONSTRUCTION SIGN, B	1.00	EACH
0036	801-06775	MAINTAINING TRAFFIC	1.00	LS
0037	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	370.00	LFT
0038	808-06716	LINE, REMOVE	595.00	LFT
0039	808-12032	GROOVING FOR PAVEMENT MARKINGS	370.00	LFT

Call: 701

Contract: B -37711-A

Section No.: 1 BRIDGE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0012	203-02000	EXCAVATION, COMMON	2610.00	CYS
0013	203-02070	BORROW	7845.00	CYS
0014	203-10106	AGGREGATE COLUMN	1.00	LS
0015	205-12108	STORMWATER MANAGEMENT BUDGET	10000.00	DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	205-12618	SWQCP PREPARATION	1.00	LS
0018	206-51215	EXCAVATION, X	5.00	CYS
0019	206-51225	EXCAVATION, DRY	51.00	CYS
0020	207-08264	SUBGRADE TREATMENT, TYPE II	49.00	SYS
0021	207-09935	SUBGRADE TREATMENT, TYPE IC	3320.00	SYS
0022	211-06467	AGGREGATE FOR END BENT BACKFILL	90.00	CYS
0023	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	711.00	SYS
0024	301-12232	COMPACTED AGGREGATE NO. 5	240.00	CYS
0025	301-12234	COMPACTED AGGREGATE NO. 53	985.00	CYS
0026	302-07455	DENSE GRADED SUBBASE	23.00	CYS
0027	306-08034	MILLING, ASPHALT, 1 1/2 IN.	178.00	SYS
0028	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	262.00	TON
0029	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	581.00	TON
0030	401-10258	JOINT ADHESIVE, SURFACE	1167.00	LFT
0031	401-10259	JOINT ADHESIVE, INTERMEDIATE	1167.00	LFT

0032	401-11785	LIQUID ASPHALT SEALANT	1167.00	LFT
0033	405-05517	ASPHALT FOR PRIME COAT	12.00	TON
0034	406-05520	ASPHALT FOR TACK COAT	2.00	TON
0035	601-01848	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 5	1.00	EACH
0036	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	613.00	LFT
0037	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00	EACH
0038	601-94689	GUARDRAIL, END TREATMENT, OS	3.00	EACH
0039	602-06729	BARRIER, DELINEATOR	16.00	EACH
0040	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	148.00	SYS
0041	610-07487	HMA FOR APPROACHES, TYPE B	14.00	TON
0042	615-06490	RIGHT-OF-WAY MARKER	27.00	EACH
0043	615-06505	MONUMENT, B	11.00	EACH
0044	615-06510	MONUMENT, C	3.00	EACH
0045	616-05688	RIPRAP, CLASS 1	30.00	TON
0046	616-06405	RIPRAP, REVETMENT	1507.00	TON
0047	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	1941.00	SYS
0048	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0049	621-02770	EROSION CONTROL BLANKET	3348.00	SYS
0050	621-06565	MULCHING MATERIAL	2.00	TON
0051	621-06567	WATER	1.00	KGAL
0052	621-06570	TOPSOIL	46.00	CYS
0053	621-06574	SODDING	64.00	SYS
0054	621-12612	SEED MIXTURE FLOODPLAIN	49.00	LBS
0055	622-05638	PLANT, DECIDUOUS SHRUB, 18 IN. OR UNDER	70.00	EACH
0056	622-05648	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. OR UNDER	140.00	EACH
0057	622-52436	SIGN, DO NOT MOW OR SPRAY	8.00	EACH
0058	628-09402	FIELD OFFICE, B	24.00	MOS
0059	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0060	628-11977	COMPUTER SYSTEM	1.00	EACH
0061	701-09558	TEST PILE, INDICATOR, PRODUCTION	94.00	LFT
0062	701-09559	TEST PILE, DYNAMIC, RESTRIKE	2.00	EACH
0063	701-09678	CONICAL PILE TIP, 12 IN.	14.00	EACH
0064	701-12360	PREBORED HOLE, 21 IN	70.00	LFT
0065	701-51195	PILE, STEEL H HP 12 X 53	631.00	LFT
0066	702-51005	CONCRETE, A, SUBSTRUCTURE	140.00	CYS
0067	703-06028	REINFORCING BARS	29450.00	LBS
0068	703-06029	REINFORCING BARS, EPOXY COATED	115627.00	LBS

0069	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	34.00 EACH
0070	704-51002	CONCRETE, C, SUPERSTRUCTURE	303.00 CYS
0071	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00 EACH
0072	706-51020	RAILING, CONCRETE C	56.00 CYS
0073	707-05985	STRUCTURAL MEMBER, CONCRETE, I-BEAM, 54 IN. X 20 IN.	1160.00 LFT
0074	709-51821	SURFACE SEAL	1.00 LS
0075	715-05172	PIPE, TYPE 3, CIRCULAR, 21 IN.	50.00 LFT
0076	715-46015	PIPE END SECTION, DIAMETER 21 IN.	2.00 EACH
0077	728-11672	DRILLED SHAFT EXPLORATORY CORE	236.00 LFT
0078	728-11673	DRILLED SHAFT PERMANENT CASING	150.00 LFT
0079	728-11856	DRILLED SHAFT 60 IN. DIAMETER	150.00 LFT
0080	728-11863	DRILLED SHAFT 54 IN. DIAMETER	56.00 LFT
0081	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00 EACH
0082	801-06640	CONSTRUCTION SIGN, A	10.00 EACH
0083	801-06645	CONSTRUCTION SIGN, B	2.00 EACH
0084	801-06775	MAINTAINING TRAFFIC	1.00 LS
0085	801-07118	BARRICADE, III-A	48.00 LFT
0086	801-07119	BARRICADE, III-B	48.00 LFT
0087	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	2802.00 LFT
0088	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	2802.00 LFT
0089	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	37.00 EACH

Call: 721

Contract: B -39779-A

Section No.: 1 BRIDGE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-02279	CURB AND GUTTER, REMOVE	613.00	LFT
0012	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0013	203-02000	EXCAVATION, COMMON	2425.00	CYS
0014	203-02070	BORROW	370.00	CYS
0015	205-12108	STORMWATER MANAGEMENT BUDGET	19800.00	DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	189.00	CYS
0018	207-09935	SUBGRADE TREATMENT, TYPE IC	1487.00	SYS
0019	211-02050	B BORROW	1030.00	CYS
0020	211-09266	STRUCTURE BACKFILL, TYPE 3	1115.00	CYS
0021	214-07203	GEOGRID, TYPE II	192.00	SYS
0022	301-12231	COMPACTED AGGREGATE NO. 2	2.00	CYS
0023	301-12234	COMPACTED AGGREGATE NO. 53	351.00	CYS
0024	302-06464	SUBBASE FOR PCCP	46.00	CYS
0025	303-01180	COMPACTED AGGREGATE NO. 53	554.00	TON
0026	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	81.00	TON
0027	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	134.00	TON
0028	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	589.00	TON
0029	401-10258	JOINT ADHESIVE, SURFACE	919.00	LFT
0030	401-10259	JOINT ADHESIVE, INTERMEDIATE	919.00	LFT
0031	401-11785	LIQUID ASPHALT SEALANT	919.00	LFT

0032	406-05521	ASPHALT FOR TACK COAT	1947.00	SYS
0033	503-12477	TERMINAL JOINT, TYPE HMA	70.00	LFT
0034	601-02241	GUARDRAIL, REMOVE	888.00	LFT
0035	601-06294	IMPACT ATTENUATOR, RESET, ED-W1, TL-3	1.00	EACH
0036	601-06855	GUARDRAIL, W-BEAM, CABLE TERMINAL ANCHOR	1.00	EACH
0037	601-08182	GUARDRAIL, THRIE BEAM	50.00	LFT
0038	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	313.00	LFT
0039	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	4.00	EACH
0040	601-12291	GUARDRAIL MGS TRANSITION WITH CURB	4.00	EACH
0041	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	163.00	LFT
0042	601-99123	GUARDRAIL, TRANSITION, GP	4.00	EACH
0043	602-06729	BARRIER, DELINEATOR	14.00	EACH
0044	605-06145	CURB AND GUTTER, B, CONCRETE	433.00	LFT
0045	607-06175	GUTTER, CONCRETE, A	180.00	LFT
0046	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	180.00	SYS
0047	616-06405	RIPRAP, REVETMENT	96.00	TON
0048	616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	193.00	SYS
0049	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0050	621-06560	MULCHED SEEDING U	700.00	SYS
0051	621-06574	SODDING	307.00	SYS
0052	627-11647	CABLE BARRIER SYSTEM, TYPE TL-4 RESET	3000.00	LFT
0053	628-09402	FIELD OFFICE, B	12.00	MOS
0054	701-06011	DYNAMIC PILE LOAD TEST	2.00	EACH
0055	701-08253	PILE, SLEEVES	14.00	EACH
0056	701-09557	TEST PILE, DYNAMIC, PRODUCTION	154.00	LFT
0057	701-09559	TEST PILE, DYNAMIC, RESTRIKE	2.00	EACH
0058	701-09739	PILE SHOE, HP 12 X 53	12.00	EACH
0059	701-51195	PILE, STEEL H HP 12 X 53	670.00	LFT
0060	702-51005	CONCRETE, A, SUBSTRUCTURE	77.50	CYS
0061	702-51015	CONCRETE, B, FOOTINGS	65.00	CYS
0062	702-92857	CONCRETE, C, SUBSTRUCTURE	36.40	CYS
0063	703-06028	REINFORCING BARS	16719.00	LBS
0064	703-06029	REINFORCING BARS, EPOXY COATED	100792.00	LBS
0065	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	36.00	EACH
0066	704-51002	CONCRETE, C, SUPERSTRUCTURE	229.30	CYS
0067	706-11600	RAILING, CONCRETE FC	35.80	CYS
0068	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	1.00	EACH

0069	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	3.00 EACH
0070	707-09865	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 36 IN. X 49 IN.	748.00 LFT
0071	709-51821	SURFACE SEAL	1.00 LS
0072	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	208.00 LFT
0073	718-12307	GEOTEXTILE FOR UNDERDRAIN, TYPE 2A	208.00 SYS
0074	718-52610	AGGREGATE FOR UNDERDRAINS	32.00 CYS
0075	720-44000	CASTING, ADJUST TO GRADE	2.00 EACH
0076	720-45025	INLET, D6	1.00 EACH
0077	724-12103	PRE-COMPRESSED FOAM JOINT	70.00 LFT
0078	731-93945	FACE PANELS, CONCRETE	3034.00 SFT
0079	731-93946	WALL ERECTION	3034.00 SFT
0080	731-93947	LEVELING PAD, CONCRETE	208.00 LFT
0081	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.00 EACH
0082	801-04308	ROAD CLOSURE SIGN ASSEMBLY	12.00 EACH
0083	801-06625	DETOUR ROUTE MARKER ASSEMBLY	85.00 EACH
0084	801-06640	CONSTRUCTION SIGN, A	98.00 EACH
0085	801-06645	CONSTRUCTION SIGN, B	12.00 EACH
0086	801-06710	FLASHING ARROW SIGN	20.00 DAY
0087	801-06775	MAINTAINING TRAFFIC	1.00 LS
0088	801-07118	BARRICADE, III-A	1244.00 LFT
0089	801-07119	BARRICADE, III-B	48.00 LFT
0090	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	1390.00 LFT
0091	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	7.00 EACH
0092	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	1090.00 LFT
0093	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	1250.00 LFT
0094	808-12032	GROOVING FOR PAVEMENT MARKINGS	1384.00 LFT
0095	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	18.00 EACH
0096	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	18.00 EACH

Call: 731

Contract: B -39958-A

Section No.: 1

SMALL STRUCTURE REPLACEMENT

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	105-09645	CONSTRUCTION ENGINEERING AND INSPECTION UTILITY RELOCATION	1.00	LS
	0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0004	109-08360	CONTRACT LIENS	1.00	DOL
	0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0013	202-02240	PAVEMENT REMOVAL	174.00	SYS
	0014	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
	0015	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
	0016	203-02000	EXCAVATION, COMMON	675.00	CYS
	0017	203-02070	BORROW	710.00	CYS
	0018	205-11626	PUMP AROUND	2.00	EACH
	0019	205-12108	STORMWATER MANAGEMENT BUDGET	40741.00	DOL
	0020	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0021	205-12618	SWQCP PREPARATION	1.00	LS
	0022	207-12498	SUBGRADE TREATMENT, TYPE ID	1873.00	SYS
	0023	211-09265	STRUCTURE BACKFILL, TYPE 2	371.00	CYS
	0024	211-09268	STRUCTURE BACKFILL, TYPE 5	352.00	CYS
	0025	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	435.00	SYS
	0026	301-12232	COMPACTED AGGREGATE NO. 5	49.00	CYS
	0027	303-01180	COMPACTED AGGREGATE NO. 53	171.00	TON
	0028	306-08034	MILLING, ASPHALT, 1 1/2 IN.	134.00	SYS
	0029	306-08043	MILLING, TRANSITION	670.00	SYS
	0030	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	198.00	TON
	0031	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	244.00	TON

0032	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	587.00 TON
0033	401-10258	JOINT ADHESIVE, SURFACE	2150.00 LFT
0034	401-10259	JOINT ADHESIVE, INTERMEDIATE	1996.00 LFT
0035	401-11785	LIQUID ASPHALT SEALANT	2330.00 LFT
0036	406-05521	ASPHALT FOR TACK COAT	5610.00 SYS
0037	601-02241	GUARDRAIL, REMOVE	850.00 LFT
0038	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	262.50 LFT
0039	601-12288	GUARDRAIL, MGS, LONG SPAN, TYPE 2	2.00 EACH
0040	601-94689	GUARDRAIL, END TREATMENT, OS	4.00 EACH
0041	615-06490	RIGHT-OF-WAY MARKER	14.00 EACH
0042	615-06505	MONUMENT, B	6.00 EACH
0043	616-05688	RIPRAP, CLASS 1	500.00 TON
0044	616-06405	RIPRAP, REVETMENT	167.00 TON
0045	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	502.00 SYS
0046	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 EACH
0047	621-06559	MULCHED SEEDING R	3047.00 SYS
0048	628-09402	FIELD OFFICE, B	12.00 MOS
0049	628-11729	CELLULAR TELEPHONE, TYPE A	1.00 EACH
0050	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00 DOL
0051	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00 DOL
0052	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	12.00 MOS
0053	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0054	628-11977	COMPUTER SYSTEM	1.00 EACH
0055	706-11455	BRIDGE RAILING PEDESTRIAN FENCE	52.00 LFT
0056	715-05123	PIPE, TYPE 1, CIRCULAR, 24 IN.	20.00 LFT
0057	723-11201	STRUCTURE, REINFORCED CONCRETE, THREE-SIDED SECTIONS, 288 IN.X 120 IN.	50.00 LFT
0058	723-11203	STRUCTURE REINFORCED CONCRETE THREE-SIDED SECTIONS	52.00 LFT
0059	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00 EACH
0060	801-06625	DETOUR ROUTE MARKER ASSEMBLY	65.00 EACH
0061	801-06640	CONSTRUCTION SIGN, A	8.00 EACH
0062	801-06775	MAINTAINING TRAFFIC	1.00 LS
0063	801-07118	BARRICADE, III-A	96.00 LFT
0064	801-07119	BARRICADE, III-B	96.00 LFT
0065	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	180.00 LFT
0066	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1440.00 LFT
0067	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	250.00 LFT
0068	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	12.00 EACH

0069 808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER

12.00 EACH

Call: 741

Contract: B -39960-A

Section No.: 1

SMALL STRUCTURE PIPE LINING

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	1428.00	SYS
0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0015	202-91385	INLET, REMOVE	1.00	EACH
0016	202-96133	PIPE, REMOVE	12.00	LFT
0017	202-96531	FENCE RIGHT-OF-WAY, REMOVE	250.00	LFT
0018	202-99080	CONCRETE, REMOVE	5.00	CYS
0019	202-99187	FENCE, FARM FIELD, REMOVE	133.00	LFT
0020	203-02000	EXCAVATION, COMMON	1676.00	CYS
0021	203-02070	BORROW	180.00	CYS
0022	205-06937	TEMPORARY SILT FENCE	800.00	LFT
0023	205-11626	PUMP AROUND	4.00	EACH
0024	205-12108	STORMWATER MANAGEMENT BUDGET	52930.00	DOL
0025	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0026	205-12618	SWQCP PREPARATION	1.00	LS
0027	206-93520	TEMPORARY SHEET PILING	1440.00	SFT
0028	207-09935	SUBGRADE TREATMENT, TYPE IC	528.00	SYS
0029	207-12498	SUBGRADE TREATMENT, TYPE ID	2409.00	SYS
0030	211-09264	STRUCTURE BACKFILL, TYPE 1	79.00	CYS
0031	211-09265	STRUCTURE BACKFILL, TYPE 2	1815.00	CYS

0032	211-09266	STRUCTURE BACKFILL, TYPE 3	520.00	CYS
0033	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	367.00	SYS
0034	301-12232	COMPACTED AGGREGATE NO. 5	73.00	CYS
0035	301-12234	COMPACTED AGGREGATE NO. 53	168.00	CYS
0036	303-01180	COMPACTED AGGREGATE NO. 53	350.00	TON
0037	306-08034	MILLING, ASPHALT, 1 1/2 IN.	8490.00	SYS
0038	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	925.00	TON
0039	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	379.00	TON
0040	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	1282.00	TON
0041	401-10258	JOINT ADHESIVE, SURFACE	9049.00	LFT
0042	401-10259	JOINT ADHESIVE, INTERMEDIATE	2355.00	LFT
0043	401-11785	LIQUID ASPHALT SEALANT	9049.00	LFT
0044	406-05520	ASPHALT FOR TACK COAT	6.00	TON
0045	603-06040	FENCE, FARM FIELD, 47 IN.	250.00	LFT
0046	603-06060	FENCE, FARM FIELD, RESET	647.00	LFT
0047	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	8968.00	LFT
0048	616-05689	RIPRAP, CLASS 2	741.00	TON
0049	616-06405	RIPRAP, REVETMENT	67.00	TON
0050	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	338.00	SYS
0051	616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	233.00	SYS
0052	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	757.00	SYS
0053	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	9.00	EACH
0054	621-06559	MULCHED SEEDING R	5319.00	SYS
0055	621-06567	WATER	1.00	KGAL
0056	621-06574	SODDING	80.00	SYS
0057	628-09403	FIELD OFFICE, C	12.00	MOS
0058	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0059	628-11730	CELLULAR TELEPHONE, TYPE B	1.00	EACH
0060	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0061	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0062	628-11780	CELLULAR TELEPHONE SERVICE, 500 MIN.	24.00	MOS
0063	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0064	628-11977	COMPUTER SYSTEM	1.00	EACH
0065	702-03607	CORED HOLE IN CONCRETE	2.00	EACH
0066	702-51005	CONCRETE, A, SUBSTRUCTURE	124.40	CYS
0067	702-51015	CONCRETE, B, FOOTINGS	43.30	CYS
0068	702-51863	FIELD DRILLED HOLE IN CONCRETE	14.00	EACH

0069	703-06029	REINFORCING BARS, EPOXY COATED	6776.00	LBS
0070	703-08247	EMBEDDED GALVANIC ANODE	1770.00	EACH
0071	708-51814	WELDED STEEL WIRE REINFORCEMENT	5620.00	SFT
0072	709-51821	SURFACE SEAL	1.00	LS
0073	711-96800	STUD SHEAR CONNECTORS	6500.00	EACH
0074	714-11073	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 9 FT. X 6 FT.	166.00	LFT
0075	714-96273	HEADWALL RECONSTRUCT	1.00	LS
0076	715-05032	PIPE, TYPE 2, CIRCULAR, 15 IN.	7.00	LFT
0077	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	1735.00	LFT
0078	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	90.00	LFT
0079	715-05129	PIPE, TYPE 1, CIRCULAR, 54 IN.	200.00	LFT
0080	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	37.00	LFT
0081	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	270.00	LFT
0082	715-06492	CONCRETE ANCHOR, 54 IN.	2.00	EACH
0083	715-09064	VIDEO INSPECTION FOR PIPE	307.00	LFT
0084	718-08308	UNDERDRAIN PATCHING	117.00	LFT
0085	718-12306	GEOTEXTILE FOR UNDERDRAIN, TYPE 1B	1174.00	SYS
0086	718-52610	AGGREGATE FOR UNDERDRAINS	138.00	CYS
0087	720-45065	INLET, N12	2.00	EACH
0088	720-45410	MANHOLE, C4	2.00	EACH
0089	725-10245	PERPETUATION, EXISTING PIPE	1.00	EACH
0090	725-11986	LINER PIPE, THERMOPLASTIC, CIRCULAR, 76.9-78.6 SFT	319.00	LFT
0091	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	28.00	EACH
0092	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	39889.00	LFT
0093	801-06640	CONSTRUCTION SIGN, A	98.00	EACH
0094	801-06645	CONSTRUCTION SIGN, B	16.00	EACH
0095	801-06710	FLASHING ARROW SIGN	334.00	DAY
0096	801-06775	MAINTAINING TRAFFIC	1.00	LS
0097	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	1.00	EACH
0098	801-07119	BARRICADE, III-B	48.00	LFT
0099	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	2653.00	LFT
0100	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	1360.00	LFT
0101	801-12042	TRUCK MOUNTED ATTENUATOR	40.00	DAY
0102	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	2026.00	LFT
0103	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	3581.00	LFT
0104	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	1050.00	LFT
0105	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	4198.00	LFT

0106	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	4198.00	LFT
0107	808-06716	LINE, REMOVE	7535.00	LFT
0108	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0109	808-12032	GROOVING FOR PAVEMENT MARKINGS	7638.00	LFT
0110	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2031.00	LFT
0111	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	53.00	EACH
0112	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	53.00	EACH

Call: 751

Contract: B -40874-A

Section No.: 1 BRIDGE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0012	203-02000	EXCAVATION, COMMON	770.00	CYS
0013	203-02020	EXCAVATION, UNCLASSIFIED	128.00	CYS
0014	203-51223	EXCAVATION, WATERWAY	171.00	CYS
0015	205-12108	STORMWATER MANAGEMENT BUDGET	11892.00	DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	205-12618	SWQCP PREPARATION	1.00	LS
0018	207-08266	SUBGRADE TREATMENT, TYPE III	1880.00	SYS
0019	207-09935	SUBGRADE TREATMENT, TYPE IC	167.00	SYS
0020	211-06467	AGGREGATE FOR END BENT BACKFILL	34.00	CYS
0021	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	167.00	SYS
0022	301-12234	COMPACTED AGGREGATE NO. 53	273.00	CYS
0023	302-06464	SUBBASE FOR PCCP	42.00	CYS
0024	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	135.00	TON
0025	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	225.00	TON
0026	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	360.00	TON
0027	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	270.00	TON
0028	401-10258	JOINT ADHESIVE, SURFACE	551.00	LFT
0029	401-10259	JOINT ADHESIVE, INTERMEDIATE	551.00	LFT
0030	401-11785	LIQUID ASPHALT SEALANT	551.00	LFT
0031	401-11787	QC/QA-HMA, 3, 76, INTERMEDIATE, OG 19.0 mm	225.00	TON

0032	406-05521	ASPHALT FOR TACK COAT	4900.00	SYS
0033	601-02241	GUARDRAIL, REMOVE	60.00	LFT
0034	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00	EACH
0035	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0036	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	166.00	SYS
0037	616-06405	RIPRAP, REVETMENT	475.00	TON
0038	616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	630.00	SYS
0039	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0040	621-06559	MULCHED SEEDING R	3000.00	SYS
0041	621-06574	SODDING	430.00	SYS
0042	628-09402	FIELD OFFICE, B	8.00	MOS
0043	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0044	628-11977	COMPUTER SYSTEM	2.00	EACH
0045	701-09558	TEST PILE, INDICATOR, PRODUCTION	70.00	LFT
0046	701-09560	TEST PILE, INDICATOR, RESTRIKE	1.00	EACH
0047	701-09739	PILE SHOE, HP 12 X 53	10.00	EACH
0048	701-51195	PILE, STEEL H HP 12 X 53	540.00	LFT
0049	703-06029	REINFORCING BARS, EPOXY COATED	33136.00	LBS
0050	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	30.00	EACH
0051	704-51002	CONCRETE, C, SUPERSTRUCTURE	95.00	CYS
0052	706-11600	RAILING, CONCRETE FC	12.00	CYS
0053	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0054	707-05983	STRUCTURAL MEMBER, CONCRETE, I-BEAM, 36 IN. X 12 IN.	307.50	LFT
0055	709-51821	SURFACE SEAL	1.00	LS
0056	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	551.00	LFT
0057	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	15.00	LFT
0058	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	52.00	LFT
0059	715-05407	PIPE, END BENT DRAIN, 6 IN.	120.00	LFT
0060	718-06531	OUTLET PROTECTOR, 3	4.00	EACH
0061	718-12308	GEOTEXTILE FOR UNDERDRAIN, TYPE 2B	622.00	SYS
0062	718-52610	AGGREGATE FOR UNDERDRAINS	48.00	CYS
0063	801-04308	ROAD CLOSURE SIGN ASSEMBLY	5.00	EACH
0064	801-06625	DETOUR ROUTE MARKER ASSEMBLY	20.00	EACH
0065	801-06640	CONSTRUCTION SIGN, A	12.00	EACH
0066	801-06645	CONSTRUCTION SIGN, B	1.00	EACH
0067	801-06775	MAINTAINING TRAFFIC	1.00	LS
0068	801-07118	BARRICADE, III-A	48.00	LFT

0069	801-07119	BARRICADE, III-B	36.00	LFT
0070	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1330.00	LFT
0071	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1330.00	LFT

Call: 761

Contract: B -41048-A

Section No.: 1 BRIDGE THIN DECK OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	306-08034	MILLING, ASPHALT, 1 1/2 IN.	4395.00	SYS
0011	306-08041	MILLING, PCCP	535.00	SYS
0012	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	408.00	TON
0013	401-10258	JOINT ADHESIVE, SURFACE	974.00	LFT
0014	401-11785	LIQUID ASPHALT SEALANT	974.00	LFT
0015	507-08271	JOINTS IN PCCP, FILLED	42.00	LFT
0016	507-08272	JOINTS IN PCCP, SAW AND SEAL	2400.00	LFT
0017	601-02241	GUARDRAIL, REMOVE	125.00	LFT
0018	601-06035	GUARDRAIL, RESET	125.00	LFT
0019	602-06729	BARRIER, DELINEATOR	74.00	EACH
0020	628-09402	FIELD OFFICE, B	10.00	MOS
0021	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0022	702-51863	FIELD DRILLED HOLE IN CONCRETE	126.00	EACH
0023	703-06029	REINFORCING BARS, EPOXY COATED	107.00	LBS
0024	704-51002	CONCRETE, C, SUPERSTRUCTURE	0.90	CYS
0025	709-51821	SURFACE SEAL	1.00	LS
0026	709-51821	SURFACE SEAL	1.00	LS
0027	709-51821	SURFACE SEAL	1.00	LS
0028	709-51821	SURFACE SEAL	1.00	LS
0029	709-51821	SURFACE SEAL	1.00	LS
0030	709-51821	SURFACE SEAL	1.00	LS
0031	709-51821	SURFACE SEAL	1.00	LS

0032	709-51821	SURFACE SEAL	1.00	LS
0033	710-09158	PATCHING CONCRETE STRUCTURES	425.00	SFT
0034	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	1360.00	SFT
0035	724-12103	PRE-COMPRESSED FOAM JOINT	160.00	LFT
0036	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	4965.00	SYS
0037	801-04308	ROAD CLOSURE SIGN ASSEMBLY	57.00	EACH
0038	801-06625	DETOUR ROUTE MARKER ASSEMBLY	80.00	EACH
0039	801-06640	CONSTRUCTION SIGN, A	152.00	EACH
0040	801-06775	MAINTAINING TRAFFIC	1.00	LS
0041	801-07118	BARRICADE, III-A	768.00	LFT
0042	801-07119	BARRICADE, III-B	384.00	LFT
0043	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	150.00	LFT
0044	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	4305.00	LFT
0045	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	3205.00	LFT
0046	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	33.00	EACH
0047	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	33.00	EACH

Call: 771

Contract: B -41061-A

Section No.: 1 BRIDGE DECK OVERLAY

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0010	202-02240	PAVEMENT REMOVAL	3352.00	SYS
	0011	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
	0012	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
	0013	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
	0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
	0015	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
	0016	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
	0017	203-02000	EXCAVATION, COMMON	1082.00	CYS
	0018	207-09935	SUBGRADE TREATMENT, TYPE IC	3492.00	SYS
	0019	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	3492.00	SYS
	0020	302-06464	SUBBASE FOR PCCP	382.80	CYS
	0021	303-01180	COMPACTED AGGREGATE NO. 53	858.00	TON
	0022	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	205.00	TON
	0023	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	256.00	TON
	0024	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	1065.00	TON
	0025	401-10258	JOINT ADHESIVE, SURFACE	3240.00	LFT
	0026	401-10259	JOINT ADHESIVE, INTERMEDIATE	3240.00	LFT
	0027	401-11785	LIQUID ASPHALT SEALANT	6480.00	LFT
	0028	406-05521	ASPHALT FOR TACK COAT	5526.00	SYS
	0029	503-12477	TERMINAL JOINT, TYPE HMA	545.00	LFT
	0030	601-06035	GUARDRAIL, RESET	600.00	LFT
	0031	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	1527.90	SYS

0032	628-09403	FIELD OFFICE, C	12.00	MOS
0033	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0034	703-06029	REINFORCING BARS, EPOXY COATED	101600.00	LBS
0035	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	597.00	EACH
0036	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	24.00	EACH
0037	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0038	709-51821	SURFACE SEAL	1.00	LS
0039	709-51821	SURFACE SEAL	1.00	LS
0040	709-51821	SURFACE SEAL	1.00	LS
0041	709-51821	SURFACE SEAL	1.00	LS
0042	709-51821	SURFACE SEAL	1.00	LS
0043	709-51821	SURFACE SEAL	1.00	LS
0044	710-09158	PATCHING CONCRETE STRUCTURES	900.00	SFT
0045	715-06566	PIPE EXTENSION, CIRCULAR, 6 IN.	128.00	LFT
0046	722-01066	HYDRODEMOLITION	8630.00	SYS
0047	722-12380	BRIDGE DECK OVERLAY, BUDGET	38045.00	DOL
0048	722-12382	TRANSVERSE GROOVING	10167.00	SYS
0049	722-12463	BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY	8630.00	SYS
0050	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	3885.00	SFT
0051	724-03276	STRUCTURAL EXPANSION JOINT SEALING SYS	260.00	LFT
0052	724-09626	STRUCTURAL EXPANSION JOINT SEAL, SS, REPLACE	302.00	LFT
0053	724-12103	PRE-COMPRESSED FOAM JOINT	545.00	LFT
0054	727-90308	EPOXY INJECTION, CRACK PREPARATION	400.00	LFT
0055	727-90309	EPOXY INJECTION, EPOXY MATERIAL	228.00	GAL
0056	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0057	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0058	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0059	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0060	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0061	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0062	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.00	EACH
0063	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	8.00	EACH
0064	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	42050.00	LFT
0065	801-06640	CONSTRUCTION SIGN, A	96.00	EACH
0066	801-06645	CONSTRUCTION SIGN, B	32.00	EACH
0067	801-06710	FLASHING ARROW SIGN	360.00	DAY
0068	801-06775	MAINTAINING TRAFFIC	1.00	LS

0069	801-07118	BARRICADE, III-A	36.00	LFT
0070	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	2715.00	LFT
0071	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	1140.00	LFT
0072	808-06716	LINE, REMOVE	36250.00	LFT
0073	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	18000.00	LFT
0074	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	18000.00	LFT
0075	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	1000.00	LFT
0076	808-10043	LINE, MULTI-COMPONENT, SOLID, WHITE, 24 IN.	1000.00	LFT
0077	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	9000.00	LFT
0078	808-12032	GROOVING FOR PAVEMENT MARKINGS	39500.00	LFT
0079	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	150.00	EACH
0080	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	150.00	EACH

Call: 771

Contract: B -41061-A

Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED CONCRETE

Line			Quantity	Unit
Item No	Item Code	Description		
0081	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	8630.00	SYS

Call: 771

Contract: B -41061-A

Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED CONCRETE

Line			Quantity	Unit
Item No	Item Code	Description		
0082	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	8630.00	SYS

Call: 781

Contract: B -41135-A

Section No.: 1 BRIDGE DECK OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	127.00	SYS
0013	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0014	203-02000	EXCAVATION, COMMON	331.00	CYS
0015	205-12108	STORMWATER MANAGEMENT BUDGET	28368.00	DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	205-12618	SWQCP PREPARATION	1.00	LS
0018	206-51220	EXCAVATION, WET	4.00	CYS
0019	207-12498	SUBGRADE TREATMENT, TYPE ID	763.00	SYS
0020	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	258.00	SYS
0021	302-06464	SUBBASE FOR PCCP	68.00	CYS
0022	303-01180	COMPACTED AGGREGATE NO. 53	13.00	TON
0023	306-08043	MILLING, TRANSITION	4320.00	SYS
0024	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	97.00	TON
0025	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	325.00	TON
0026	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	105.00	TON
0027	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	252.00	TON
0028	401-10258	JOINT ADHESIVE, SURFACE	3022.00	LFT
0029	401-10259	JOINT ADHESIVE, INTERMEDIATE	622.00	LFT
0030	401-11785	LIQUID ASPHALT SEALANT	3022.00	LFT
0031	406-05521	ASPHALT FOR TACK COAT	6628.00	SYS

0032	507-08272	JOINTS IN PCCP, SAW AND SEAL	232.00	LFT
0033	601-06035	GUARDRAIL, RESET	192.00	LFT
0034	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	258.00	SYS
0035	616-05688	RIPRAP, CLASS 1	328.00	TON
0036	616-05689	RIPRAP, CLASS 2	345.00	TON
0037	616-06405	RIPRAP, REVETMENT	150.00	TON
0038	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	705.00	SYS
0039	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0040	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0041	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0042	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.00	EACH
0043	621-02770	EROSION CONTROL BLANKET	1238.00	SYS
0044	621-06559	MULCHED SEEDING R	3298.00	SYS
0045	621-06560	MULCHED SEEDING U	1554.00	SYS
0046	621-06574	SODDING	53.00	SYS
0047	628-09402	FIELD OFFICE, B	12.00	MOS
0048	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0049	702-51005	CONCRETE, A, SUBSTRUCTURE	0.70	CYS
0050	702-92857	CONCRETE, C, SUBSTRUCTURE	5.00	CYS
0051	703-06028	REINFORCING BARS	105.00	LBS
0052	703-06029	REINFORCING BARS, EPOXY COATED	14670.00	LBS
0053	704-51002	CONCRETE, C, SUPERSTRUCTURE	1.50	CYS
0054	708-51814	WELDED STEEL WIRE REINFORCEMENT	1259.00	SFT
0055	709-51821	SURFACE SEAL	1.00	LS
0056	709-51821	SURFACE SEAL	1.00	LS
0057	709-51821	SURFACE SEAL	1.00	LS
0058	710-09158	PATCHING CONCRETE STRUCTURES	1259.00	SFT
0059	711-51035	STRUCTURAL STEEL	681.00	LBS
0060	722-01066	HYDRODEMOLITION	3113.00	SYS
0061	722-12380	BRIDGE DECK OVERLAY, BUDGET	56336.00	DOL
0062	722-12382	TRANSVERSE GROOVING	3372.00	SYS
0063	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	3113.00	SYS
0064	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	850.00	SFT
0065	722-51874	OVERLAY DAM	324.00	SFT
0066	724-12103	PRE-COMPRESSED FOAM JOINT	98.00	LFT
0067	801-04308	ROAD CLOSURE SIGN ASSEMBLY	11.00	EACH
0068	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	9236.00	LFT

0069	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	5343.00	LFT
0070	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	1.00	EACH
0071	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	30.00	LFT
0072	801-06625	DETOUR ROUTE MARKER ASSEMBLY	36.00	EACH
0073	801-06640	CONSTRUCTION SIGN, A	52.00	EACH
0074	801-06645	CONSTRUCTION SIGN, B	4.00	EACH
0075	801-06710	FLASHING ARROW SIGN	120.00	DAY
0076	801-06775	MAINTAINING TRAFFIC	1.00	LS
0077	801-07118	BARRICADE, III-A	96.00	LFT
0078	801-07119	BARRICADE, III-B	192.00	LFT
0079	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	324.00	LFT
0080	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	336.00	LFT
0081	801-12393	TEMPORARY PAVEMENT MARKING, REMOVABLE, 37 IN	42.00	LFT
0082	802-04089	SIGN, SHEET, REMOVE	1.00	EACH
0083	802-04893	REFERENCE POST	4.00	EACH
0084	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	52.00	LFT
0085	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	20.00	SFT
0086	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	210.00	LFT
0087	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1684.00	LFT
0088	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	386.00	LFT
0089	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	150.00	LFT
0090	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	892.00	LFT
0091	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	1784.00	LFT
0092	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	32.00	EACH
0093	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	32.00	EACH

Call: 781

Contract: B -41135-A

Section No.: 2 BRIDGE DECK OVERLAY LATEX MODIFIED CONCRETE

Line

Item No	Item Code	Description	Quantity	Unit
0094	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	3113.00	SYS

Call: 781

Contract: B -41135-A

Section No.: 3 BRIDGE DECK OVERLAY SILICA FUME MODIFIED CONCRETE

Line

Item No	Item Code	Description
0095	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED

Quantity	Unit
3113.00	SYS

Call: 791

Contract: B -41165-A

Section No.: 1 BRIDGE PAINTING

Line

Item No	Item Code	Description
0001	105-06845	CONSTRUCTION ENGINEERING
0002	109-08359	LIQUIDATED DAMAGES
0003	109-08360	CONTRACT LIENS
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT
0007	110-01001	MOBILIZATION AND DEMOBILIZATION
0008	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.
0009	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.
0010	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.
0011	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.
0012	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION
0013	801-06640	CONSTRUCTION SIGN, A
0014	801-06710	FLASHING ARROW SIGN
0015	801-06775	MAINTAINING TRAFFIC
0016	801-12042	TRUCK MOUNTED ATTENUATOR

Quantity	Unit
1.00	LS
1.00	DOL
1.00	DOL
1.00	DOL
1.00	DOL
1.00	DOL
1.00	LS
1.00	LS
1.00	LS
1.00	LS
1.00	LS
8.00	EACH
8.00	EACH
60.00	DAY
1.00	LS
30.00	DAY

Call: 801

Contract: B -41192-A

Section No.: 1

BRIDGE THIN DECK OVERLAY

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0007	709-51821	SURFACE SEAL	1.00 LS
0008	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	640.00 SFT
0009	727-90308	EPOXY INJECTION, CRACK PREPARATION	100.00 LFT
0010	727-90309	EPOXY INJECTION, EPOXY MATERIAL	6.00 GAL
0011	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00 LS
0012	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	2440.00 SYS
0013	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	16696.00 LFT
0014	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	4439.00 LFT
0015	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	1.00 EACH
0016	801-06539	TEMPORARY TRAFFIC SIGNAL INSTALLATION, MAINTAIN	1.00 LS
0017	801-06640	CONSTRUCTION SIGN, A	27.00 EACH
0018	801-06645	CONSTRUCTION SIGN, B	6.00 EACH
0019	801-06710	FLASHING ARROW SIGN	32.00 DAY
0020	801-06775	MAINTAINING TRAFFIC	1.00 LS
0021	801-07118	BARRICADE, III-A	104.00 LFT
0022	801-07119	BARRICADE, III-B	100.00 LFT
0023	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	820.00 LFT
0024	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	5.00 SYS
0025	808-06716	LINE, REMOVE	1580.00 LFT
0026	808-75051	LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	995.00 LFT
0027	808-75054	LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN.	520.00 LFT
0028	808-75059	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 4 IN.	65.00 LFT
0029	808-75071	PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC, LANE INDICATION ARROW	2.00 EACH
0030	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	30.00 EACH
0031	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	30.00 EACH

Call: 811

Contract: B -41194-A

Section No.: 1 BRIDGE DECK OVERLAY

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	12.00 EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0004	109-08360	CONTRACT LIENS	1.00 DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0013	202-02240	PAVEMENT REMOVAL	2126.00 SYS
0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0015	203-02000	EXCAVATION, COMMON	1655.00 CYS
0016	203-08607	LINEAR GRADING	1069.00 LFT
0017	205-12108	STORMWATER MANAGEMENT BUDGET	17600.00 DOL
0018	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0019	205-12618	SWQCP PREPARATION	1.00 LS
0020	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	35.00 CYS
0021	206-51235	COFFERDAM	1.00 LS
0022	207-12498	SUBGRADE TREATMENT, TYPE ID	3988.00 SYS
0023	211-06467	AGGREGATE FOR END BENT BACKFILL	35.00 CYS
0024	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	3988.00 SYS
0025	301-12231	COMPACTED AGGREGATE NO. 2	161.00 CYS
0026	301-12234	COMPACTED AGGREGATE NO. 53	1149.00 CYS
0027	302-06464	SUBBASE FOR PCCP	66.00 CYS
0028	306-08034	MILLING, ASPHALT, 1 1/2 IN.	198.00 SYS
0029	306-08038	MILLING, ASPHALT, 4 IN.	491.00 SYS
0030	306-08432	MILLING, APPROACH	105.00 SYS
0031	401-06264	PROFILOGRAPH, HMA	1.00 LS

0032	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	346.00 TON
0033	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	554.00 TON
0034	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	1217.00 TON
0035	401-10258	JOINT ADHESIVE, SURFACE	2836.00 LFT
0036	401-10259	JOINT ADHESIVE, INTERMEDIATE	2716.00 LFT
0037	401-11785	LIQUID ASPHALT SEALANT	2836.00 LFT
0038	406-05520	ASPHALT FOR TACK COAT	2.00 TON
0039	503-12477	TERMINAL JOINT, TYPE HMA	101.00 LFT
0040	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	1.00 EACH
0041	601-01626	GUARDRAIL, CONNECTOR SYSTEM, W-BEAM CURVED, 2	1.00 EACH
0042	601-01701	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 2	1.00 EACH
0043	601-02103	GUARDRAIL, W-BEAM, SHOP CURVED, 6 FT 3 IN. SPACING	25.00 LFT
0044	601-02241	GUARDRAIL, REMOVE	1072.00 LFT
0045	601-06855	GUARDRAIL, W-BEAM, CABLE TERMINAL ANCHOR	2.00 EACH
0046	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	557.00 LFT
0047	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	2.00 EACH
0048	601-12291	GUARDRAIL MGS TRANSITION WITH CURB	1.00 EACH
0049	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	2.00 EACH
0050	601-94689	GUARDRAIL, END TREATMENT, OS	3.00 EACH
0051	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	13.00 LFT
0052	602-06729	BARRIER, DELINEATOR	14.00 EACH
0053	605-06095	CURB, INTEGRAL B CONCRETE	40.00 LFT
0054	605-08636	CURB AND GUTTER, TURNOUT COMBINED	5.00 LFT
0055	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	3289.00 LFT
0056	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	298.00 SYS
0057	610-07487	HMA FOR APPROACHES, TYPE B	9.00 TON
0058	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00 EACH
0059	616-05688	RIPRAP, CLASS 1	530.00 TON
0060	616-06405	RIPRAP, REVETMENT	170.00 TON
0061	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	304.00 SYS
0062	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	608.00 SYS
0063	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 EACH
0064	621-06559	MULCHED SEEDING R	2405.00 SYS
0065	621-06574	SODDING	60.00 SYS
0066	628-09403	FIELD OFFICE, C	12.00 MOS
0067	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0068	702-51863	FIELD DRILLED HOLE IN CONCRETE	1138.00 EACH

0069	703-06029	REINFORCING BARS, EPOXY COATED	40902.00	LBS
0070	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	48.00	EACH
0071	704-51002	CONCRETE, C, SUPERSTRUCTURE	71.30	CYS
0072	706-06351	CONCRETE BRIDGE RAILING TRANSITION, TPF-1	4.00	EACH
0073	706-11404	RAILING, STEEL PF-1	374.00	LFT
0074	706-11602	RAILING, CONCRETE PF-1	23.60	CYS
0075	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0076	709-51821	SURFACE SEAL	1.00	LS
0077	710-09158	PATCHING CONCRETE STRUCTURES	270.00	SFT
0078	715-01354	CLEAN EXISTING PIPE	142.00	LFT
0079	715-04809	PIPE, PVC, 3"	158.00	LFT
0080	722-01066	HYDRODEMOLITION	842.00	SYS
0081	722-12380	BRIDGE DECK OVERLAY, BUDGET	13365.00	DOL
0082	722-12382	TRANSVERSE GROOVING	1177.00	SYS
0083	722-12463	BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY	842.00	SYS
0084	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	758.00	SFT
0085	722-51874	OVERLAY DAM	116.00	SFT
0086	724-12103	PRE-COMPRESSED FOAM JOINT	101.00	LFT
0087	801-03291	CONSTRUCTION SIGN, D	1.00	EACH
0088	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0089	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3270.00	LFT
0090	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	72.00	LFT
0091	801-06625	DETOUR ROUTE MARKER ASSEMBLY	44.00	EACH
0092	801-06640	CONSTRUCTION SIGN, A	44.00	EACH
0093	801-06645	CONSTRUCTION SIGN, B	11.00	EACH
0094	801-06775	MAINTAINING TRAFFIC	1.00	LS
0095	801-07118	BARRICADE, III-A	120.00	LFT
0096	801-07119	BARRICADE, III-B	96.00	LFT
0097	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	720.00	LFT
0098	801-12081	PORTABLE SIGNAL	1.00	LS
0099	801-12482	DRIVEWAY ASSISTANCE DEVICE	1.00	EACH
0100	801-97643	TEMPORARY BUZZ STRIPS	1728.00	LFT
0101	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	24.00	LFT
0102	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	6.00	SFT
0103	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	2192.00	LFT
0104	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	2192.00	LFT
0105	808-06716	LINE, REMOVE	2410.00	LFT

0106	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	12.00	LFT
0107	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	6.00	EACH
0108	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	27.00	EACH

Call: 811

Contract: B -41194-A

Section No.: 2 BRIDGE DECK OVERLAY LATEX MODIFIED CONCRETE

Line

Item No	Item Code	Description	Quantity	Unit
0109	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	879.00	SYS

Call: 811

Contract: B -41194-A

Section No.: 3 BRIDGE DECK OVERLAY SILICA FUME MODIFIED CONCRETE

Line

Item No	Item Code	Description	Quantity	Unit
0110	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	879.00	SYS

Call: 821

Contract: B -42090-A

Section No.: 1 BRIDGE MAINTENANCE AND REPAIR

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0009	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0010	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0011	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0012	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0013	205-12108	STORMWATER MANAGEMENT BUDGET	13542.00 DOL
0014	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0015	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	30.00 CYS
0016	616-93772	INSPECTION HOLE	3.00 EACH
0017	619-11050	CLEAN STEEL BRIDGE, PARTIAL, QP-2, BRIDGE NO.	1.00 LS
0018	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00 LS
0019	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00 LS
0020	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00 LS
0021	619-51860	PAINT STEEL BRIDGE, PARTIAL, BRIDGE NO.	1.00 LS
0022	619-95315	CLEAN AND PAINT BEARING ASSEMBLIES, BRIDGE NO.	1.00 LS
0023	619-95315	CLEAN AND PAINT BEARING ASSEMBLIES, BRIDGE NO.	1.00 LS
0024	628-09401	FIELD OFFICE, A	8.00 MOS
0025	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0026	702-51863	FIELD DRILLED HOLE IN CONCRETE	14.00 EACH
0027	710-09158	PATCHING CONCRETE STRUCTURES	100.00 SFT
0028	711-05728	REPAIR	10.00 EACH
0029	711-51035	STRUCTURAL STEEL	1467.00 LBS
0030	711-51877	JACKING AND SUPPORTING, BEAMS	1.00 LS
0031	711-51877	JACKING AND SUPPORTING, BEAMS	1.00 LS

0032	711-51877	JACKING AND SUPPORTING, BEAMS	1.00	LS
0033	724-12103	PRE-COMPRESSED FOAM JOINT	170.00	LFT
0034	724-12420	BRIDGE JOINT NOSING	248.00	SFT
0035	724-12461	CONCRETE FOR PATCHING STRUCTURAL EXPANSION JOINT	83.00	SFT
0036	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.00	EACH
0037	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0038	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	10080.00	LFT
0039	801-06625	DETOUR ROUTE MARKER ASSEMBLY	24.00	EACH
0040	801-06640	CONSTRUCTION SIGN, A	53.00	EACH
0041	801-06710	FLASHING ARROW SIGN	20.00	DAY
0042	801-06775	MAINTAINING TRAFFIC	1.00	LS
0043	801-07118	BARRICADE, III-A	72.00	LFT
0044	801-07119	BARRICADE, III-B	48.00	LFT
0045	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0046	801-12042	TRUCK MOUNTED ATTENUATOR	20.00	DAY
0047	801-12324	LAW ENFORCEMENT OFFICER	450.00	HRS
0048	801-12647	LAW ENFORCEMENT OFFICER TRAINING	1.00	DOL

Call: 831

Contract: B -42127-A

Section No.: 1 REPAIR OR REPLACE JOINTS

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0007	628-09403	FIELD OFFICE, C	6.00 MOS
0008	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0009	724-12103	PRE-COMPRESSED FOAM JOINT	636.00 LFT
0010	724-12420	BRIDGE JOINT NOSING	608.00 SFT
0011	724-12461	CONCRETE FOR PATCHING STRUCTURAL EXPANSION JOINT	224.00 SFT
0012	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.00 EACH
0013	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00 EACH
0014	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	6720.00 LFT
0015	801-06625	DETOUR ROUTE MARKER ASSEMBLY	38.00 EACH
0016	801-06640	CONSTRUCTION SIGN, A	49.00 EACH
0017	801-06645	CONSTRUCTION SIGN, B	3.00 EACH
0018	801-06710	FLASHING ARROW SIGN	8.00 DAY
0019	801-06775	MAINTAINING TRAFFIC	1.00 LS
0020	801-07118	BARRICADE, III-A	136.00 LFT
0021	801-07119	BARRICADE, III-B	72.00 LFT
0022	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00 EACH
0023	801-12042	TRUCK MOUNTED ATTENUATOR	8.00 DAY
0024	801-12324	LAW ENFORCEMENT OFFICER	72.00 HRS
0025	801-12647	LAW ENFORCEMENT OFFICER TRAINING	2.00 DOL

Call: 841

Contract: B -42212-A

Section No.: 1 BRIDGE DECK PATCHING

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0007	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0008	202-02240	PAVEMENT REMOVAL	8.00 SYS
0009	507-08272	JOINTS IN PCCP, SAW AND SEAL	71.00 LFT
0010	609-06262	REINFORCED CONCRETE BRIDGE APPROACH, 14 IN.	8.00 SYS
0011	709-51821	SURFACE SEAL	1.00 LS
0012	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	144.00 SFT
0013	724-12103	PRE-COMPRESSED FOAM JOINT	71.00 LFT
0014	724-12461	CONCRETE FOR PATCHING STRUCTURAL EXPANSION JOINT	176.00 SFT
0015	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00 EACH
0016	801-06625	DETOUR ROUTE MARKER ASSEMBLY	33.00 EACH
0017	801-06640	CONSTRUCTION SIGN, A	13.00 EACH
0018	801-06775	MAINTAINING TRAFFIC	1.00 LS
0019	801-07118	BARRICADE, III-A	72.00 LFT
0020	801-07119	BARRICADE, III-B	48.00 LFT
0021	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	20.00 LFT
0022	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	170.00 LFT

Call: 851

Contract: B -43150-A

Section No.: 1 BRIDGE DECK OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	202-02240	PAVEMENT REMOVAL	1992.00	SYS
0010	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0011	202-62420	BRIDGE RAILING, REMOVE	110.00	LFT
0012	202-94954	BARRIER WALL, CONCRETE, REMOVE	385.00	LFT
0013	203-02000	EXCAVATION, COMMON	335.00	CYS
0014	205-12108	STORMWATER MANAGEMENT BUDGET	1266.00	DOL
0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0016	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	25.00	CYS
0017	207-09935	SUBGRADE TREATMENT, TYPE IC	3270.00	SYS
0018	211-02050	B BORROW	18.00	CYS
0019	211-06467	AGGREGATE FOR END BENT BACKFILL	23.00	CYS
0020	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	2036.00	SYS
0021	302-06464	SUBBASE FOR PCCP	463.00	CYS
0022	402-10087	HMA FOR TEMPORARY PAVEMENT, D	815.00	TON
0023	406-05521	ASPHALT FOR TACK COAT	2467.00	SYS
0024	503-03489	RETROFITTED TIE BARS	220.00	EACH
0025	503-05240	D-1 CONTRACTION JOINT	220.00	LFT
0026	503-12478	TERMINAL JOINT, TYPE PCCP	220.00	LFT
0027	503-12479	EXPANSION JOINT WITH LOAD TRANSFER	220.00	LFT
0028	503-12505	JOINTED REINFORCED CONCRETE PAVEMENT 14 IN.	977.00	SYS
0029	602-01064	CONCRETE BARRIER	80.00	LFT
0030	602-01064	CONCRETE BARRIER	87.00	LFT
0031	602-06729	BARRIER, DELINEATOR	25.00	EACH

0032	602-11938	CONCRETE BARRIER, MODIFIED SECTION	31.80	CYS
0033	609-06263	REINFORCED CONCRETE BRIDGE APPROACH, 15 IN.	1058.00	SYS
0034	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	36.00	SYS
0035	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0036	621-06560	MULCHED SEEDING U	1234.00	SYS
0037	628-09403	FIELD OFFICE, C	5.00	MOS
0038	628-11976	COMPUTER SYSTEM EQUIPMENT	4.00	EACH
0039	702-51863	FIELD DRILLED HOLE IN CONCRETE	864.00	EACH
0040	702-92857	CONCRETE, C, SUBSTRUCTURE	24.60	CYS
0041	703-06029	REINFORCING BARS, EPOXY COATED	70399.00	LBS
0042	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	558.00	EACH
0043	706-11601	RAILING, CONCRETE FT	13.40	CYS
0044	706-51020	RAILING, CONCRETE C	23.00	CYS
0045	709-51821	SURFACE SEAL	1.00	LS
0046	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	50.00	SFT
0047	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	1424.00	SFT
0048	724-12103	PRE-COMPRESSED FOAM JOINT	220.00	LFT
0049	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	3165.00	SYS
0050	801-04308	ROAD CLOSURE SIGN ASSEMBLY	1.00	EACH
0051	801-06201	TEMPORARY PANEL SIGNS	444.00	SFT
0052	801-06202	TEMPORARY PANEL SIGN SUPPORTS	228.00	LFT
0053	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	21915.00	LFT
0054	801-06625	DETOUR ROUTE MARKER ASSEMBLY	6.00	EACH
0055	801-06640	CONSTRUCTION SIGN, A	27.00	EACH
0056	801-06645	CONSTRUCTION SIGN, B	4.00	EACH
0057	801-06775	MAINTAINING TRAFFIC	1.00	LS
0058	801-07118	BARRICADE, III-A	36.00	LFT
0059	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	2110.00	LFT
0060	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	3.00	EACH
0061	808-06716	LINE, REMOVE	4532.00	LFT
0062	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	2032.00	LFT
0063	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	2032.00	LFT
0064	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	285.00	LFT
0065	808-10043	LINE, MULTI-COMPONENT, SOLID, WHITE, 24 IN.	90.00	LFT
0066	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	1524.00	LFT
0067	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	24.00	EACH

Call: 901

Contract: T -41022-A

Section No.: 1 CURVE SIGN AND MARKING VISIBILITY IMPROVEMENTS

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0007	628-09403	FIELD OFFICE, C	8.00 MOS
0008	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0009	801-06775	MAINTAINING TRAFFIC	1.00 LS
0010	801-12042	TRUCK MOUNTED ATTENUATOR	60.00 DAY
0011	802-04089	SIGN, SHEET, REMOVE	462.00 EACH
0012	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	2869.00 LFT
0013	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	40.00 EACH
0014	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	2408.00 SFT
0015	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	1948.00 SFT

Call: 911

Contract: T -41025-A

Section No.: 1 CABLE BARRIER SYSTEM

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0008	203-02070	BORROW	200.00	CYS
	0009	203-08607	LINEAR GRADING	25872.00	LFT
	0010	205-12108	STORMWATER MANAGEMENT BUDGET	46355.00	DOL
	0011	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0012	205-12618	SWQCP PREPARATION	1.00	LS
	0013	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	10.00	EACH
	0014	621-06559	MULCHED SEEDING R	57533.00	SYS
	0015	621-06567	WATER	20.00	KGAL
	0016	627-09327	CABLE BARRIER SYSTEM, TYPE TL-4	25890.00	LFT
	0017	627-09331	SAFETY TERMINAL TYPE, TL-4	24.00	EACH
	0018	627-10178	CABLE BARRIER SYSTEM, TYPE TL-4 SPARE PARTS	1.00	LS
	0019	628-09403	FIELD OFFICE, C	9.00	MOS
	0020	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
	0021	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.00	EACH
	0022	801-03290	CONSTRUCTION SIGN, C	4.00	EACH
	0023	801-06640	CONSTRUCTION SIGN, A	84.00	EACH
	0024	801-06645	CONSTRUCTION SIGN, B	10.00	EACH
	0025	801-06710	FLASHING ARROW SIGN	240.00	DAY
	0026	801-06775	MAINTAINING TRAFFIC	1.00	LS
	0027	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	8.00	EACH
	0028	801-12042	TRUCK MOUNTED ATTENUATOR	60.00	DAY
	0029	804-06740	DELINEATOR WITH POST, D2	24.00	EACH

Call: 921

Contract: T -41260-A

Section No.: 1 TRAFFIC SIGNAL VISIBILITY IMPROVEMENTS

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0007	628-09402	FIELD OFFICE, B	8.00 MOS
0008	628-11729	CELLULAR TELEPHONE, TYPE A	2.00 EACH
0009	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00 DOL
0010	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00 DOL
0011	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	16.00 MOS
0012	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0013	628-11977	COMPUTER SYSTEM	2.00 EACH
0014	801-06640	CONSTRUCTION SIGN, A	24.00 EACH
0015	801-06645	CONSTRUCTION SIGN, B	8.00 EACH
0016	801-06775	MAINTAINING TRAFFIC	1.00 LS
0017	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	421.00 SFT
0018	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	126.00 SFT
0019	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	223.00 SFT
0020	805-03372	TETHER FOR SIGNAL	35.00 EACH
0021	805-06483	CONTROLLER	8.00 EACH
0022	805-08244	CELLULAR MODEM KIT	8.00 EACH
0023	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	99.00 EACH
0024	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	12.00 EACH
0025	805-78230	TRAFFIC SIGNAL HEAD, 5 SECTION, 12 IN.	6.00 EACH
0026	805-78415	SPAN, CATENARY, AND TETHER	1.00 EACH
0027	805-78420	DISCONNECT HANGER	40.00 EACH
0028	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	6344.00 LFT
0029	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	3219.00 LFT
0030	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	4412.00 LFT

Call: 931

Contract: T -41262-A

Section No.: 1 CENTERLINE RUMBLE STRIPES INSTALLATION

Line			Quantity	Unit
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	617250.00	LFT
0008	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0009	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0010	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0011	628-11781	CELLULAR TELEPHONE SERVICE, 750 MIN.	6.00	MOS
0012	801-03290	CONSTRUCTION SIGN, C	13.00	EACH
0013	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	43277.00	LFT
0014	801-06640	CONSTRUCTION SIGN, A	224.00	EACH
0015	801-06775	MAINTAINING TRAFFIC	1.00	LS
0016	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	70990.00	LFT
0017	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	859877.00	LFT
0018	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	413736.00	LFT

Call: 941

Contract: T -41263-A

Section No.: 1 RAISED PAVEMENT MARKINGS, REFURBISHED

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0008	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0009	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0010	628-11781	CELLULAR TELEPHONE SERVICE, 750 MIN.	6.00	MOS
0011	801-06710	FLASHING ARROW SIGN	180.00	DAY
0012	801-06775	MAINTAINING TRAFFIC	1.00	LS
0013	808-75994	PRISMATIC REFLECTOR	26258.00	EACH
0014	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	190.00	EACH
0015	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1265.00	EACH

Call: 951

Contract: T -42696-A

Section No.: 1 ITS PROGRAM EQUIPMENT

Line			Quantity	Unit
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0008	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0009	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0010	628-11781	CELLULAR TELEPHONE SERVICE, 750 MIN.	6.00	MOS
0011	801-06640	CONSTRUCTION SIGN, A	36.00	EACH
0012	801-06645	CONSTRUCTION SIGN, B	16.00	EACH
0013	801-06775	MAINTAINING TRAFFIC	1.00	LS
0014	805-12016	UNINTERRUPTIBLE POWER SUPPLY	14.00	EACH