

**Schedule of Pay Items Letting Date December 7, 2022 Letting ID 221207**

Call: 150

Contract: R -35352-A

Section No.: 1 INTERSECTION IMPROVEMENT WITH ADDED TURN LANES

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0011	202-02271	HEADWALL, REMOVE	2.00 EACH
0012	202-91385	INLET, REMOVE	2.00 EACH
0013	202-94749	CURB, ASPHALT, REMOVE	171.00 LFT
0014	202-96133	PIPE, REMOVE	113.00 LFT
0015	203-02000	EXCAVATION, COMMON	1256.00 CYS
0016	205-12108	STORMWATER MANAGEMENT BUDGET	16285.00 DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0018	205-12618	SWQCP PREPARATION	1.00 LS
0019	207-08264	SUBGRADE TREATMENT, TYPE II	67.00 SYS
0020	207-12498	SUBGRADE TREATMENT, TYPE ID	2889.00 SYS
0021	211-02050	B BORROW	491.00 CYS
0022	211-09265	STRUCTURE BACKFILL, TYPE 2	108.00 CYS
0023	303-01180	COMPACTED AGGREGATE NO. 53	138.00 TON
0024	304-12625	HMA PATCHING FULL DEPTH, TYPE C	64.00 TON
0025	306-08036	MILLING, ASPHALT, 2 IN.	5640.00 SYS
0026	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	891.00 TON
0027	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	345.00 TON
0028	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	787.00 TON
0029	401-10258	JOINT ADHESIVE, SURFACE	4332.00 LFT
0030	401-10259	JOINT ADHESIVE, INTERMEDIATE	4332.00 LFT
0031	401-11785	LIQUID ASPHALT SEALANT	4332.00 LFT

0032	406-05520	ASPHALT FOR TACK COAT	2.00 TON
0033	605-06140	CURB AND GUTTER, CONCRETE	265.00 LFT
0034	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	389.00 LFT
0035	610-07488	HMA FOR APPROACHES, TYPE C	67.00 TON
0036	610-09108	PCCP FOR APPROACHES, 9 IN.	78.00 SYS
0037	615-06490	RIGHT-OF-WAY MARKER	18.00 EACH
0038	615-06505	MONUMENT, B	10.00 EACH
0039	615-06510	MONUMENT, C	2.00 EACH
0040	616-06405	RIPRAP, REVETMENT	125.00 TON
0041	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	189.00 SYS
0042	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 EACH
0043	621-06560	MULCHED SEEDING U	1827.00 SYS
0044	621-06567	WATER	3.00 KGAL
0045	621-06574	SODDING	117.00 SYS
0046	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0047	628-12683	FIELD OFFICE, D	18.00 MOS
0048	629-12029	PLANT GROWTH LAYER	1947.00 SYS
0049	715-05121	PIPE, TYPE 1, CIRCULAR, 18 IN.	82.00 LFT
0050	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	74.00 LFT
0051	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	51.00 LFT
0052	715-09064	VIDEO INSPECTION FOR PIPE	207.00 LFT
0053	715-46010	PIPE END SECTION, DIAMETER 18 IN.	3.00 EACH
0054	720-03757	MANHOLE, C15	1.00 EACH
0055	720-07309	TRENCH DRAIN	2.00 LFT
0056	720-11721	CASTING TRENCH DRAIN	2.00 LFT
0057	720-45030	INLET, E7	1.00 EACH
0058	720-45410	MANHOLE, C4	1.00 EACH
0059	720-93409	INLET, B15 MODIFIED	2.00 EACH
0060	801-03290	CONSTRUCTION SIGN, C	1.00 EACH
0061	801-04308	ROAD CLOSURE SIGN ASSEMBLY	3.00 EACH
0062	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	2500.00 LFT
0063	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3630.00 LFT
0064	801-06625	DETOUR ROUTE MARKER ASSEMBLY	30.00 EACH
0065	801-06640	CONSTRUCTION SIGN, A	20.00 EACH
0066	801-06645	CONSTRUCTION SIGN, B	3.00 EACH
0067	801-06710	FLASHING ARROW SIGN	95.00 DAY
0068	801-06775	MAINTAINING TRAFFIC	1.00 LS

0069	801-07118	BARRICADE, III-A	60.00	LFT
0070	801-07119	BARRICADE, III-B	16.00	LFT
0071	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	650.00	LFT
0072	802-04089	SIGN, SHEET, REMOVE	1.00	EACH
0073	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	36.00	LFT
0074	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	15.00	LFT
0075	802-07060	SIGN, SHEET, RELOCATE	6.00	EACH
0076	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	38.00	SFT
0077	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	10.00	SFT
0078	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	19.00	SFT
0079	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.00	EACH
0080	805-01579	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00	LS
0081	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	4.00	EACH
0082	805-01842	HANDHOLE, SIGNAL, TYPE 1	9.00	EACH
0083	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00	LS
0084	805-02445	CONTROLLER AND CABINET, P1	1.00	EACH
0085	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	5.00	EACH
0086	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	1.00	EACH
0087	805-78230	TRAFFIC SIGNAL HEAD, 5 SECTION, 12 IN.	1.00	EACH
0088	805-78415	SPAN, CATENARY, AND TETHER	3.00	EACH
0089	805-78420	DISCONNECT HANGER	3.00	EACH
0090	805-78445	SIGNAL SERVICE	1.00	EACH
0091	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GAUGE	65.00	LFT
0092	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	2431.00	LFT
0093	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	170.00	LFT
0094	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	64.00	LFT
0095	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GAUGE	542.00	LFT
0096	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	1525.00	LFT
0097	805-78785	SIGNAL DETECTOR HOUSING	7.00	EACH
0098	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	717.00	LFT
0099	805-78925	CONTROLLER CABINET FOUNDATION, P1	1.00	EACH
0100	805-81032	SIGNAL POLE, STEEL STRAIN, 30 FT	3.00	EACH
0101	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	1.00	EACH
0102	805-92504	LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	7.00	EACH
0103	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	1359.00	LFT
0104	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	140.00	LFT
0105	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	3613.00	LFT

0106	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	335.00	LFT
0107	808-10118	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 24 IN.	22.00	LFT
0108	808-12032	GROOVING FOR PAVEMENT MARKINGS	8650.00	LFT
0109	808-75215	LINE, THERMOPLASTIC, SOLID, WHITE, 12 IN.	75.00	LFT
0110	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	4702.00	LFT
0111	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	389.00	LFT
0112	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	80.00	LFT
0113	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	9.00	EACH
0114	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	6.00	EACH
0115	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	16.00	EACH
0116	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	16.00	EACH