

Schedule of Pay Items Letting Date June 15, 2022 Letting ID 220615

Call: 140

Contract: R -40557-A

Section No.: 1 SLIDE CORRECTION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	104-05404	DESIGN BUILD	1.00	LS
0002	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	203-02020	EXCAVATION, UNCLASSIFIED	3775.00	CYS
0014	205-12108	STORMWATER MANAGEMENT BUDGET	19726.00	DOL
0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0016	205-12618	SWQCP PREPARATION	1.00	LS
0017	206-51235	COFFERDAM	1.00	LS
0018	207-12498	SUBGRADE TREATMENT, TYPE ID	1234.00	SYS
0019	211-09267	STRUCTURE BACKFILL, TYPE 4	26.00	CYS
0020	301-12231	COMPACTED AGGREGATE NO. 2	49.00	CYS
0021	303-01180	COMPACTED AGGREGATE NO. 53	232.00	TON
0022	304-07493	WIDENING WITH HMA, TYPE B	33.00	TON
0023	306-08034	MILLING, ASPHALT, 1 1/2 IN.	142.00	SYS
0024	306-08043	MILLING, TRANSITION	592.00	SYS
0025	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	154.00	TON
0026	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	149.00	TON
0027	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	371.00	TON
0028	401-10258	JOINT ADHESIVE, SURFACE	1184.00	LFT
0029	401-10259	JOINT ADHESIVE, INTERMEDIATE	1104.00	LFT
0030	401-11785	LIQUID ASPHALT SEALANT	1184.00	LFT
0031	406-05520	ASPHALT FOR TACK COAT	2.00	TON

0032	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.00 TON
0033	601-02241	GUARDRAIL, REMOVE	318.80 LFT
0034	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	337.50 LFT
0035	601-12289	GUARDRAIL, MGS, HEIGHT TRANSITION	1.00 EACH
0036	601-94689	GUARDRAIL, END TREATMENT, OS	1.00 EACH
0037	615-06490	RIGHT-OF-WAY MARKER	21.00 EACH
0038	615-06505	MONUMENT, B	3.00 EACH
0039	616-05688	RIPRAP, CLASS 1	540.00 TON
0040	616-06405	RIPRAP, REVETMENT	3909.00 TON
0041	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	175.00 SYS
0042	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	2002.00 SYS
0043	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00 EACH
0044	621-06559	MULCHED SEEDING R	1196.00 SYS
0045	621-06567	WATER	1.00 KGAL
0046	621-06574	SODDING	213.00 SYS
0047	628-09403	FIELD OFFICE, C	10.00 MOS
0048	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0049	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	119.00 LFT
0050	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	72.00 LFT
0051	718-06531	OUTLET PROTECTOR, 3	1.00 EACH
0052	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	191.00 LFT
0053	718-12308	GEOTEXTILE FOR UNDERDRAIN, TYPE 2B	103.00 SYS
0054	718-52610	AGGREGATE FOR UNDERDRAINS	7.00 CYS
0055	801-04308	ROAD CLOSURE SIGN ASSEMBLY	13.00 EACH
0056	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	820.00 LFT
0057	801-06625	DETOUR ROUTE MARKER ASSEMBLY	69.00 EACH
0058	801-06640	CONSTRUCTION SIGN, A	34.00 EACH
0059	801-06775	MAINTAINING TRAFFIC	1.00 LS
0060	801-07119	BARRICADE, III-B	204.00 LFT
0061	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	14.00 LFT
0062	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	2.00 EACH
0063	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	2.30 SFT
0064	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	9.00 SFT
0065	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1230.00 LFT
0066	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1230.00 LFT
0067	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	15.00 EACH
0068	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	15.00 EACH