

Schedule of Pay Items Letting Date January 19, 2023 Letting ID 230119

Call: 161

Contract: R -40872-B

Section No.: 1 ROAD RECONSTRUCTION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-02250	TREE 10 IN., REMOVE	1.00 EACH
0011	201-02255	TREE 18 IN., REMOVE	1.00 EACH
0012	201-02265	TREE 48 IN., REMOVE	1.00 EACH
0013	201-02270	TREE 60 IN., REMOVE	1.00 EACH
0014	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0015	202-02240	PAVEMENT REMOVAL	2853.00 SYS
0016	202-02279	CURB AND GUTTER, REMOVE	263.00 LFT
0017	202-05545	REGULATED MATERIALS, DISPOSE, TYPE C	51.00 CYS
0018	202-05550	REGULATED MATERIALS, REMOVE, TYPE C	51.00 CYS
0019	202-05555	REGULATED MATERIALS, TRANSPORT, TYPE C	51.00 CYS
0020	202-07603	TESTING FOR WASTES, TYPE C	1.00 EACH
0021	202-52710	SIDEWALK CONCRETE, REMOVE	1693.00 SYS
0022	202-91351	TRACK, REMOVE	1266.00 LFT
0023	202-96133	PIPE, REMOVE	488.00 LFT
0024	202-97009	FIRE HYDRANT ASSEMBLY, REMOVE	2.00 EACH
0025	203-02000	EXCAVATION, COMMON	2683.00 CYS
0026	205-12108	STORMWATER MANAGEMENT BUDGET	10000.00 DOL
0027	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0028	205-12618	SWQCP PREPARATION	1.00 LS
0029	207-08264	SUBGRADE TREATMENT, TYPE II	596.00 SYS
0030	207-09935	SUBGRADE TREATMENT, TYPE IC	7250.00 SYS
0031	211-02050	B BORROW	51.00 CYS

0032	211-09265	STRUCTURE BACKFILL, TYPE 2	1447.00	CYS
0033	211-09266	STRUCTURE BACKFILL, TYPE 3	25.00	CYS
0034	214-11796	GEOGRID, TYPE IB	421.00	SYS
0035	301-12234	COMPACTED AGGREGATE NO. 53	1433.00	CYS
0036	302-07455	DENSE GRADED SUBBASE	151.00	CYS
0037	303-08210	COMPACTED AGGREGATE, NO. 53, TEMPORARY FOR DRIVEWAYS	240.00	TON
0038	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	436.00	TON
0039	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	724.00	TON
0040	401-10258	JOINT ADHESIVE, SURFACE	4310.00	LFT
0041	401-10259	JOINT ADHESIVE, INTERMEDIATE	4310.00	LFT
0042	401-11785	LIQUID ASPHALT SEALANT	4310.00	LFT
0043	406-05520	ASPHALT FOR TACK COAT	3.00	TON
0044	601-06035	GUARDRAIL, RESET	10.00	LFT
0045	604-01268	HAND RAIL ALUMINUM	55.00	LFT
0046	604-06070	SIDEWALK, CONCRETE	1609.00	SYS
0047	604-08086	CURB RAMP, CONCRETE	145.00	SYS
0048	604-12083	DETECTABLE WARNING SURFACES	23.00	SYS
0049	604-44251	STEPS, CONCRETE	16.00	CYS
0050	605-02278	CURB, REMOVE	2062.00	LFT
0051	605-06120	CURB, CONCRETE	207.00	LFT
0052	605-06140	CURB AND GUTTER, CONCRETE	1872.00	LFT
0053	610-07487	HMA FOR APPROACHES, TYPE B	120.00	TON
0054	610-08446	PCCP FOR APPROACHES, 6 IN.	176.00	SYS
0055	610-09108	PCCP FOR APPROACHES, 9 IN.	421.00	SYS
0056	621-06567	WATER	80.00	kGAL
0057	621-06575	SODDING, NURSERY	1302.00	SYS
0058	628-09403	FIELD OFFICE, C	20.00	MOS
0059	702-02925	WATERPROOFING MEMBRANE SYSTEM	55.00	SFT
0060	702-90915	CONCRETE, CLASS, A	5.00	CYS
0061	714-05562	RETAINING WALL	155.00	SFT
0062	715-02745	GATE VALVE WITH VALVE BOX 8 IN.	3.00	EACH
0063	715-03053	METER PIT	22.00	EACH
0064	715-05024	PIPE, TYPE 2, CIRCULAR, 36 IN.	62.00	LFT
0065	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	253.00	LFT
0066	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	20.00	LFT
0067	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	807.00	LFT
0068	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	326.00	LFT

0069	715-05914	PIPE PVC 18 IN.	22.00	LFT
0070	715-06050	CAP	14.00	EACH
0071	715-09064	VIDEO INSPECTION FOR PIPE	1599.00	LFT
0072	715-11473	PIPE, PVC, 16 IN.	25.00	LFT
0073	715-90714	PIPE PVC, 12 IN	82.00	LFT
0074	715-90853	TAPPING SLEEVE WITH VALVE	2.00	EACH
0075	715-90853	TAPPING SLEEVE WITH VALVE	5.00	EACH
0076	715-90853	TAPPING SLEEVE WITH VALVE	3.00	EACH
0077	715-91739	WATER SERVICE LINE, 0.75 IN.	570.00	LFT
0078	715-93403	WATER SERVICE CONNECTION, 0.75 IN.	22.00	EACH
0079	715-93913	WATER MAIN, 8 IN.	140.00	LFT
0080	715-93913	WATER MAIN, 8 IN.	1437.00	LFT
0081	720-02810	INLET, B5	1.00	EACH
0082	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	2.00	EACH
0083	720-45260	PIPE CATCH BASIN, 12 IN.	1.00	EACH
0084	720-45410	MANHOLE, C4	8.00	EACH
0085	720-94612	MANHOLE, K4	1.00	EACH
0086	720-94840	CASTING, WATER VALVE, ADJUST TO GRADE	1.00	EACH
0087	720-95422	MANHOLE, J4	1.00	EACH
0088	720-96999	FIRE HYDRANT ASSEMBLY	3.00	EACH
0089	720-98174	INLET, B15	15.00	EACH
0090	720-98555	INLET, C15	2.00	EACH
0091	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0092	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2034.00	LFT
0093	801-06625	DETOUR ROUTE MARKER ASSEMBLY	22.00	EACH
0094	801-06640	CONSTRUCTION SIGN, A	21.00	EACH
0095	801-06645	CONSTRUCTION SIGN, B	10.00	EACH
0096	801-06775	MAINTAINING TRAFFIC	1.00	LS
0097	801-07118	BARRICADE, III-A	154.00	LFT
0098	801-07119	BARRICADE, III-B	144.00	LFT
0099	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	48.00	LFT
0100	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	4.00	EACH
0101	802-07060	SIGN, SHEET, RELOCATE	13.00	EACH
0102	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	9.00	SFT
0103	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2074.00	LFT
0104	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	182.00	LFT
0105	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2034.00	LFT

0106	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	171.00	LFT
0107	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	698.00	LFT

Call: 541

Contract: B -40162-A

Section No.: 1

BRIDGE DECK REPLACEMENT

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0012	201-90788	DEBRIS, REMOVE STRUCTURE NO.	1.00	LS
	0013	202-02240	PAVEMENT REMOVAL	511.00	SYS
	0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
	0015	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
	0016	203-02000	EXCAVATION, COMMON	550.00	CYS
	0017	205-12108	STORMWATER MANAGEMENT BUDGET	52407.00	DOL
	0018	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0019	205-12618	SWQCP PREPARATION	1.00	LS
	0020	206-51225	EXCAVATION, DRY	155.00	CYS
	0021	206-51235	COFFERDAM	1.00	LS
	0022	207-09935	SUBGRADE TREATMENT, TYPE IC	8587.00	SYS
	0023	211-06467	AGGREGATE FOR END BENT BACKFILL	122.00	CYS
	0024	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	1071.00	SYS
	0025	302-06464	SUBBASE FOR PCCP	128.00	CYS
	0026	303-01180	COMPACTED AGGREGATE NO. 53	68.00	TON
	0027	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	273.00	TON
	0028	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	175.00	TON
	0029	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	308.00	TON
	0030	401-10258	JOINT ADHESIVE, SURFACE	2340.00	LFT
	0031	401-10259	JOINT ADHESIVE, INTERMEDIATE	900.00	LFT

0032	401-11785	LIQUID ASPHALT SEALANT	3240.00	LFT
0033	402-10086	HMA FOR TEMPORARY PAVEMENT, TYPE C	4134.00	TON
0034	406-05521	ASPHALT FOR TACK COAT	4561.00	SYS
0035	503-12477	TERMINAL JOINT, TYPE HMA	152.00	LFT
0036	601-02241	GUARDRAIL, REMOVE	1657.00	LFT
0037	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	1113.00	LFT
0038	601-12292	GUARDRAIL, MGS, TRANSITION WITHOUT CURB	8.00	EACH
0039	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0040	601-94690	GUARDRAIL, END TREATMENT, MS	4.00	EACH
0041	602-06729	BARRIER, DELINEATOR	56.00	EACH
0042	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	1560.00	LFT
0043	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	517.00	SYS
0044	615-06505	MONUMENT, B	4.00	EACH
0045	616-05689	RIPRAP, CLASS 2	344.00	TON
0046	616-06405	RIPRAP, REVETMENT	98.00	TON
0047	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	420.00	SYS
0048	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0049	621-04258	SEED MIXTURE	1.00	LBS
0050	621-06567	WATER	1.00	KGAL
0051	621-06574	SODDING	54.00	SYS
0052	621-12612	SEED MIXTURE, FLOODPLAIN	28.00	LBS
0053	628-09403	FIELD OFFICE, C	24.00	MOS
0054	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0055	628-11730	CELLULAR TELEPHONE, TYPE B	1.00	EACH
0056	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0057	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0058	628-11781	CELLULAR TELEPHONE SERVICE, 750 MIN.	48.00	MOS
0059	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0060	628-11977	COMPUTER SYSTEM	1.00	EACH
0061	628-12685	TELEPHONE SERVICE, A	24.00	MOS
0062	701-09557	TEST PILE, DYNAMIC, PRODUCTION	297.00	LFT
0063	701-09559	TEST PILE, DYNAMIC, RESTRIKE	6.00	EACH
0064	701-09662	PILE, STEEL PIPE, 0.250 IN., 14 IN.	492.00	LFT
0065	701-09826	PILE, STEEL PIPE, 0.5 IN., 14 IN.	1340.00	LFT
0066	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	15.00	EACH
0067	702-51005	CONCRETE, A, SUBSTRUCTURE	91.00	CYS
0068	702-92857	CONCRETE, C, SUBSTRUCTURE	49.90	CYS

0069	703-06029	REINFORCING BARS, EPOXY COATED	486073.00	LBS
0070	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	82.00	EACH
0071	704-51002	CONCRETE, C, SUPERSTRUCTURE	1156.90	CYS
0072	706-09960	RAILING, CONCRETE FC	1930.00	LFT
0073	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	8.00	EACH
0074	709-51821	SURFACE SEAL	1.00	LS
0075	709-51821	SURFACE SEAL	1.00	LS
0076	710-09158	PATCHING CONCRETE STRUCTURES	10.00	SFT
0077	711-04297	STRUCTURAL STEEL, FIELD CUT	576.00	SQIN
0078	711-51038	STRUCTURAL STEEL	1.00	LS
0079	711-51864	DRILLED HOLE	96.00	EACH
0080	711-90114	JACKING AND SUPPORTING, SUPERSTRUCTURE	1.00	LS
0081	711-90114	JACKING AND SUPPORTING, SUPERSTRUCTURE	1.00	LS
0082	711-96800	STUD SHEAR CONNECTORS	10638.00	EACH
0083	713-04331	TEMPORARY CAUSEWAY	1.00	LS
0084	715-05407	PIPE, END BENT DRAIN, 6 IN.	320.00	LFT
0085	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	15.00	EACH
0086	722-12732	LONGITUDINAL GROOVING	5001.00	SYS
0087	724-12773	BRIDGE EXPANSION JOINT, PCF	152.00	LFT
0088	726-92406	BEARING ASSEMBLY ELASTOMERIC	26.00	EACH
0089	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	41135.00	LFT
0090	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	5294.00	LFT
0091	801-06640	CONSTRUCTION SIGN, A	54.00	EACH
0092	801-06645	CONSTRUCTION SIGN, B	9.00	EACH
0093	801-06710	FLASHING ARROW SIGN	365.00	DAY
0094	801-06775	MAINTAINING TRAFFIC	1.00	LS
0095	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	1.00	EACH
0096	801-07119	BARRICADE, III-B	240.00	LFT
0097	801-07606	TEMPORARY CROSSOVER DRAINAGE PIPE	1000.00	LFT
0098	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	1.00	EACH
0099	801-12042	TRUCK MOUNTED ATTENUATOR	10.00	DAY
0100	801-12883	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, CONTINUOUS	3.00	EACH
0101	801-52817	TEMPORARY CROSSOVER, B	2.00	EACH
0102	808-06716	LINE, REMOVE	2677.00	LFT
0103	808-75002	LINE, PAINT, BROKEN, WHITE, 6 IN.	1724.00	LFT
0104	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	1864.00	LFT
0105	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	3284.00	LFT

0106 808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER

26.00 EACH