

# Mix Designs, Trial Batches & PCCP Production

501 QC/QA PCCP

502 Non-QC/QA PCCP

506 Patching PCCP

# QC/QA PCCP

- Section 501 of Standard Specifications
  - RSP in Contracts let on or after Feb 2009
    - Revisions to mix design and trial batch
  - Prior lettings allowed thru CO
    - See Construction Memo 09-06
    - Entitled “PCCP Cost Savings Measures”
  - Otherwise Section 501.04 & .05 in 2008 Book

# CMDS for QC/QA PCCP

- Concrete Mix Design Submittal
  - Prepared By Contr. on Department Spreadsheet
  - Specific information
    - Plant & Contract
    - Specification Reference
    - Materials
    - Proportioning
    - Targets for UW, W/C and Fine to Total Agg Ratio
  - Submitted to, and Approved by DTE
    - Ready for Trial Batch Only
    - (not approved for **P**roduction)

### INDOT CONCRETE MIX DESIGN SPREADSHEET FOR ENGLISH CONTRACTS

MIX PRODUCER imi Southwest, Inc. CONTRACT NO. IR-29384  
 PRODUCT ID 1455 INDOT DISTRICT Vincennes  
 PLANT LOCATION Lloyd Expressway - Evansville  
 INDOT PLANT NO. 1494 SUBMITTAL STAGE CMDS

INDOT CMD NO. **086501011S** SPEC. REFERENCE **501**

| FINE & COARSE AGGREGATE MATERIALS |             |  |      |      |      |         |
|-----------------------------------|-------------|--|------|------|------|---------|
| Q#                                | Source Code | PRODUCER NAME                                  | SIZE | TYPE | QUAL | LEDGES  |
| Q972021                           | 2621        | zer Crushed Stone, Evansville Redist(Cape Sar  | #8   | CS   | AP   | 804-812 |
| Q972021                           | 2632        | ilzer Crushed Stone, Evansville Redist(Evansvi | #23  | NS   |      |         |

\*\*% passing No. 200 sieve , CA contributes 1.6% , FA contributes 0.3%

| CEMENT & POZZOLAN MATERIALS |                            |                  |               | WATER        |
|-----------------------------|----------------------------|------------------|---------------|--------------|
| W#                          | MANUFACTURER / LOCATION    | PLANT or PRODUCT | DESCRIPTION   | SOURCE       |
| W028367                     | Lehigh Portland Cement Co. | Mitchell, IN.    | Type I Cement | pub. utility |
|                             |                            |                  |               | QUALITY      |

| AIR ENTRAINING AGENT, CHEMICAL ADMIXTURES & CALCIUM CHLORIDE SOLUTION |                  |              |      |                     |
|---|------------------|--------------|------|---------------------|
| W#  | MANUFACTURER     | PRODUCT NAME | TYPE | DOSAGE RANGE oz/cwt |
| W028619   | W.R. Grace & Co. | Darex II AEA | AEA  | 0.50 to 5.0         |
| W028645   | W.R.Grace & Co.  | Daracem 55   | A    | 3.0-9.0             |

| BATCH PARAMETERS |               |                        |                |                |
|------------------|---------------|------------------------|----------------|----------------|
| MATERIAL         | WEIGHT<br>lbs | SP GR or<br>Bulk (ssd) | AGG.<br>ABS. % | VOLUME<br>ft³  |
| Cement           | 564           | 3.150                  | X              | 2.87           |
| Fly Ash          |               |                        | X              | 0.00           |
| GGBFS            |               |                        | X              | 0.00           |
| FA               | 1262          | 2.584                  | 1.34           | 7.83           |
| CA 1             | 1778          | 2.629                  | 2.22           | 10.84          |
| CA 2             |               |                        |                | 0.00           |
| water            | 230.9         | 1.000                  | X              | 3.70           |
| air              | 0             | 0.000                  | X              | 1.76           |
| ?                | 3835          |                        | X              | 27.00          |
| Yield Results:   |               |                        |                | <b>Correct</b> |

| SPECIFICATION PARAMETERS    |       |
|-----------------------------|-------|
| Cement/Fly Ash Ratio, by wt |       |
| Cement/GGBFS Ratio, by wt   |       |
| Cement Reduction, %         |       |
| Fly Ash Replacement Ratio   |       |
| GGBFS Replacement Ratio     |       |
| Cement Multiplier           |       |
| Fly Ash Addition, %         |       |
| GGBFS Addition, %           |       |
| Silica Fume Content, %      |       |
| Target W/(C+P), by wt       | 0.409 |
| Target Unit Weight, pcf     | 142.0 |
| FA to total Agg, % by wt    | 42    |
| FA to total Agg, % by vol   |       |
| *** % Passing 1 inch sieve  | 100   |
| ** % Passing No. 200 sieve  | 1.1   |

**DISTRIBUTION AFTER APPROVAL:**

Project Engineer  
 Contractor  
 Mix Producer  
 District Testing File

NAME: Mike Collins DATE: 7/23/2008  
 REPRESENTATIVE OF CONTRACTOR OR MIX PRODUCER

DTE SIGNATURE: *Mark Fligon* DATE: 7/26/2008

Producer Comments: For slip form work. Back up plant is #1532 Oak Grove Rd. Evansville  
 Same source for all raw materials, different distribution yard for aggregates.

DTE Notes: Concrete can not come from plant #1532 unless it has another approved INDOT CMD NO.

# CMDS for QC/QA PCCP

- Critical Elements for PE/PS Review
  - Contract No.
  - Submittal Stage (CMDS)
  - Specification Reference, 501
  - INDOT CMD No. with S suffix letter
  - Signed by DTE
  - DTE Notes or comments

# INDOT CONCRETE MIX DESIGN SPREADSHEET FOR ENGLISH CONTRACTS

|                 |                               |                 |           |
|-----------------|-------------------------------|-----------------|-----------|
| MIX PRODUCER    | imi Southwest, Inc.           | CONTRACT NO.    | IR-29384  |
| PRODUCT ID      | 1455                          | INDOT DISTRICT  | Vincennes |
| PLANT LOCATION  | Lloyd Expressway - Evansville |                 |           |
| INDOT PLANT NO. | 1494                          | SUBMITTAL STAGE | CMDS      |

|               |            |                 |     |
|---------------|------------|-----------------|-----|
| INDOT CMD NO. | 086501011S | SPEC. REFERENCE | 501 |
|---------------|------------|-----------------|-----|

| FINE & COARSE AGGREGATE MATERIALS |             |   |      |      |      |         |
|-----------------------------------|-------------|---|------|------|------|---------|
| Q#                                | Source Code | PRODUCER NAME                                   | SIZE | TYPE | QUAL | LEDGES  |
| Q972021                           | 2621        | zer Crushed Stone, Evansville Redist(Cape Sar   | #8   | CS   | AP   | 804-812 |
| Q972021                           | 2632        | ilzer Crushed Stone, Evansville Redist(Evansvil | #23  | NS   |      |         |
|                                   |             |   |      |      |      |         |

\*\*% passing No. 200 sieve , CA contributes 1.6% , FA contributes 0.3%

| CEMENT & POZZOLAN MATERIALS |                            |                  |               |
|-----------------------------|----------------------------|------------------|---------------|
| W#                          | MANUFACTURER / LOCATION    | PLANT or PRODUCT | DESCRIPTION   |
| W028367                     | Lehigh Portland Cement Co. | Mitchell, IN.    | Type I Cement |
|                             |                            |                  |               |
|                             |                            |                  |               |

|              |
|--------------|
| WATER        |
| SOURCE       |
| pub. utility |
| QUALITY      |

| AIR ENTRAINING AGENT, CHEMICAL ADMIXTURES & CALCIUM CHLORIDE SOLUTION |                  |              |      |                     |
|---|------------------|--------------|------|---------------------|
| W#  | MANUFACTURER     | PRODUCT NAME | TYPE | DOSAGE RANGE oz/cwt |
| W028619   | W.R. Grace & Co. | Darex II AEA | AEA  | 0.50 to 5.0         |
| W028645   | W.R.Grace & Co.  | Daracem 55   | A    | 3.0-9.0             |
|   |                  |              |      |                     |

| BATCH PARAMETERS |               |                        |                |               |
|------------------|---------------|------------------------|----------------|---------------|
| MATERIAL         | WEIGHT<br>lbs | SP GR or<br>Bulk (ssd) | AGG.<br>ABS. % | VOLUME<br>ft³ |
| Cement           | 564           | 3.150                  | <del> </del>   | 2.87          |
| Flv Ash          |               |                        | <del> </del>   | 0.00          |

| SPECIFICATION PARAMETERS    |  |
|-----------------------------|--|
| Cement/Fly Ash Ratio, by wt |  |
| Cement/GGBFS Ratio, by wt   |  |
| Cement Reduction, %         |  |
| Flv Ash Replacement Ratio   |  |

|  |  |  |  |  |
|--|--|--|--|--|
|  |  |  |  |  |
|--|--|--|--|--|

| BATCH PARAMETERS |               |                        |                       |                           |
|------------------|---------------|------------------------|-----------------------|---------------------------|
| MATERIAL         | WEIGHT<br>lbs | SP GR or<br>Bulk (ssd) | AGG.<br>ABS. %        | VOLUME<br>ft <sup>3</sup> |
| Cement           | 564           | 3.150                  | <del>          </del> | 2.87                      |
| Fly Ash          |               |                        | <del>          </del> | 0.00                      |
| GGBFS            |               |                        | <del>          </del> | 0.00                      |
|                  |               |                        | <del>          </del> | 0.00                      |
| FA               | 1262          | 2.584                  | 1.34                  | 7.83                      |
| CA 1             | 1778          | 2.629                  | 2.22                  | 10.84                     |
| CA 2             |               |                        |                       | 0.00                      |
| water            | 230.9         | 1.000                  | <del>          </del> | 3.70                      |
| air              | 0             | 0.000                  | <del>          </del> | 1.76                      |
| ?                | 3835          | <del>          </del>  | <del>          </del> | 27.00                     |
| Yield Results:   |               |                        |                       | <b>Correct</b>            |

| SPECIFICATION PARAMETERS    |       |
|-----------------------------|-------|
| Cement/Fly Ash Ratio, by wt |       |
| Cement/GGBFS Ratio, by wt   |       |
| Cement Reduction, %         |       |
| Fly Ash Replacement Ratio   |       |
| GGBFS Replacement Ratio     |       |
| Cement Multiplier           |       |
| Fly Ash Addition, %         |       |
| GGBFS Addition, %           |       |
| Silica Fume Content, %      |       |
| Target W/(C+P), by wt       | 0.409 |
| Target Unit Weight, pcf     | 142.0 |
| FA to total Agg, % by wt    | 42    |
| FA to total Agg, % by vol   |       |
| *** % Passing 1 inch sieve  | 100   |
| ** % Passing No. 200 sieve  | 1.1   |

DISTRIBUTION AFTER APPROVAL:

Project Engineer  
 Contractor  
 Mix Producer  
 District Testing File

NAME: Mike Collins DATE: 7/23/2008  
 REPRESENTATIVE OF CONTRACTOR OR MIX PRODUCER

DTE SIGNATURE: *Mark Fligor / AET* DATE: 7/26/2008

Producer Comments: For slip form work. Back up plant is #1532 Oak Grove Rd. Evansville  
 Same source for all raw materials, different distribution yard for aggregates.

DTE Notes: Concrete can not come from plant #1532 unless it has another approved INDOT CMD NO.

# Trial Batch For QC/QA PCCP

- Rely on DTE for Instruction/Guidance/HELP!
- Details in Special Provision in CIB
  - Trial Batch Not Required in all cases
    - Cement content 564 pcy & Design W/C  $\leq 0.420$
    - Class C per 702 using AP Quality CA
  - Trial Batch Required for Most Cases
    - Purpose
    - Preparation
    - Procedure



# Purpose of Trial Batch

- Validate Concrete Properties
- QC & Acceptance Testing Comparison
- Baseline Properties Of CMD
- Confirm Targets for UW and W/C
  - Part of Acceptance Testing (see 501.27)
- View Plant Process to understand QC needs
  - Part of QCP as defined in ITM 803
    - Trial Batch Demonstration (section 6.6)
    - Concrete Batching (section 6.7)

# Preparation For Trial Batch

- CMDS Approved by DTE
- Certified Tech & Qualified Inspector Present
- Allow Adequate Time
- Test Equipment and Molds
  - W/C
  - Unit Weight
  - Air Content
  - Beams for 7-day Flexural Strength
- Demonstration not Experimentation

# Procedure for Trial Batch

- 501.06 of Standard Specifications
  - Plant, prior to production
  - Lab, prior to production (ASTM C 192)
- Two page Worksheet
  - Part of Workbook with CMDS
  - Provides systematic approach
  - Promotes success
- Start With Aggregate Properties
  - Sample and test aggregate moistures for W/C
  - Bulk Sp. Gr. and absorption stated in CMDS

**TRIAL BATCH QC/QA PCCP per 501.06**

Date: 8/12/2008 Plant No. 1494 Location: Ohio St; Evansville, IN  
 Batching & Mixing Equipment: \_\_\_\_\_  
 INDOT CMD No. 086501011S  
 Name(s) of Contractor's Certified Technician and ACI Grade 1 Certification Number: John Summers (IMI), Larry Brown and Micah Meives (E&B).  
 Name(s) of INDOT Qualified Technician & Submitter Nos. Brandon Deputy

**AGGREGATE TEST RESULTS**

| Properties             | Contractor Result | Last Name of ACI Certified Technician | INDOT Result | Last Name of INDOT Qual. Technician |
|------------------------|-------------------|---------------------------------------|--------------|-------------------------------------|
| FA Bulk Sp. Gr. (SSD)  | 2.584             | Lingerfelt                            | NA           | NA                                  |
| FA Absorption, %       | 1.34              | Lingerfelt                            | NA           | NA                                  |
| FA Moisture, %         | 3.67              | Average                               | 3.51         | Deputy                              |
| CA Bulk Sp. Gr. (SSD)  | 2.629             | Lingerfelt                            | NA           | NA                                  |
| CA Absorption, %       | 2.22              | Lingerfelt                            | NA           | NA                                  |
| CA Moisture, %         | 2.54              | Average                               | 2.53         | Deputy                              |
| Agg. Correction Factor |                   |                                       | 0.2          | Irvin                               |

**CONCRETE BATCHING**

| Materials | Design Batch Weights (SSD Aggregate) lbs | Target Batch Weights (Moist Aggregates) lbs | Target Batch Size yd <sup>3</sup> | Total Target Batch Weights | Actual Batch Weights lbs | Batching Error ± % | Allowable Error ± % |
|-----------|--|---|-----------------------------------|----------------------------|--------------------------|--------------------|---------------------|
|           |  |   |                                   | lbs                        |                          |                    |                     |
| Cement    | 564                                      | 564   | 4.0000                            | 2256.00                    | 2260.00                  | 0.18               | ±1.49               |
| Fly Ash   | 0  | 0   | 4.0000                            | 0.00                       |                          |                    | ±1.49               |
| GGBFS     | 0  | 0   | 4.0000                            | 0.00                       |                          |                    | ±1.49               |
| FA        | 1262                                     | 1291  | 4.0000                            | 5165.62                    | 5160.00                  | -0.11              | ±2.49               |
| CA        | 1778                                     | 1784  | 4.0000                            | 7134.76                    | 7180.00                  | 0.63               | ±2.49               |
| Water     | 231                                      | 196   | 4.0000                            | 783.22                     | 772.00                   | -1.43              | ±1.49               |
| Σ         | 3835                                     | 3835  | NA                                | 15339.60                   | 15372.00                 | NA                 | NA                  |

**ADMIXTURE DOSAGE**

| Admixture Name | Target Dosage fl oz/cwt | Total Req. Dosage fl oz | Actual Dosage fl oz | Batching Error ± % | Allowable Error ± % |
|----------------|-------------------------|-------------------------|---------------------|--------------------|---------------------|
| Darex II AEA   | 1.60                    | 36.096                  | 36                  | -0.3               | ±3.49               |
| Daracem 55     | 3.00                    | 67.68                   | 68                  | 0.5                | ±3.49               |
| 0              |                         | 0                       |                     |                    | ±3.49               |

Comments on Batching: Carla (IA) Results- FA- 3.86%. CA- 2.69%.  
 John Summers Results- FA- 3.63%. CA- 2.40%.  
 Probe-3.70%.  
 Moisture Cookouts for Contractor are an average of State and Summers results.

v4cmdstp

**PLASTIC CONCRETE TEST RESULTS, 501.06**

| Plastic Property<br>086501011S    | Contractor Certified Technician Results | Last Name of ACI Certified Technician | INDOT Qualified Technician Results | Last Name of INDOT Qualified Technician |
|-----------------------------------|---|---------------------------------------|------------------------------------|---|
|                                   |   |                                       |                                    |   |
| Water/Cementitious Unit Wt. (pcf) | 0.403                                   | Summers                               | 0.399                              | Deputy                                  |
|                                   | 143.3                                   | Brown                                 | 144.0                              | Deputy                                  |
| Air Content (%)                   | 5.9                                     | Brown                                 | 5.7                                | Deputy                                  |
| Slump (inches)                    | 2.25                                    | Meives                                | 1.75                               | Deputy                                  |
| Relative Yield                    | 0.993                                   | Brown                                 | 0.988                              | Deputy                                  |

**FLEXURAL STRENGTH TEST RESULTS, 501.06**

| Age In Days | Contractor's Lab Result psi |         | Last Name of Contractor Technician | INDOT Qualified Technician Result psi |         | Last Name of INDOT Qualified Technician |
|-------------|-----------------------------|---------|------------------------------------|---------------------------------------|---------|---|
|             | Specimen                    | Average |                                    | Specimen                              | Average |   |
|             |                             | #DIV/0! |                                    |                                       | #DIV/0! |   |
| 7           | 658                         |         | Brown                              | 666                                   |         | Deputy                                  |
| 7           | 626                         | 642     | Brown                              | 620                                   | 643     | Deputy                                  |

Comments on Test Results: Carla- Slump 1.75". Air=5.7% UW= 144.4 Ry=0.986  
 John Sommers- Slump=2". Air=5.8%. UW= 142.9 Ry=0.996; Carla's Ry is only one that is low for measured air content, all others as expected for measured air content.

**Test Results From First Annual Production Lot of CMDT, 501.04**

| Properties                   | Contractor QC Results |          |          | INDOT Acceptance Results |          |          |
|------------------------------|-----------------------|----------|----------|--------------------------|----------|----------|
|                              | Sublot 1              | Sublot 2 | Sublot 3 | Sublot 1                 | Sublot 2 | Sublot 3 |
| Water/Cementitious Ratio     | 0.405                 | 0.405    | 0.423    | 0.405                    | 0.405    | 0.423    |
| Unit Weight, pcf             | 144.6                 | 143.6    | 144.1    | 144.7                    | 143.7    | 144.1    |
| Air Content, %               | 6.2                   | 6.8      | 6.4      | 6.2                      | 6.8      | 6.4      |
| Relative Yield               | 0.988                 | 0.993    | 0.991    | 0.987                    | 0.992    | 0.989    |
| Ave 7-day Flex Strength, psi | 658                   | 651      | 682      | 667                      | 611      | 633      |

Comments on Results: AZ question INDOT W/C results matching exactly to Contractor's values. INDOT and Contractor Ry's are low for measured air contents. Underyielding in Sublot 3 does not support W/C being higher than target.

**INDOT Acceptance Test Results**

**First Changes per 501.04(b)**

| Properties                   | First Sublot |
|------------------------------|--------------|
| Water/Cementitious Ratio     |              |
| Unit Weight, pcf             |              |
| Air Content, %               |              |
| Relative Yield               |              |
| Ave 7-day Flex Strength, psi |              |

Comments on Results:

**INDOT Acceptance Test Results**

**Second Changes per 501.04(b)**

| Properties                   | First Sublot |
|------------------------------|--------------|
| Water/Cementitious Ratio     |              |
| Unit Weight, pcf             |              |
| Air Content, %               |              |
| Relative Yield               |              |
| Ave 7-day Flex Strength, psi |              |

Comments on Results:

v4cmdstp

# CMDP for QC/QA PCCP

- Concrete Mix Design Production
  - Must have successful trial batch
  - Prepared on Department Spreadsheet
  - Submitted to DTE for Review and Approval

# CMDP for QC/QA PCCP

## Critical Elements for PE/PS Review

- Contract No.
- Submittal Stage, CMDP
- Specification Reference, 501
- INDOT CMD No. with **P** suffix letter
- Final Targets for UW, W/C & % Fine / Total Agg
- Signed by DTE
- DTE Notes

# INDOT CONCRETE MIX DESIGN SPREADSHEET FOR ENGLISH CONTRACTS

|                 |                               |                 |           |
|-----------------|-------------------------------|-----------------|-----------|
| MIX PRODUCER    | imi Southwest, Inc.           | CONTRACT NO.    | IR-29384  |
| PRODUCT ID      | 1455                          | INDOT DISTRICT  | Vincennes |
| PLANT LOCATION  | Lloyd Expressway - Evansville |                 |           |
| INDOT PLANT NO. | 1494                          | SUBMITTAL STAGE | CMDP      |

|               |            |                 |     |
|---------------|------------|-----------------|-----|
| INDOT CMD NO. | 086501011P | SPEC. REFERENCE | 501 |
|---------------|------------|-----------------|-----|

| FINE & COARSE AGGREGATE MATERIALS |             |   |      |      |      |         |
|-----------------------------------|-------------|---|------|------|------|---------|
| Q#                                | Source Code | PRODUCER NAME                                   | SIZE | TYPE | QUAL | LEDGES  |
| Q972021                           | 2621        | zer Crushed Stone, Evansville Redist(Cape Sar   | #8   | CS   | AP   | 804-812 |
| Q972021                           | 2632        | ilzer Crushed Stone, Evansville Redist(Evansvil | #23  | NS   |      |         |
|                                   |             |   |      |      |      |         |

\*\*% passing No. 200 sieve , CA contributes 1.6% , FA contributes 0.3%

| CEMENT & POZZOLAN MATERIALS |                            |                  |               |
|-----------------------------|----------------------------|------------------|---------------|
| W#                          | MANUFACTURER / LOCATION    | PLANT or PRODUCT | DESCRIPTION   |
| W028367                     | Lehigh Portland Cement Co. | Mitchell, IN.    | Type I Cement |
|                             |                            |                  |               |
|                             |                            |                  |               |

|              |
|--------------|
| WATER        |
| SOURCE       |
| pub. utility |
| QUALITY      |

| AIR ENTRAINING AGENT, CHEMICAL ADMIXTURES & CALCIUM CHLORIDE SOLUTION |                  |              |      |                     |
|---|------------------|--------------|------|---------------------|
| W#  | MANUFACTURER     | PRODUCT NAME | TYPE | DOSAGE RANGE oz/cwt |
| W028619   | W.R. Grace & Co. | Darex II AEA | AEA  | 0.50 to 5.0         |
| W028645   | W.R.Grace & Co.  | Daracem 55   | A    | 3.0-9.0             |
|   |                  |              |      |                     |

| BATCH PARAMETERS |               |                        |                |               |
|------------------|---------------|------------------------|----------------|---------------|
| MATERIAL         | WEIGHT<br>lbs | SP GR or<br>Bulk (ssd) | AGG.<br>ABS. % | VOLUME<br>ft³ |
| Cement           | 564           | 3.150                  | <del> </del>   | 2.87          |
| Flv Ash          |               |                        | <del> </del>   | 0.00          |

| SPECIFICATION PARAMETERS    |  |
|-----------------------------|--|
| Cement/Fly Ash Ratio, by wt |  |
| Cement/GGBFS Ratio, by wt   |  |
| Cement Reduction, %         |  |
| Flv Ash Replacement Ratio   |  |

|  |  |  |  |  |
|--|--|--|--|--|
|  |  |  |  |  |
|--|--|--|--|--|

| BATCH PARAMETERS |               |                        |                       |                           |
|------------------|---------------|------------------------|-----------------------|---------------------------|
| MATERIAL         | WEIGHT<br>lbs | SP GR or<br>Bulk (ssd) | AGG.<br>ABS. %        | VOLUME<br>ft <sup>3</sup> |
| Cement           | 564           | 3.150                  | <del>          </del> | 2.87                      |
| Fly Ash          |               |                        | <del>          </del> | 0.00                      |
| GGBFS            |               |                        | <del>          </del> | 0.00                      |
|                  |               |                        | <del>          </del> | 0.00                      |
| FA               | 1262          | 2.584                  | 1.34                  | 7.83                      |
| CA 1             | 1778          | 2.629                  | 2.22                  | 10.84                     |
| CA 2             |               |                        |                       | 0.00                      |
| water            | 230.9         | 1.000                  | <del>          </del> | 3.70                      |
| air              | 0             | 0.000                  | <del>          </del> | 1.76                      |
| ?                | 3835          | <del>          </del>  | <del>          </del> | 27.00                     |
| Yield Results:   |               |                        |                       | <b>Correct</b>            |

| SPECIFICATION PARAMETERS    |       |
|-----------------------------|-------|
| Cement/Fly Ash Ratio, by wt |       |
| Cement/GGBFS Ratio, by wt   |       |
| Cement Reduction, %         |       |
| Fly Ash Replacement Ratio   |       |
| GGBFS Replacement Ratio     |       |
| Cement Multiplier           |       |
| Fly Ash Addition, %         |       |
| GGBFS Addition, %           |       |
| Silica Fume Content, %      |       |
| Target W/(C+P), by wt       | 0.409 |
| Target Unit Weight, pcf     | 142.0 |
| FA to total Agg, % by wt    | 42    |
| FA to total Agg, % by vol   |       |
| *** % Passing 1 inch sieve  | 100   |
| ** % Passing No. 200 sieve  | 1.1   |

DISTRIBUTION AFTER APPROVAL:

Project Engineer  
 Contractor  
 Mix Producer  
 District Testing File

NAME: Mike Collins DATE: 10/27/2008  
 REPRESENTATIVE OF CONTRACTOR OR MIX PRODUCER

DTE SIGNATURE: *Mark Fligor / AET* DATE: 10/27/2008

Producer Comments: For slip form work. Back up plant is #1532 Oak Grove Rd. Evansville  
 Same source for all raw materials, different distribution yard for aggregates.

DTE Notes: Concrete can not come from plant #1532 unless it has another approved INDOT CMD NO.



# CMDP Flexibility (500-R-559)

- For Existing CMDP
  - Change in Materials
  - Adjustments to Materials
  - Other Adjustments

# Change in Materials, 501.04(a)

- Requires new CMDS with changes
- Requires Trial Batch or Verification
  - Trial Batch prior to production
    - at plant
    - in Lab
  - Verification during first day of production
- Requires new CMDP

# Adjustments to Materials, 501.04(b)

- Requires new CMDS with adjustments
- Does Not Require new Trial Batch or Verification
- Requires new CMDP

# Other Adjustments, 501.04(c)

- Other Adjustments:
  - Admixture dosage rates
  - Fine to Total Aggregate Ratio,  $\pm 3\%$
- Does Not Require new CMDS
- Does Not Require DTE Notification

# Non-QC/QA PCCP

- Section 502 of Standard Specifications
  - Contracts let on or after February 2009 have RSP
    - no major changes, only clarification
  - CMDS submitted by Contractor or Mix Producer
  - Trial Batch only required for High-Early Strength
  - DTE reviews and processes
  - CMDP issued
- Critical Elements for PE/PS review

# INDOT CONCRETE MIX DESIGN SPREADSHEET FOR ENGLISH CONTRACTS

|                 |                               |                 |            |
|-----------------|-------------------------------|-----------------|------------|
| MIX PRODUCER    | imi Southwest, Inc.           | CONTRACT NO.    | RS-29868-A |
| PRODUCT ID      | 7000                          | INDOT DISTRICT  | Vincennes  |
| PLANT LOCATION  | Lloyd Expressway - Evansville |                 |            |
| INDOT PLANT NO. | 1494                          | SUBMITTAL STAGE | CMDP       |

|               |            |                 |                       |
|---------------|------------|-----------------|-----------------------|
| INDOT CMD NO. | 096502001P | SPEC. REFERENCE | 502 Standard Strength |
|---------------|------------|-----------------|-----------------------|

| FINE & COARSE AGGREGATE MATERIALS |             |   |      |      |      |         |
|-----------------------------------|-------------|---|------|------|------|---------|
| Q#                                | Source Code | PRODUCER NAME                                       | SIZE | TYPE | QUAL | LEDGES  |
| Q972021                           | 2621        | Mulzer Crushed Stone, Evansville Redist(Cape Sandy) | #8   | CS   | AP   | 603-610 |
| Q972021                           | 2632        | Mulzer Crushed Stone, Evansville Redist(Evansville) | #23  | NS   |      |         |
|                                   |             |   |      |      |      |         |

| CEMENT & POZZOLAN MATERIALS |                                     |                  |                 |
|-----------------------------|-------------------------------------|------------------|-----------------|
| W#                          | MANUFACTURER / LOCATION             | PLANT or PRODUCT | DESCRIPTION     |
| W028367                     | Lehigh Portland Cement Co.          | Mitchell, IN.    | Type I Cement   |
| W028160                     | Mineral Resource Technologies, Inc. | Petersburg, IN   | Class F Fly Ash |
|                             |                                     |                  |                 |

|              |
|--------------|
| WATER        |
| SOURCE       |
| pub. utility |
| QUALITY      |
| potable      |

| AIR ENTRAINING AGENT, CHEMICAL ADMIXTURES & CALCIUM CHLORIDE SOLUTION |                  |              |      |                     |
|---|------------------|--------------|------|---------------------|
| W#  | MANUFACTURER     | PRODUCT NAME | TYPE | DOSAGE RANGE oz/cwt |
| W028619   | W.R. Grace & Co. | Darex II AEA | AEA  | 0.50 to 5.0         |
| W028645   | W.R. Grace & Co. | Daracem 55   | A    | 3.0-9.0             |
|   |                  |              |      |                     |

| BATCH PARAMETERS |               |                        |                |               |
|------------------|---------------|------------------------|----------------|---------------|
| MATERIAL         | WEIGHT<br>lbs | SP GR or<br>Bulk (ssd) | AGG.<br>ABS. % | VOLUME<br>ft³ |
| Cement           | 479           | 3.150                  | <del> </del>   | 2.44          |
| Flv Ash          | 106           | 2.530                  | <del> </del>   | 0.67          |

| SPECIFICATION PARAMETERS    |         |
|-----------------------------|---------|
| Cement/Fly Ash Ratio, by wt |         |
| Cement/GGBFS Ratio, by wt   |         |
| Cement Reduction, %         | 15      |
| Flv Ash Replacement Ratio   | 1.25 :1 |

|  |  |  |  |  |
|--|--|--|--|--|
|  |  |  |  |  |
|--|--|--|--|--|

| BATCH PARAMETERS |               |                                 |                                 |                           |
|------------------|---------------|---------------------------------|---------------------------------|---------------------------|
| MATERIAL         | WEIGHT<br>lbs | SP GR or<br>Bulk (ssd)          | AGG.<br>ABS. %                  | VOLUME<br>ft <sup>3</sup> |
| Cement           | 479           | 3.150                           | <del>                    </del> | 2.44                      |
| Fly Ash          | 106           | 2.530                           | <del>                    </del> | 0.67                      |
| GGBFS            |               |                                 | <del>                    </del> | 0.00                      |
|                  |               |                                 | <del>                    </del> | 0.00                      |
| FA               | 1164          | 2.584                           | 1.34                            | 7.22                      |
| CA 1             | 1795          | 2.654                           | 1.42                            | 10.84                     |
| CA 2             |               |                                 |                                 | 0.00                      |
| water            | 254.0         | 1.000                           | <del>                    </del> | 4.07                      |
| air              | 0             | 0.000                           | <del>                    </del> | 1.76                      |
| ?                | 3798          | <del>                    </del> | <del>                    </del> | 27.00                     |
| Yield Results:   |               |                                 |                                 | <b>Correct</b>            |

| SPECIFICATION PARAMETERS    |         |
|-----------------------------|---------|
| Cement/Fly Ash Ratio, by wt |         |
| Cement/GGBFS Ratio, by wt   |         |
| Cement Reduction, %         | 15      |
| Fly Ash Replacement Ratio   | 1.25 :1 |
| GGBFS Replacement Ratio     |         |
| Cement Multiplier           |         |
| Fly Ash Addition, %         |         |
| GGBFS Addition, %           |         |
| Silica Fume Content, %      |         |
| Target W/(C+P), by wt       | 0.434   |
| Target Unit Weight, pcf     | 140.7   |
| FA to total Agg, % by wt    | 39      |
| FA to total Agg, % by vol   |         |
| % Passing 1 inch sieve      |         |
| % Passing No. 200 sieve     |         |

DISTRIBUTION AFTER APPROVAL:

Project Engineer  
 Contractor  
 Mix Producer  
 District Testing File

NAME: Mike Collins DATE: 1/19/2009  
 REPRESENTATIVE OF CONTRACTOR OR MIX PRODUCER

DTE SIGNATURE:  DATE: 1/26/2009

Producer Comments:

DTE Notes: sent to AZ for processing on 1/26/09

# Patching PCCP

- Section 506 of Standard Specifications
  - Contracts let on or after February 2009
    - RSP in CIB identifies revisions to 506.03
  - Prior lettings allow CO
    - See Construction Memo 09-06
  - Otherwise Section 506.03 & .05 of 2008 Book



# CMDS For Patching PCCP

- Critical Elements for PE/PS Review
  - Contract No.
  - Submittal Stage (CMDS, ready for trial batch)
  - Specification Reference, 506 Full or Partial
  - INDOT CMD No. with **S** suffix letter
  - Signed by DTE
  - DTE Notes

# Trial Batch For Patching PCCP

- Rely on DTE for Instruction/Guidance/HELP!
- Details in CIB Special Provision
  - When a Trial Batch is Required
    - Purpose
    - Preparation
    - Procedure
  - When a Trial Batch is Not Required
    - Quantity of Partial Depth < 10 cyd
    - Quantity of Full Depth < 10 cyd

# CMDP for Patching PCCP

- CMDP Must have successful trial batch
- Submitted by Contractor or mix producer to DTE
- Prepared on Department Spreadsheet
- Critical Elements for PE/PS Review
  - Contract No.
  - Submittal Stage, CMDP
  - Specification Reference, 506 Full or Partial Depth
  - INDOT CMD No. with **P** suffix letter
  - Signed by DTE
  - DTE Notes

# INDOT CONCRETE MIX DESIGN SPREADSHEET FOR ENGLISH CONTRACTS

|                 |                               |                 |           |
|-----------------|-------------------------------|-----------------|-----------|
| MIX PRODUCER    | imi Southwest, Inc.           | CONTRACT NO.    | IR-29384  |
| PRODUCT ID      | 1453                          | INDOT DISTRICT  | Vincennes |
| PLANT LOCATION  | Lloyd Expressway - Evansville |                 |           |
| INDOT PLANT NO. | 1494                          | SUBMITTAL STAGE | CMDP      |

|               |            |                 |                |
|---------------|------------|-----------------|----------------|
| INDOT CMD NO. | 086506004P | SPEC. REFERENCE | 506 Full Depth |
|---------------|------------|-----------------|----------------|

| FINE & COARSE AGGREGATE MATERIALS |             |   |      |      |      |         |
|-----------------------------------|-------------|---|------|------|------|---------|
| Q#                                | Source Code | PRODUCER NAME                                       | SIZE | TYPE | QUAL | LEDGES  |
| Q972021                           | 2621        | Mulzer Crushed Stone, Evansville Redist(Cape Sandy) | #8   | CS   | AP   | 804-812 |
| Q972021                           | 2632        | Mulzer Crushed Stone, Evansville Redist(Evansville) | #23  | NS   |      |         |
|                                   |             |   |      |      |      |         |

| CEMENT & POZZOLAN MATERIALS |                            |                  |               |
|-----------------------------|----------------------------|------------------|---------------|
| W#                          | MANUFACTURER / LOCATION    | PLANT or PRODUCT | DESCRIPTION   |
| W028367                     | Lehigh Portland Cement Co. | Mitchell, IN.    | Type I Cement |
|                             |                            |                  |               |
|                             |                            |                  |               |

|              |
|--------------|
| WATER        |
| SOURCE       |
| pub. utility |
| QUALITY      |
| potable      |

| AIR ENTRAINING AGENT, CHEMICAL ADMIXTURES & CALCIUM CHLORIDE SOLUTION |                      |                           |            |                     |
|---|----------------------|---------------------------|------------|---------------------|
| W#  | MANUFACTURER         | PRODUCT NAME              | TYPE       | DOSAGE RANGE oz/cwt |
| W028619   | W.R. Grace & Co.     | Darex II AEA              | AEA        | 0.50 to 5.0         |
| W028645   | W.R. Grace & Co.     | Daracem 55                | A          | 3.0-9.0             |
|   | Dow Chemical Company | Liquidow Calcium Chloride | CaCl Typ L | 32.3 - 64.4         |

concentration of CaCl Type L is 29.0%      solution density is 10.69 lbs /gal      water portion is 7.59 lbs/gal

| BATCH PARAMETERS |               |                        |                |                           |
|------------------|---------------|------------------------|----------------|---------------------------|
| MATERIAL         | WEIGHT<br>lbs | SP GR or<br>Bulk (ssd) | AGG.<br>ABS. % | VOLUME<br>ft <sup>3</sup> |
| Cement           | 658           | 3.150                  |                | 3.35                      |
| Fly Ash          |               |                        |                | 0.00                      |

| SPECIFICATION PARAMETERS    |  |
|-----------------------------|--|
| Cement/Fly Ash Ratio, by wt |  |
| Cement/GGBFS Ratio, by wt   |  |
| Cement Reduction, %         |  |
| Fly Ash Replacement Ratio   |  |

|                                       |  |                               |
|---------------------------------------|--|-------------------------------|
| Dow Chemical Company                  | Liquidow Calcium Chloride   CaCl Typ L | 32.3 - 64.4                   |
| concentration of CaCl Type L is 29.0% | solution density is 10.69 lbs /gal     | water portion is 7.59 lbs/gal |

| BATCH PARAMETERS |               |                        |                 |                           |
|------------------|---------------|------------------------|-----------------|---------------------------|
| MATERIAL         | WEIGHT<br>lbs | SP GR or<br>Bulk (ssd) | AGG.<br>ABS. %  | VOLUME<br>ft <sup>3</sup> |
| Cement           | 658           | 3.150                  | <del>XXXX</del> | 3.35                      |
| Fly Ash          |               |                        | <del>XXXX</del> | 0.00                      |
| GGBFS            |               |                        | <del>XXXX</del> | 0.00                      |
|                  |               |                        | <del>XXXX</del> | 0.00                      |
| FA               | 1124          | 2.584                  | 1.34            | 6.97                      |
| CA 1             | 1740          | 2.629                  | 2.22            | 10.61                     |
| CA 2             |               |                        |                 | 0.00                      |
| water            | 269.0         | 1.000                  | <del>XXXX</del> | 4.31                      |
| air              | 0             | 0.000                  | <del>XXXX</del> | 1.76                      |
| ?                | 3791          |                        | <del>XXXX</del> | 27.00                     |
|                  |               |                        | Yield Results:  | <b>Correct</b>            |

| SPECIFICATION PARAMETERS    |       |
|-----------------------------|-------|
| Cement/Fly Ash Ratio, by wt |       |
| Cement/GGBFS Ratio, by wt   |       |
| Cement Reduction, %         |       |
| Fly Ash Replacement Ratio   |       |
| GGBFS Replacement Ratio     |       |
| Cement Multiplier           |       |
| Fly Ash Addition, %         |       |
| GGBFS Addition, %           |       |
| Silica Fume Content, %      |       |
| Target W/(C+P), by wt       | 0.409 |
| Target Unit Weight, pcf     | 140.4 |
| FA to total Agg, % by wt    | 39    |
| FA to total Agg, % by vol   |       |
| % Passing 1 inch sieve      |       |
| % Passing No. 200 sieve     |       |

**DISTRIBUTION AFTER APPROVAL:**

Project Engineer  
 Contractor  
 Mix Producer  
 District Testing File

NAME: Mike Collins DATE: 5/30/2008  
 REPRESENTATIVE OF CONTRACTOR OR MIX PRODUCER

DTE SIGNATURE:  DATE: 6/18/2008

Producer Comments: MC requesting to use INDOT CMD# 076506003P for IR-29384. CMD #076506003P is metric; this mix converted to standard units with updated Sp. Gr. and absorption. CaCl Type L added on job. 1% = 1.65 gal/cyd of solution (contributes 12.6 lbs water/cyd); 2% = 3.31gal/cyd (contributes 25.1 lbs water/cyd).

**DTE Notes: 506.03 only allows this mix to be used in 2008 construction season w/ DTE approval.**  
 CMDP 076506003P was also transferred over to RS-28668 via 086506002P on 5/14/08

# CMDP Flexibility (500-R-559)

- For Existing CMDP Patching
  - Change in Materials
  - Adjustments to Materials
  - Other Adjustments

# Change in Materials, 506.03(a)

- Requires new CMDS with changes
- Requires new Trial Batch or Verification
  - Trial Batch at plant prior to production
  - Verification during first day of production
- Requires new CMDP

# Adjustments to Materials, 506.03(b)

- Requires new CMDS with adjustments
- Does Not Require new Trial Batch or Verification
- Requires new CMDP



# Other Adjustments to Materials, 506.03(c)

- Other Adjustments:
  - Admixture dosage rates
  - Fine to Total Aggregate Ratio,  $\pm 3\%$
- Does Not Require new CMDS
- Does Not Require DTE Notification

# PE/PS Workshop

Session #9

Portland Cement  
Concrete Paving

February 26, 2009

# PE/PS Workshop



# PE/PS Workshop

- The Quality Control Plan
  - ITM 803
  - Authority/obligation to shut 'er down
  - Things to look for
    - Qualified QC Technician for Contractor
    - Contingency plans for troubleshooting mix
    - What if ???

# PE/PS Workshop



- Subbase Prep.
  - Generally 6 and 3
  - Baby the 8's
  - Watch the Underdrains
  - Drainage!

# Forming/String-lining



# Forming

- Forms:
  - Tolerances
  - Smoothness!
  - Oil (especially wood)
  - Clean 'em once in a while!



# Slipforming

- Plenty of stakes and plenty of tension
- Check it, check it again (contractor)
- Periodic depth and width checks





# Joint Materials



# Joint Materials



# Joint Materials

- Joints matter huge!
- Same plane as slab
- Cut wires and oil dowels
- Pin 'em down!
- One piece as often as possible



# Joint Materials



# Joint Materials



# The Paving Train

- Specifically for Slipforming
- Breakdown – vibration, tie bar insertion
- Finish – final shape, tie bars for next pour
- Straight edging and floating
- Micro and macrotexture
- Curing

# The Paving Train



# The Paving Train





# The Paving Train



# The Paving Train



# The Paving Train



# Curing

- Typically with white pigment cure
  - Quickly after tining
  - Good coverage, even sides
  - Repair after sawing
- Other Methods
- Same for test specimens

# Joint Sawing



# Strength Gain Monitoring With Maturity Meter



# Smoothness

- Still with a profilograph (for now)
- 501.25 for methodology and locations
- Irregular sections: straight edge
- Long Patches

# Acceptance Testing

- Run Tests in accordance with ITM's
- See 501.28 for Pay Factor determination
- Generally, looking for 100% pay
  - Exceptions: smoothness...up to 6% above
  - Thickness...up to 5% above
    - Controversy
    - Measure yourself, before submission





Questions?

---

# **SECTION 506 – PCCP PATCHING**

Prepared by Dan Streib

# Concrete Mix Designs

---

- Concrete Mix Design Submittal (CMDS) must be submitted to the DMTE a minimum of 7 calendar days prior to the trial batch utilizing the Department provided spreadsheet
- Once approved the Concrete Mix Design Submittal (CMDS) will be used by the PE/PS & contractor to conduct the trial batch. Trial batch results will be used by the DMTE in order to approve the CMDS and designated the mix as a CMDP ready for production.
- A new CMDS along with a new Trial Batch will be needed for every change in material or change in source.

# Trial Batches

- Trial batches will verify.
  - Minimum portland cement content ..... 658 lbs/cy<sup>3</sup>
  - Maximum water/cement ratio ..... 0.45
  - Minimum slump..... 2 in. (50 mm)
  - Air Content..... 6.5% ± 1.5%
  - Minimum Flexural strength, third point loading..... 300 psi (2100 kPa) at 24 h
  - Minimum flexural strength, third point loading..... 500 psi (3500 kPa) at 3 days
  
- When calcium chloride solution is added, a maximum of 2%, by weight (mass) of cement, shall be used, so remember to account for calcium usage in the trial batch and verify calcium weights with your DMTE.

# Job Control

---

## ■ Air Content

- Air test on the 1<sup>st</sup> load of the day & once every 50 cyds there after.

## ■ Flexural Strength

- Once per every 150 cyds & tested for 3 day strength requirements.



# Patch Selection











# PCCP REMOVAL

# Partial Depth Removal

---

- Vertical saw cuts, a minimum of 1" to a maximum of 3" in depth.
- Reinforcing steel encountered during removal operation shall be cause for a full depth patch.
- Patches that fall below 3" shall also be cause for a full depth patch.
- All partial depth patches shall be sandblasted and cleaned prior to placing concrete.




2008/06/21









# Full Depth Removal



The saw cut shall be full lane width and thickness of the PCCP.

---







Patches may be broken and dug.







2008/06/21



2008/06/21

Patches may be sawed and picked.









---

**All subbase material  
disturbed during the removal  
operation shall be recompact**



Patches greater than 18' long shall have type D-1 contraction joints.



# Placing Concrete

---

- The concrete shall be placed level to the adjacent PCCP and consolidated by internal vibration. The concrete shall be hand finished in accordance with 504.
- Concrete shall be cured in accordance with spec 504.04(a)(Curing Compound). In addition, polyethylene film shall be placed over the patch and covered with a 4" layer of rigid (Styrofoam) or flexible insulation (blankets).

# Opening to Traffic

- A patch may be opened to traffic in accordance with the following when calcium chloride is used.

| T                 | H  | HT | T                      | H  | HT |
|-------------------|----|----|------------------------|----|----|
| 40-42°F (4-5°C)   | 30 | 26 | 61-63°F (16-17°C)      | 14 | 9  |
| 43-45°F (6-7°C)   | 27 | 23 | 64-66°F (18-19°C)      | 14 | 9  |
| 46-48°F (8-9°C)   | 24 | 21 | 67-69°F (20-21°C)      | 14 | 8  |
| 49-51°F (10-11°C) | 21 | 19 | 70-72°F (22°C)         | 14 | 7  |
| 52-54°F (12°C)    | 19 | 16 | 73-75°F (23-24°C)      | 14 | 6  |
| 55-57°F (13-14°C) | 16 | 14 | Above 75°F(Above 24°C) | 14 | 5  |
| 58-60°F (15°C)    | 16 | 11 |                        |    |    |

PCCP patches with calcium chloride may be opened to traffic sooner than permitted by the above table if test beams indicate a modulus of rupture of 300 psi (2100 kPa) or greater

# Questions

---

?



**QC/QA PCCP**

**Tracking Lots &  
Sublots**

# Tracking Lots and Sublots

- Guidelines for determining sample locations are described in Standard Specifications, Special Provisions and ITM 802.
- The forms you use may vary from District to District.
- TD-522 QC determines the location of the plastic tests and the cores for each subplot.

TD-522 QC

# INDIANA DEPARTMENT OF TRANSPORTATION

Copies To:

## DIVISION OF MATERIALS & TESTS

FILE

### RANDOM SAMPLING OF QC/QA PCCP

CONTRACT NO. \_\_\_\_\_ PAVEMENT DEPTH \_\_\_\_\_

ITEM NO. & DESCRIPTION \_\_\_\_\_

**Lot 1**

| Sublot - Section | Date | CMD No. | Random No. (A) | SYD to be Sampled | CYD Sampled Today | Random Location (Sta., Line, Dir., Lane Width) |
|------------------|------|---------|----------------|-------------------|-------------------|--|
| 1                |      |         |                | (A x 2400)        |                   |  |
| 1-a              |      |         |                | (A x 1200)        |                   |  |
| 1-b              |      |         |                | (A x 1200) + 1200 |                   |  |
| 2                |      |         |                | (A x 2400) + 2400 |                   |  |
| 2-a              |      |         |                | (A x 1200) + 2400 |                   |  |
| 2-b              |      |         |                | (A x 1200) + 3600 |                   |  |

| Sublot -<br>Section | Date | CMD<br>No. | Random<br>No. (A) | SYD to be Sampled | C<br>Sal<br>To |
|---------------------|------|------------|-------------------|-------------------|----------------|
| 1                   |      |            |                   | (A x 2400)        |                |
| 1-a                 |      |            |                   | (A x 1200)        |                |
| 1-b                 |      |            |                   | (A x 1200) + 1200 |                |
| 2                   |      |            |                   | (A x 2400) + 2400 |                |
| 2-a                 |      |            |                   | (A x 1200) + 2400 |                |
| 2-b                 |      |            |                   | (A x 1200) + 3600 |                |
| 3                   |      |            |                   | (A x 2400) + 4800 |                |
|                     |      |            |                   |                   |                |

# Random Sampling

- Use random numbers to determine SYD to be sampled.

| Sublot - Section | Date     | CMD No. | Random No. (A) | SYD to be Sampled | CYD Sampled Today | Random Location (Sta., Line, Dir., Lane Width) |
|------------------|----------|---------|----------------|-------------------|-------------------|--|
| 1                | 9/5/2008 | SF004   | 0.321          | 770               |                   | Line J Ct & Rt Ln WB 24' Sta. 731+02           |
|                  |          |         |                | (A x 2400)        |                   |  |
| 1-a              |          | SF004   | 0.187          | 224               |                   | Line J Ct & Rt Ln WB 24' Sta. 728+97           |
|                  |          |         |                | (A x 1200)        |                   |  |
| 1-b              |          | SF004   | 0.169          | 1403              |                   | Line J Ct & Rt Ln WB 24' Sta. 733+39           |
|                  |          |         |                | (A x 1200) + 1200 |                   |  |

- For the tests, convert the sample SYD to Lft. to determine the station.
- $770 * 9 / 24' = 289'$
- $728+13 + 289' = 731+02.$



# Random Sampling

- Track daily production to determine the subplot area for each pour.

| Lot No. | Sublot No. | CMD   | Date     | W/C Ratio (Y/N) | Location (Sta to Sta, Dir, Lane, Width)                      | Area SYD | Cum. Lot Qty SYD |
|---------|------------|-------|----------|-----------------|--|----------|------------------|
| 1       | 1          | SF004 | 9/5/2008 | Y               | Line J EB Ct./Rt Lane 24'<br>Sta 728+13-737+13               | 2400.00  | 2400.00          |
| 1       | 2          | SF004 | 9/5/2008 | Y               | Line J EB Ct./Rt Lane 24'<br>Sta. 737+13-744+00              | 1832.00  | 4232.00          |
| 1       | 2          | SF004 | 9/9/2008 | Y               | Line JWN 16' Lane & 8' Shld.<br>Sta. 1745+24-1747+37         | 568.00   | 4800.00          |
| 1       | 3          | SF004 | 9/9/2008 | Y               | Line JWN 16' Lane & 8' Shld.<br>Sta. 1747+38 - 1756+03.31    | 2310.16  | 7110.16          |
| 1       | 3          | SF004 | 9/9/2008 | Y               | Line J EB Lt Turn Ln & Lt Ln<br>24' Sta. 733+10.58-732+76.89 | 89.84    | 7200.00          |

# Entering Test Results

- Suggest you use one report number for each subplot.
- R YY D SUB# 5### L S
- YY = Year
- D = District #
- SUB# = 4 Digit Submitter number
- 5### L S = Sample number where L=Lot, S=Sublot



# Tests

- IT-403QE-v1 QC/QA Water Cement Ratio
- IT-404QE-v1 QC/QA PCCP Core Length
- T121QCE-v1 CRA Yield of PC Pavement Concrete
- T152QC-v1 QC/QA Air Content of Concrete
- T97QE-v1 Flexural Strength

**INDIANA**  
**Department of Transportation**  
**Test Results**

**SAMPLE ID:** R083378750011      **CONTRACT ID:** IR-29410      **SAMPLE DATE:** 09/05/20

**MATERIAL:** 501M00010      QC/QA PCCP

**PRODUCER:** CONC1752      Berns Construction Co - Indianapolis, IN

**PRODUCT NAME:**

**LOT/SUBLOT:** Lot 1 / Sublot 1

**QUANTITY:** 2400      SYS      **SAMPLED FROM:** Jobsite

**STATION:** 731+02      **OFFSET:**      **REFERENCE:** Line J

**CONTROL TYPE:**      **BEGINNING NUMBER:**      **ENDING**

**JOB MIX FORMULA #:**

**STANDARD SAMPLE REMARKS:** Sample Information is complete and testing has started.

**AUTHORIZED** 00/00/0000      **AUTHORIZED BY:**

|                                   |                    |   |              |
|-----------------------------------|--------------------|---|--------------|
| <b>TEST METHOD:</b> IT403QE-v1    |                    | QC/QA Water Cementitious Ratio (ENGLISH)            |              |
| <b>SAMPLE TEST NUMBER:</b> 50011e |                    |   |              |
|                                   | <b>FIELD LABEL</b> | <b>RESULTS</b>                                      | <b>UNITS</b> |
|                                   | Difference         | -0.019  |              |
| <b>TEST METHOD:</b> IT404QE-v1    |                    | QC/QA PCCP Core Length (ENGLISH)                    |              |
| <b>SAMPLE TEST NUMBER:</b> 38479  |                    |   |              |
|                                   | <b>FIELD LABEL</b> | <b>RESULTS</b>                                      | <b>UNITS</b> |
|                                   | Difference         | 0.16  | IN           |
| <b>TEST METHOD:</b> T121QCE-v1    |                    | CRA Yield of PC Pavement Concrete (QC/QA) (ENGLISH) |              |

**JOB MIX FORMULA #:**

**STANDARD SAMPLE REMARKS:**Sample Information is complete and testing has started.

**AUTHORIZED** 00/00/0000

**AUTHORIZED BY:**

| <b>TEST METHOD:</b> IT403QE-v1    |  | <b>QC/QA Water Cementitious Ratio (ENGLISH)</b>            |              |
|-----------------------------------|--|--|--------------|
| <b>SAMPLE TEST NUMBER:</b> 50011e |  |  |              |
| <b>FIELD LABEL</b>                |  | <b>RESULTS</b>   | <b>UNITS</b> |
| Difference                        |  | -0.019   |              |
| <b>TEST METHOD:</b> IT404QE-v1    |  | <b>QC/QA PCCP Core Length (ENGLISH)</b>                    |              |
| <b>SAMPLE TEST NUMBER:</b> 38479  |  |  |              |
| <b>FIELD LABEL</b>                |  | <b>RESULTS</b>   | <b>UNITS</b> |
| Difference                        |  | 0.16   | IN           |
| <b>TEST METHOD:</b> T121QCE-v1    |  | <b>CRA Yield of PC Pavement Concrete (QC/QA) (ENGLISH)</b> |              |
| <b>SAMPLE TEST NUMBER:</b> 50011b |  |  |              |
| <b>FIELD LABEL</b>                |  | <b>RESULTS</b>   | <b>UNITS</b> |
| % Difference                      |  | -2.6   | %            |
| Relative Concrete Yield           |  | 1.005  |              |
| <b>TEST METHOD:</b> T152QC-v1     |  | <b>QC/QA Air Content of Concrete</b>                       |              |
| <b>SAMPLE TEST NUMBER:</b> 50011a |  |  |              |
| <b>FIELD LABEL</b>                |  | <b>RESULTS</b>   | <b>UNITS</b> |
| Difference                        |  | -0.5   | %            |
| <b>TEST METHOD:</b> T97QE-v1      |  | <b>QC/QA Flexural Strength (ENGLISH)</b>                   |              |
| <b>SAMPLE TEST NUMBER:</b> 50011c |  |  |              |
| <b>FIELD LABEL</b>                |  | <b>RESULTS</b>   | <b>UNITS</b> |
| Difference                        |  | 95   |              |