

BASIS FOR USE
OF RECURRING SPECIAL PROVISIONS
AND RECURRING PLAN DETAILS

CODE Date	Description BASIS FOR USE
100-C-146 R 3-07-00	Payment of Predetermined Minimum Wage (Davis-Bacon) IN010001 ALL PROJECTS IN LAKE, LAPORTE, PORTER, AND ST. JOSEPH COUNTIES EXCEPT BUILDING CONSTRUCTION.
100-C-147 R 3-07-00	Payment of Predetermined Minimum Wage (Davis-Bacon) IN010006 ALL PROJECTS IN COUNTIES OTHER THAN LAKE, LAPORTE, PORTER, AND ST. JOSEPH EXCEPT BUILDING CONSTRUCTION.
100-C-148 A 6-06-97	Payment of Predetermined Minimum Wage (Davis-Bacon) _____ ALL BUILDING CONSTRUCTION - DETERMINED BY CENTRAL OFFICE PERSONNEL
100-C-151 R11-19-99	Federally Funded Contract with DBE AS DETERMINED BY CONTRACTS SECTION
100-C-152 R 1-04-99	Federally Funded Contract without DBE AS DETERMINED BY CONTRACTS SECTION
100-C-166 A 2-19-01	As Built Plans ALL CONTRACTS WITH PERMANENT TRAFFIC SIGNAL INSTALLATIONS
101-B-042 R 9-1-93	Structure Numbers for Pay Items MORE THAN ONE BRIDGE FILE NUMBER IN CONTRACT, AND LUMP SUM PAY ITEMS SHOWN TO BE REQUIRED FOR EACH SUCH BRIDGE FILE
102-C-082 R 1-04-99	Schedule of Pay Items for Alternate Bids PAY ITEMS IN CONTRACT WHICH REQUIRE ALTERNATE BIDS
102-C-145 R 8-21-03	Toll Road Special Provisions ALL TOLL ROAD CONTRACTS
102-C-170 A 1-16-02	Prequalification BUILDING CONSTRUCTION
103-C-036 R 9-22-99	Owners' and Contractors' Protective Liability Insurance Coverage for Operations of the Designated Contractor ALL FEDERAL AID LOCAL PUBLIC AGENCY CONTRACTS
103-C-159 R 3-08-05	Wage Stipulations 100% STATE FUNDED CONTRACTS
104-C-112 R 6-06-03	Traffic Control Changes and On-Call Maintenance of Traffic Control Devices TRAFFIC BEING MAINTAINED ON PRESENT ROADWAY WITH NO WATCHMAN REQUIRED
104-C-139 A 9-19-95	Geotechnical Evaluation Report GEOTECHNICAL REPORT HAS BEEN DEVELOPED AND APPROVED

104-R-168 Schedule of Operations and Traffic Control for Undersealing,
R 6-06-03 Concrete Patching, Placing Underdrains, and Resurfacing
PAVEMENT UNDERSEALING, PATCHING, SHOULDER DRAIN PLACEMENT,
AND RESURFACING SPECIFIED

105-C-056 Engineer Application Personal Computer
R11-23-04 ALL CONTRACTS WITH FIELD OFFICE

105-C-071b Fax Machine in Field Office (Advanced Features)
R 5-01-03 AS DETERMINED NECESSARY BY DISTRICT CONSTRUCTION

105-C-180 Construction Engineering
A 6-17-04 ALL CONTRACTS EXCEPT MOWING, PAINTING, HERBICE

105-R-305 Pipe Structure Pay Items
R 1-04-99 ALL CONTRACTS WITH PIPE STRUCTURE PAY ITEMS

106-C-074 Basis for Use of Approved or Prequalified Materials
R 1-04-99 ALL CONTRACTS

107-B-040 Environmental Restrictions
R 1-04-99 AS DETERMINED BY PROJECT DESIGNER

107-C-029 Equal Employment Opportunity Trainees
R 7-14-98 AS DETERMINED BY CONTRACT SERVICES

107-C-051 Environmental Permits
R10-17-00 AS DETERMINED BY PROJECT DESIGNER

107-C-169 Traffic Control Device Report
A12-13-01 ALL CONTRACTS

107-C-169d Traffic Control Device Report Form
A12-13-01 ALL CONTRACTS

107-R-042a Railroad Information
R 1-04-99 HIGHWAY OVER OR UNDER RAILWAY

107-R-042b Protection of Railway Interest
R10-08-96 AS DETERMINED BY UTILITIES SECTION

107-R-169 Statements About Existing Conditions of Utilities, Additional
R 1-04-99 Right-of-Way, and Encroachments
ALL CONTRACTS

108-C-043 Incentive for Opening Project to Traffic
R 4-22-04 Ahead of Schedule
AS DETERMINED NECESSARY BY DEPARTMENT PERSONNEL WHO SET
CONTRACT TIME

108-C-078 Partnering Overhead
R10-25-99 AS DETERMINED NECESSARY BY DISTRICT CONSTRUCTION

108-C-089 Percentage of Work Required of Prime Contractor
R 1-04-99 AS DETERMINED BY CONTRACT SERVICES PERSONNEL WHO WILL PROCESS
CONTRACTS SHORTLY BEFORE LETTING

108-C-090 Latest Date to Begin Work
R 1-04-00 DELAYED START OF WORK DESIRED

108-C-091 Failure to Complete on Time for Restriction-One Structure
R 1-04-99 LANE RESTRICTIONS ON ONE LANE, PHASE, OR DIRECTION

108-C-092 Failure to Complete on Time for Restriction-Two or More Structures
R 1-04-99 LANE RESTRICTIONS ON MORE THAN ONE STRUCTURE, PHASE, OR DIRECTION

108-C-093 Failure to Complete on Time for Road Closure
R 1-04-99 AS DETERMINED NECESSARY BY DEPARTMENT PERSONNEL WHO SET CONTRACT TIME FOR CONTRACT WHICH INCLUDES DETOUR

108-C-094 Failure to Complete on Time for Intermediate Completion Date
R 1-04-99 AS DETERMINED NECESSARY BY DEPARTMENT PERSONNEL WHO SET CONTRACT TIME FOR CONTRACT IN WHICH A CERTAIN PORTION OF THE WORK IS TO BE COMPLETED BEFORE THE ENTIRE CONTRACT IS

108-C-095 Failure to Complete on Time for Calendar Completion Date
R 6-06-03 AS DETERMINED NECESSARY BY DEPARTMENT PERSONNEL WHO SET CONTRACT TIME

108-C-096 Failure to Complete on Time for Work Days
R 6-06-03 AS DETERMINED NECESSARY BY DEPARTMENT PERSONNEL WHO SET CONTRACT TIME

108-C-127 Earliest Date To Begin Work
R 1-04-00 AS DETERMINED NECESSARY BY DISTRICT CONSTRUCTION

108-C-181 Determination and Extension of Contract
A 6-17-04 ALL CONTRACTS

108-L-001 Notice to Proceed With Demolition Work
R 1-04-99 PAY ITEMS: 202-03000 HOUSES AND BUILDINGS PARCEL NO. _____ REMOVE

108-L-012 Specialty Pay Items
A 12-1-93 PAY ITEM: 202-01261 TESTING FOR ASBESTOS REMOVAL

108-R-148 Construction Equipment in Park Areas
R 1-04-99 PARK CONTRACT

109-B-148 Cost Reduction Incentive
A 3-21-01 ALL PROJECTS WITH A BRIDGE

111-C-178 Stockpiled Materials
A 3-01-04 ALL CONTRACTS EXCEPT MOWING, HERBICIDE, AND PAINTING

112-C-122 State Funded Contract with Davis-Bacon Wage Rates
R 1-04-99 AS DETERMINED BY CONTRACTS SECTION

200-R-401 Recyclable Spent Foundry Sand Application
R 2-18-05 PAY ITEMS OF BORROW OR B BORROW (REQUIRES 200-R-402 ALSO)

201-C-052 Clearing Right-of-Way
R 1-04-99 PAY ITEMS FOR CLEARING RIGHT-OF-WAY

201-M-030 Debris Removal at Bridge Structures
R 1-04-99 DEBRIS REMOVAL MAINTENANCE CONTRACT

201-R-021 Burning of Natural Growth Permitted
R 2-21-90 IDEM HAS ISSUED PERMIT TO DEPARTMENT FOR BURNING OF NATURAL GROWTH

201-R-179 Air-Curtained Open-Pit Incineration of Natural Growth Required
R 2-21-90 IDEM HAS ISSUED PERMIT TO DEPARTMENT FOR BURNING BY MEANS OF AIR-CURTAINED OPEN-PIT INCINERATOR

202-L-013 Inspection and Testing for Asbestos Material
A 6-06-03 AS DETERMINED BY PRE-ENGINEERING AND ENVIRONMENT

203-B-025 Marion County Borrow Pits
R 1-04-99 PROJECT LIMITS IN MARION COUNTY, PAY ITEM: 203-02070

203-R-121 Borrow Pit Wetland Enhancement
R 1-04-99 BORROW PIT EXCAVATION EXPECTED TO REACH WATER TABLE

203-R-155 Rock Backfill
R 5-22-02 PAY ITEM: 202-92634 ROCK BACKFILL

203-R-260 Linear Grading
R 1-04-99 PAY ITEM: 203-90014 OR 203-02080 LINEAR GRADING. EARTH WEDGING AT OUTSIDE EDGE OF SHOULDER OR BEHIND GUARDRAIL, OR MEDIAN EARTH FILLING

203-R-360 Embankments Constructed of Coal Combustion By-Products
R 7-20-04 PAY ITEM OF 3800 CUBIC METERS (5000 CYS) OR MORE OF BORROW

204-R-049 Piezometers
R 1-04-99 PAY ITEM: 204-02295 PIEZOMETER

206-B-026 Steel Sheet Piling at Railroad Grade Separation
R 1-04-99 STEEL SHEET PILING REQUIRED, RAILWAY WITHIN PROJECT LIMITS

206-B-113 General Bridge Requirements
R 6-06-03 BRIDGE REPLACEMENT OR NEW BRIDGE CONSTRUCTION

207-R-430 Recycling Existing Concrete Pavement
R12-13-04 WHEN DETERMINED NECESSARY BY DISTRICT CONSTRUCTION

207-R-481 Subgrade
A12-13-04 PAY ITEM: SUBGRADE TREATMENT, TYPE

208-R-111 Gore Area Treatment
R 1-04-99 PAY ITEM: 203-02046 GRADING OF GORE AREA

211-R-415 Crushed Glass as Bedding Material
A 2-12-02 AS DETERMINED BY MATERIALS AND TESTS DIVISION

213-R-446 Flowable Backfill
A 3-23-04 PAY ITEM: FLOWABLE BACKFILL

305-R-431 Cement Concrete Pavement Cracking and Seating
R 5-22-02 PAY ITEM: CONCRETE PAVEMENT CRACKING AND SEATING

400-R-475 HMA Revisions for 2005
R 3-22-05 PAY ITEMS FOR HMA OR QC/QA HMA

405-R-482 A11-24-04	Prime Coat ALL PROJECTS WITH SUBGRADE TREATMENT OR WITH HMA MATERIALS
411-R-432 R11-18-04	Warranted Micro-Surfacing (Renumbered from 410-R-432) PAY ITEM OF MICRO-SURFACING
500-R-476 A 8-04-04	PCCP Revisions for 2005 PAY ITEMS FOR PCCP OR QC/QA PCCP OR CONCRETE APPROACHES
506-R-491 A 3-23-05	Concrete Pavement Patching PROJECTS WITH CONCRETE PAVEMENT PATCHING
506-R-491d A 3-23-05	Concrete Pavement Patching Details RECURRING SPECIAL PROVISION 506-R-491
601-R-016 R10-03-01	Construction Zone Energy Absorbing Terminal, CZ PAY ITEM: ENERGY ABSORBING TERMINAL, CZ
601-R-146 R 1-04-99	Removal of Guardrail REMOVED GUARDRAIL TO BECOME PROPERTY OF DEPARTMENT
601-R-237 R 1-04-99	Spare Parts Package for Guardrail End Treatment AS DETERMINED BY DEPARTMENT PERSONNEL WHO SET CONTRACT TIME
601-R-338 R 3-18-04	Guardrail Blockouts PAY ITEM FOR GUARDRAIL
602-R-388d A11-16-00	Concrete Barrier AS DETERMINED BY DESIGN DIVISION
603-R-109 R 9-1-95	Gate Barricade PAY ITEM: GATE BARRICADE
603-R-414 R 12-1-02	Vinyl Coated Chain Link Fence PAY ITEM: VINYL COATED CHAIN LINK FENCE
605-R-479 A 6-17-04	Integral Concrete Curb & Gutter PAY ITEM FOR INTEGRAL CONCRETE CURB & GUTTER
609-B-163 A 6-17-04	Type I-A Joints PAY ITEM FOR REINFORCED CONCRETE BRIDGE APPROACH
609-B-163d A 7-15-04	Type I-A Joints 609-B-163
610-R-100 R 6-06-03	Median Crossovers MEDIAN CROSSOVERS REQUIRED AS SHOWN ON PLANS
615-R-020 R 1-04-99	Wood Post Parking Barriers PAY ITEM: PARKING BARRIER WOOD POST
616-R-102 R 9-1-95	Gabion Revet Mattress PAY ITEM: 616-02305 GABIONS
620-R-483 R 3-21-05	Sound Barrier Systems ANY 620 PAY ITEM
621-R-398 3-21-01	Capping Cut and Fill Slopes Steeper Than 3:1 AS DETERMINED BY PROJECT ENGINEER

622-R-209 Wildlife Habitat Species and Spacing
A 5-13-91 PAY ITEM: 622-91786 SEEDLING; SPECIES AND SPACING NOT SHOWN ON PLANS

623-M-025 Roadside Mowing
R 3-01-02 MAINTENANCE CONTRACT FOR MOWING

623-M-039 Mowing Cycles, Starting Dates, and Failure to Complete
R 6-06-03 Mowing on Time
MAINTENANCE CONTRACT FOR MOWING

624-M-024 Herbicide Treatment
R 3-01-02 MAINTENANCE CONTRACT FOR HERBICIDE TREATMENT

624-M-040 Herbicide Formula and Application Period
R 6-06-03 MAINTENANCE CONTRACT FOR HERBICIDE TREATMENT

625-R-194 Gabions
R5-22-02 PAY ITEM: 616-02305 GABIONS

626-R-165 Modified Section Concrete Median Barrier
R 3-01-02 CONCRETE MEDIAN BARRIER REQUIRED OF OTHER THAN STANDARD SHAPE

701-B-068 Bitumen Coating for Piles
R 9-01-95 BITUMEN COATED PILES

701-B-078 Oversized Predrilled Pile Holes for Integral End Bent Structures
R 5-22-02 PAY ITEM: 701-93633 PILE HOLE PREDRILLED

701-B-101d Pile Driving and Equipment Data Form
R11-05-99 PAY ITEMS FOR PILES

701-B-132 Pile Driving
R 3-05-99 AS DETERMINED BY THE PROJECT DESIGNER

701-B-154 Oversized Predrilled Pile Holes for Reduction of Pile Downdrag
A12-06-01 AS DETERMINED BY PROJECT DESIGNER

703-C-138 Reinforcing Bars
A 1-04-99 PROJECTS DESIGNED WITH HARD METRIC REINFORCING STEEL

706-B-140d Bridge Railing Type TS-1 & Guardrail Transition Type TGS-1
R 7-01-01 PAY ITEM: BRIDGE RAILING TYPE TS-S

707-B-085 Alternate Prestressed Precast Concrete I-Beam to Standard
R 5-01-03 AASHTO Type IV Prestressed Precast Concrete I-Beam
ALTERNATE BEAM SECTION PERMITTED IN LOCAL AGENCY PROJECT

709-B-070 Tinted Epoxy Penetrating Sealer
R 9-01-93 PAY ITEMS FOR SURFACE SEAL TINTED

709-M-019 Surface Seal for Steel Bridge to be Painted
R 1-04-99 PAY ITEMS: CLEAN STEEL BRIDGE, PAINT STEEL BRIDGE

713-B-076 Temporary Pipe
R 1-04-99 TEMPORARY PIPE SPECIFIED ON PLANS IN LIEU OF TEMPORARY BRIDGE

714-R-437 A 6-02-03	Oversize Precast Reinforced Concrete Box Culvert PRECAST REINFORCED CONCRETE BOX CULVERT WITH SPANS GREATER THAN 3.65 M (12')
715-R-342 A 9-04-97	Pipe Backfill Methods METRIC PROJECTS REFERRING TO PIPES BY GROUPS, EXCEPT GROUP K
715-R-361 A 9-1-98	Pipe Material Abbreviations PAY ITEMS FOR PIPE
715-R-478 A 6-17-04	Placing or Replacing Structures Under Existing Pavement PAY ITEM FOR HMA OR PCCP FOR STRUCTURE INSTALLATION, TYPE
715-R-478d A11-01-04	Structure Placement Under Existing Roadway (3 drawings) 715-R-478
717-R-152 R 5-22-02	Alternates to Structural Plate Structures PAY ITEMS FOR PIPE STRUCTURAL PLATE
718-R-397 2-26-01	Underdrain Outlet Protectors PAY ITEM FOR TYPE 2 OR TYPE 3 OUTLET PROTECTORS
718-R-397d 2-26-01	Precast Outlet Protector Type 2 or Type 3 718-R-397
720-M-021 R 9-01-95	Extension of Cast Iron Floor Drains PAY ITEM: DRAIN EXTENSION CAST IRON
720-R-104 R 6-06-03	Capped Inlet PAY ITEM: 720-44296 CAP INLET
720-T-021 R 11-1-92	Drainage Structures TRAFFIC CONTRACT - DRAINAGE STRUCTURES REQUIRED
723-R-282 R 6-02-03	Precast Reinforced Concrete 3-Sided Drainage Structure PAY ITEMS FOR CULVERT PRECAST 3 SIDED
723-R-282f R 6-02-03	Precast Reinforced Concrete 3-Sided Flat-Topped Drainage Structure AS DETERMINED BY THE DESIGNER
724-B-046 R 5-22-02	Modular Expansion Joints PAY ITEM: 724-51927 MODULAR EXPANSION JOINT
724-B-086 R 6-14-01	Approved Expansion Joint SS Devices PAY ITEM: 724-51925 EXPANSION JOINT SS
724-B-131 R 1-27-98	Polymer Modified Asphalt Joint System PAY ITEM: 501-02221 EXPANSION JOINT POLYMER MODIFIED ASPHALT
724-B-131d R 7-14-97	Polymer Modified Asphalt Joint System Details ACCOMPANIES 724-B-131
724-B-145 R 6-05-03	Expansion Joint Sealing System PAY ITEM: EXPANSION JOINT SEALING SYSTEM
724-B-147d A 1-22-01	Alternate SS Joint AS CALLED FOR BY INDOT BRIDGE REHAB SECTION

726-B-044 Bearing Assemblies
R 1-04-99 PAY ITEM: 707-95870 BEARING ASSEMBLY

727-B-012 Concrete Repair by Epoxy Injection
R 1-04-99 PAY ITEMS FOR EPOXY INJECTION EQUIPMENT, CRACK PREPARATION,
EPOXY MATERIAL

728-B-039 Masonry Coating
R 3-01-02 PAY ITEMS FOR MASONRY COATING; MASONRY COATING SPECIFIED
WITHOUT PAYMENT

729-B-009 Concrete for Patching Bridge Structures
R 3-28-96 PAY ITEM: CONCRETE, A, PATCHING

730-B-157 QC/QA Superstructure Concrete
R 8-29-03 PAY ITEM: CONCRETE, QC/QA, SUPERSTRUCTURE

731-R-202 Mechanically Stabilized Earth Retaining Walls
R 3-01-05 DETAILS FOR PROPRIETARY MECHANICALLY STABILIZED EARTH WALL
SYSTEMS INCLUDED IN PLANS

732-R-310r Modular Concrete Block Retaining Walls With Ground Reinforcing
R12-03-03 AS DETERMINED BY PROJECT DESIGNER

732-R-310u Modular Concrete Block Retaining Walls Without Ground Reinforcing
R12-03-03 AS DETERMINED BY PROJECT DESIGNER

732-R-433 Bin-Type Retaining Wall
R 5-22-02 PAY ITEMS FOR RETAINING WALL BIN TYPE _____ DESIGN _____

733-B-104 Silica Fume Modified Structural Concrete Bridge Deck Overlay
R 9-02-02 PAY ITEM: 722-51842 BRIDGE DECK OVERLAY; MICROSILICA ADMIXTURE
SPECIFIED

735-R-468 Wingwalls and Headwalls for Precast Concrete Box Culverts
A12-01-03 PAY ITEMS: CULVERT, PRECAST REINFORCED CONCRETE BOX AND
CONCRETE CULVERT EXTENSION, PRECAST REINFORCED CONCRETE
BOX SECTION

801-C-157 Certification of Temporary Traffic Control Devices
R 1-21-03 PAY ITEM: MAINTENANCE OF TRAFFIC

801-M-006 Maintaining Traffic for Maintenance or Resurface Work
R 6-06-03 MAINTENANCE OR RESURFACE CONTRACT, PAY ITEMS FOR MAINTAINING
TRAFFIC

801-R-030 Temporary U-Turns for Contractor's Vehicles
R 3-01-04 AS DETERMINED NECESSARY BY DEPARTMENT PERSONNEL WHO SET
CONTRACT TIME

801-R-253 Mobile Construction Signs
A 1-14-93 PAY ITEM: 801-92448 CONSTRUCTION SIGNS, MOBILE

801-R-471 Material Used for Temporary Ingress/Egress to Properties
A 4-12-04 AS CALLED FOR BY DISTRICT CONSTRUCTION ENGINEER

801-T-089 Maintaining Existing Traffic Signal Installation
R 7-08-99 PAY ITEM: TEMPORARY TRAFFIC SIGNAL INSTALL AND MAINTAIN

801-T-148d A 8-19-04	Channelizing Devices ALL CONTRACTS EXCEPT MOWING AND HERBICIDE
805-T-035 R11-07-02	Delay Amplifiers CONTRACT WITH TRAFFIC SIGNAL INSTALLATIONS
805-T-036 R 7-01-95	Department Furnished Materials CONTRACT WITH TRAFFIC SIGNAL INSTALLATIONS
805-T-039d A 3-16-93	Loop Testing Table PAY ITEM: 805-01439 MICROLOOP DETECTOR
805-T-041 R 7-01-95	Miscellaneous Equipment CONTRACT WITH TRAFFIC SIGNAL INSTALLATIONS
805-T-069 A 2-27-89	Traffic Signalization Locations AT LEAST 2 LOCATIONS TO BE SIGNALIZED
805-T-075 R 1-04-99	Saw Cut Requirement PAY ITEMS FOR LOOP DETECTORS
805-T-076 R 1-04-99	Solid State Controllers PAY ITEMS FOR CONTROLLER SOLID STATE PRE-TIMED
805-T-078 A 8-22-90	Electrical Insulation Sealant CONTRACT WITH TRAFFIC SIGNAL OR LIGHTING INSTALLATIONS
805-T-083 R 1-04-99	Traffic Signal Equipment Salvaged by the Contractor TRAFFIC SIGNAL EQUIPMENT TO BECOME PROPERTY OF CONTRACTOR
805-T-084 R11-24-04	Traffic Signal Equipment Salvaged by the Department PAY ITEM: 202-96151 TRANSPORTATION OF SALVAGEABLE ITEMS
805-T-085 R 7-01-95	Signal Bulb Replacement, Aerial Inspection, and Loop Replacement TRAFFIC MAINTENANCE CONTRACT FOR SIGNAL BULB REPLACEMENT
805-T-086 R 7-1-95	Traffic Signal Maintenance and Repair TRAFFIC MAINTENANCE CONTRACT FOR NON-BULB SIGNAL MAINTENANCE
805-T-093 A 2-2-93	Detector Card Rack and Detector Modules PAY ITEM: DETECTOR MODULE
805-T-095 R 4-16-01	Signal Controllers PAY ITEMS FOR CONTROLLER AND CABINET
805-T-105 A 7-01-95	Conversion of Metric Standards ENGLISH DESIGNED CONTRACTS; PAY ITEMS FOR TRAFFIC SIGNAL
805-T-123 A11-20-00	Video Vehicle Detector System PAY ITEM: VIDEO VEHICLE DETECTOR SYSTEM
805-T-124 A11-20-00	Integrated Video Vehicle Detector System PAY ITEM: INTEGRATED VIDEO VEHICLE DETECTOR SYSTEM
805-T-144 A 6-13-03	Traffic Vehicle Detection Loop Shape PAY ITEM: SAW CUT FOR ROADWAY LOOP AND SEALANT

807-T-087 Highway Illumination Maintenance and Repair
R 7-01-95 TRAFFIC MAINTENANCE CONTRACT FOR LIGHTING MAINTENANCE

808-B-114 Repainting No-Passing Zone Pavement Markings
R 1-04-99 BRIDGE CONTRACT; PAY ITEM FOR LINE SOLID YELLOW 4 IN. USED AS
NO-PASSING ZONE MARKING

808-T-116 Snowplowable Raised Pavement Markers
A 1-03-00 PAY ITEM FOR SNOWPLOWABLE RAISED PAVEMENT MARKERS

808-T-141 Removal of Snowplowable Raised Pavement Markers
R 6-06-03 PAY ITEM: SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE

904-R-480 Aggregates
A 6-17-04 ALL CONTRACTS EXCEPT MOWING, PAINTING, HERBICIDE

912-R-477 Admixtures for Use in Concrete
A 7-15-04 ALL CONTRACTS EXCEPT MOWING, PAINTING, HERBICIDE

913-T-117 Encapsulated Lens High Intensity Reflective Sheeting
A 1-12-00 PAY ITEM FOR SIGN, SHEET

913-T-120 Reflective Lenses for Snowplowable Raised Pavement Markers
R 6-13-01 PAY ITEM FOR SNOWPLOWABLE RAISED PAVEMENT MARKER

913-T-137 Traffic Signal Materials and Equipment
R11-24-04 ANY 805 PAY ITEM