

RIETH-RILEY CONSTRUCTION Co., Inc.

100% Quality • 100% Employee Owned • Over 100 Years

INVITATION TO BID

July 22 ,2024

Minority and Women's Business Enterprises Division
402 W Washington Street, Room 2469
Indianapolis, IN 46204

Project: BM-24-115 16th St and MLK JR St over Canal Bridge Rehabilitation

Location: Marion County

Bid Date: August 8, 2024

Quotes Due: August 7, 2024, by 9am

To Whom It May Concern:

Rieth-Riley Construction Co., Inc. is bidding on the project listed above as a prime contractor for **BM-24-115 16th St and MLK JR St over Canal Bridge Rehabilitation** We are inviting quotations from MBE/WBE/IVOSB subcontractor/supplier firms that might be interested in partnering with us on the project.

Subcontractor/Supplier opportunities include TRAFFIC SIGNS/MARKINGS, PIPE, SOD/SEED, ELECTRICAL, AGGREGATE, TRUCKING, SURVEYING, CONCRETE FLATWORK, REBAR, CLEARING, MILLING, READY MIX, SWQCP, TESTING, GUARDRAIL, RESTEEL/METAL DECK, SURFACE SEAL, POTHOLING

Plans and specifications are available for review on Repro Graphix or by request through Rieth-Riley's Estimator.

Questions regarding this project should be directed to Mike Compton at mcompton@rieth-riley.com or 317-634-5561.

Written quotations should be sent via email to mcompton@rieth-riley.com no later than August 7, 2024 by 9am.

Thank you



PART 3
CONTRACT ITEMS AND UNIT PRICES

Project Number: BM-24-115

Contractor:

Project Name: 16th Street and Dr. Martin Luther King Jr. Street over the Canal STBG FY2025

Bid Date: 07/11/2024

LN	Pay Item Number	Pay Item Name	Quantity	Unit	UnitPrice	Price
001	I-105-06845	CONSTRUCTION ENGINEERING	1.00	LSUM	\$	\$
002	I-110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LSUM	\$	\$
003	I-201-52370	CLEARING RIGHT OF WAY	1.00	LSUM	\$	\$
004	D-202-01000	SIDEWALK, REMOVE (ALL TYPES)	529.00	SYS	\$	\$
005	I-202-02240	PAVEMENT REMOVAL	2,215.00	SYD	\$	\$
006	D-202-02250	DRIVEWAY, REMOVE (ALL TYPES)	176.00	SYS	\$	\$
007	D-202-02300	CURB, REMOVE (ALL TYPES)	933.00	LFT	\$	\$
008	I-202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LSUM	\$	\$
009	I-202-74035	SIGN, REMOVE	3.00	EACH	\$	\$
010	I-202-90277	DETECTOR HOUSING, REMOVE	3.00	EACH	\$	\$
011	I-202-91840	FENCE, CHAIN. LINK, REMOVE	44.00	LFT	\$	\$
012	I-202-95579	SERVICE POINT, REMOVE	1.00	EACH	\$	\$
013	I-203-02000	EXCAVATION, COMMON	80.00	CYS	\$	\$
014	I-203-02070	BORROW	914.00	CYS	\$	\$
015	I-205-03371	SEDIMENT, REMOVE	543.00	CYS	\$	\$
016	I-205-12108	STORM WATER MANAGEMENT BUDGET	20,543.00	DOL	\$1.00	\$20,543
017	I-207-08264	SUBGRADE TREATMENT, TYPE II	62.00	SYD	\$	\$
018	I-207-09935	SUBGRADE TREATMENT, TYPE IC	529.00	SYD	\$	\$
019	I-211-09265	STRUCTURE BACKFILL, TYPE 2	32.00	CYS	\$	\$

PART 3
CONTRACT ITEMS AND UNIT PRICES

LN	Pay Item Number	Pay Item Name	Quantity	Unit	UnitPrice	Price
020	I-213-08068	DRILLED HOLE FOR FLOWABLE BACKFILL	160.00	EACH	\$	\$
021	I-213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	2,871.00	CYS	\$	\$
022	I-301-12233	COMPACTED AGGREGATE NO 8	16.00	CYS	\$	\$
023	I-304-07494	WIDENING WITH HMA, TYPE C	349.00	TONS	\$	\$
024	I-306-08034	MILLING, ASPHALT, 1 1/2 IN.	2,300.00	SYD	\$	\$
025	I-401-10258	JOINT ADHESIVE, SURFACE	1,718.00	LFT	\$	\$
026	I-401-10259	JOINT ADHESIVE, INTERMEDIATE	1,193.00	LFT	\$	\$
027	I-401-11785	LIQUID ASPHALT SEALANT	1,718.00	LFT	\$	\$
028	D-402-02130	HMA SURFACE, TYPE C	191.00	TON	\$	\$
029	I-406-05521	ASPHALT FOR TACK COAT	4,384.00	SYD	\$	\$
030	I-503-05240	D-1 CONTRACTION JOINT	51.00	LFT	\$	\$
031	I-601-01522	GUARDRAIL, TRANSITION, TYPE TGB	1.00	EACH	\$	\$
032	I-601-02241	GUARDRAIL, REMOVE	27.00	LFT	\$	\$
033	I-601-05999	CURVED TERMINAL END	1.00	EACH	\$	\$
034	I-604-06070	SIDEWALK, CONCRETE	621.00	SYD	\$	\$
035	I-604-08086	CURB RAMP, CONCRETE	15.20	SYD	\$	\$
036	I-604-12083	DETECTABLE WARNING SURFACES	4.20	SYD	\$	\$
037	I-605-06120	CURB, CONCRETE	816.00	LFT	\$	\$
038	I-610-07487	HMA FOR APPROACHES, TYPE B	29.00	TON	\$	\$
039	I-621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH	\$	\$

PART 3
CONTRACT ITEMS AND UNIT PRICES

LN	Pay Item Number	Pay Item Name	Quantity	Unit	UnitPrice	Price
040	I-621-06560	MULCHED SEEDING U	2,576.00	SYD	\$	\$
041	I-621-06567	WATER	1.00	KGAL	\$	\$
042	I-621-06574	SODDING	9.00	SYD	\$	\$
043	I-622-05651	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2.5 TO 3.5 IN.	25.00	EACH	\$	\$
044	I-702-90915	CONCRETE, CLASS, A	45.00	CYS	\$	\$
045	I-703-06029	REINFORCING BARS, EPOXY COATED	7,330.00	LBS	\$	\$
046	I-706-06372	CONCRETE BRIDGE RAILING TRANSITION, TTX (MODIFIED)	1.00	EACH	\$	\$
047	I-706-08502	REINFORCED CONCRETE MOMENT SLAB, 15 IN.	197.00	SYD	\$	\$
048	I-706-09965	RAILING, CONCRETE TX (MODIFIED)	210.40	LFT	\$	\$
049	I-709-51821	SURFACE SEAL	1.00	LSUM	\$	\$
050	I-715-05123	PIPE, TYPE 1, CIRCULAR, 24 IN.	204.00	LFT	\$	\$
051	I-715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	167.00	LFT	\$	\$
052	I-715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	8.00	LFT	\$	\$
053	D-715-10110	CORE DRILL EXISTING STRUCTURE, CONNECT PIPING	2.00	EACH	\$	\$
054	D-720-44002	CASTING, REMOVE AND ADJUST TO GRADE	1.00	EACH	\$	\$
055	I-720-44040	CASTING, 7, FURNISH AND ADJUST TO GRADE	2.00	EACH	\$	\$
056	I-720-44080	CASTING, 15, FURNISH AND ADJUST TO GRADE	1.00	EACH	\$	\$
057	D-720-96997	STRUCTURE, EXISTING, CLEAN	4.00	EACH	\$	\$
058	I-720-98174	INLET, B15	3.00	EACH	\$	\$
059	I-720-98555	INLET, C15	1.00	EACH	\$	\$

PART 3
CONTRACT ITEMS AND UNIT PRICES

LN	Pay Item Number	Pay Item Name	Quantity	Unit	UnitPrice	Price
060	I-801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00	EACH	\$	\$
061	I-801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2,730.00	LFT	\$	\$
062	I-801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	1,284.00	LFT	\$	\$
063	I-801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATI ON ARROW	3.00	EACH	\$	\$
064	I-801-06625	DETOUR ROUTE MARKER ASSEMBLY	43.00	EACH	\$	\$
065	I-801-06640	CONSTRUCTION SIGN, A	46.00	EACH	\$	\$
066	I-801-06645	CONSTRUCTION SIGN, B	32.00	EACH	\$	\$
067	I-801-06710	FLASHING ARROW SIGN	180.00	DAY	\$	\$
068	I-801-06775	MAINTAINING TRAFFIC	1.00	LSUM	\$	\$
069	I-801-07118	BARRICADE, III-A	240.00	LFT	\$	\$
070	I-801-07119	BARRICADE, III-B	96.00	LFT	\$	\$
071	I-801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	260.00	LFT	\$	\$
072	I-805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	4.00	EACH	\$	\$
073	I-805-01842	HANDHOLE SIGNAL TYPE 1	1.00	EACH	\$	\$
074	D-805-02060	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	3.00	EACH	\$	\$
075	I-805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	4.00	EACH	\$	\$
076	I-805-02596	CONDUIT RISER WITH WEATHERHEAD, STEEL	2.00	EACH	\$	\$
077	I-805-08214	CONDUIT, PVC, 2 IN. SCHEDULE 40	405.00	LFT	\$	\$
078	I-805-08487	BACKPLATE, SIGNAL	8.00	EACH	\$	\$
079	I-805-11817	PEDESTRIAN PUSH BUTTON, APS	8.00	EACH	\$	\$

PART 3
CONTRACT ITEMS AND UNIT PRICES

LN	Pay Item Number	Pay Item Name	Quantity	Unit	UnitPrice	Price
080	D-805-78000	DETECTION LOOP, 6 FT DIA.	16.00	EACH	\$	\$
081	I-805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	530.00	LFT	\$	\$
082	I-805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	530.00	LFT	\$	\$
083	I-805-78785	SIGNAL DETECTOR HOUSING	3.00	EACH	\$	\$
084	I-805-90005	SIGNAL POLE, PEDESTAL, 10 FT	3.00	EACH	\$	\$
085	I-805-91703	CONDUIT, STEEL, GALVANIZED, 1.5 IN.	5.00	LFT	\$	\$
086	I-807-12354	METERED SERVICE POINT	1.00	EACH	\$	\$
087	I-807-78590	HANDHOLE	1.00	EACH	\$	\$
088	I-807-95515	SERVICE POINT WEATHERHEAD	1.00	EACH	\$	\$
089	I-808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	240.00	LFT	\$	\$
090	I-808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	92.00	LFT	\$	\$
091	I-808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	146.00	LFT	\$	\$
092	I-808-06716	LINE, REMOVE	60.00	LFT	\$	\$
093	I-808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	368.00	LFT	\$	\$
094	I-808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	67.00	LFT	\$	\$
095	I-808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW W	2.00	EACH	\$	\$
096	I-808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	1.00	EACH	\$	\$

TOTAL BID AMOUNT (in figures) \$
