

Schedule of Pay Items Letting Date November 15, 2023 Letting ID 231115

Call: 131

Contract: R -41299-A

Section No.: 1 ROAD RECONSTRUCTION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	20.00 EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	20.00 EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0005	109-08360	CONTRACT LIENS	1.00 DOL
0006	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0007	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0008	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0009	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0010	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0011	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00 DOL
0012	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0013	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0014	201-52370	CLEARING RIGHT-OF-WAY	1.00 LS
0015	202-52710	SIDEWALK CONCRETE, REMOVE	321.00 SYS
0016	202-91385	INLET, REMOVE	7.00 EACH
0017	202-93047	MANHOLE, REMOVE	5.00 EACH
0018	202-96133	PIPE, REMOVE	773.00 LFT
0019	203-02000	EXCAVATION, COMMON	13985.00 CYS
0020	205-12108	STORMWATER MANAGEMENT BUDGET	18536.00 DOL
0021	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0022	205-12618	SWQCP PREPARATION	1.00 LS
0023	206-51220	EXCAVATION, WET	70.00 CYS
0024	206-51235	COFFERDAM	1.00 LS
0025	207-08264	SUBGRADE TREATMENT, TYPE II	2274.00 SYS
0026	207-08266	SUBGRADE TREATMENT, TYPE III	3722.00 SYS
0027	207-12635	SUBGRADE TREATMENT, TYPE IBC	30523.00 SYS
0028	211-09264	STRUCTURE BACKFILL, TYPE 1	1249.00 CYS
0029	211-09265	STRUCTURE BACKFILL, TYPE 2	172.00 CYS
0030	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	5.00 CYS
0031	214-11796	GEOGRID, TYPE IB	766.00 SYS

0032	214-12238	GEOTEXTILE FOR PAVEMENT, TYPE 2A	3345.00	SYS
0033	301-12232	COMPACTED AGGREGATE, NO. 5	223.00	CYS
0034	301-12234	COMPACTED AGGREGATE, NO. 53	5431.00	CYS
0035	302-07455	DENSE GRADED SUBBASE	252.00	CYS
0036	302-12387	AGGREGATE DRAINAGE LAYER	5946.00	CYS
0037	303-01180	COMPACTED AGGREGATE, NO. 53	71.00	TON
0038	304-12623	HMA PATCHING, FULL DEPTH, TYPE B	28.00	TON
0039	306-08034	MILLING, ASPHALT, 1 1/2 IN.	462.00	SYS
0040	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	2234.00	TON
0041	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	5191.00	TON
0042	401-10258	JOINT ADHESIVE, SURFACE	15665.00	LFT
0043	401-10259	JOINT ADHESIVE, INTERMEDIATE	11100.00	LFT
0044	401-11785	LIQUID ASPHALT SEALANT	15665.00	LFT
0045	406-05520	ASPHALT FOR TACK COAT	16.00	TON
0046	601-03464	GUARDRAIL, STEEL CURVED TERMINAL END SECTION	1.00	EACH
0047	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	362.50	LFT
0048	601-94689	GUARDRAIL END TREATMENT, TYPE OS	1.00	EACH
0049	604-05528	HMA FOR SIDEWALK	667.00	TON
0050	604-06070	SIDEWALK, CONCRETE	1275.00	SYS
0051	604-08086	CURB RAMP, CONCRETE	265.00	SYS
0052	604-12083	DETECTABLE WARNING SURFACES	85.00	SYS
0053	604-95344	HANDRAIL, PEDESTRIAN	32.00	LFT
0054	605-06140	CURB AND GUTTER, CONCRETE	6030.00	LFT
0055	605-06250	CENTER CURB, C CONCRETE	102.00	SYS
0056	610-07487	HMA FOR APPROACHES, TYPE B	169.00	TON
0057	610-08446	PCCP FOR APPROACHES, 6 IN.	1508.00	SYS
0058	611-08232	MAILBOX ASSEMBLY, RESET, SINGLE	8.00	EACH
0059	611-08233	MAILBOX ASSEMBLY, RESET, DOUBLE	1.00	EACH
0060	616-06405	RIPRAP, REVETMENT	389.00	TON
0061	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	324.00	SYS
0062	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0063	621-06560	MULCHED SEEDING, TYPE U	7778.00	SYS
0064	621-06567	WATER	29.00	KGAL
0065	621-06575	SODDING, NURSERY	3889.00	SYS
0066	622-05649	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. TO 2 IN.	20.00	EACH
0067	622-05650	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 IN. TO 2.5 IN.	20.00	EACH
0068	622-05651	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2.5 IN. TO 3.5 IN.	45.00	EACH

0069	628-09403	FIELD OFFICE, TYPE C	18.00	MOS
0070	702-04325	TEMPORARY SHORING	1.00	LS
0071	702-51015	CONCRETE, B, FOOTINGS	109.70	CYS
0072	703-06028	REINFORCING BARS	2920.00	LBS
0073	703-06029	REINFORCING BARS, EPOXY COATED	15528.00	LBS
0074	704-51002	CONCRETE, C, SUPERSTRUCTURE	83.00	CYS
0075	711-04845	BRIDGE, STEEL TRUSS, PRE-ENGINEERED	1.00	LS
0076	715-03321	SAFETY METAL END SECTION, 6:1, DIAMETER 12 IN.	3.00	EACH
0077	715-03475	SAFETY METAL END SECTION, 4:1, DIAMETER 15 IN.	5.00	EACH
0078	715-03476	SAFETY METAL END SECTION, 4:1, DIAMETER 24 IN.	1.00	EACH
0079	715-03487	SAFETY METAL END SECTION, 4:1, DIAMETER 30 IN.	1.00	EACH
0080	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	660.00	LFT
0081	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	949.00	LFT
0082	715-05151	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	306.00	LFT
0083	715-05152	PIPE, TYPE 2, CIRCULAR, DIAMETER 18 IN.	384.00	LFT
0084	715-05154	PIPE, TYPE 2, CIRCULAR, DIAMETER 24 IN.	838.00	LFT
0085	715-05156	PIPE, TYPE 2, CIRCULAR, DIAMETER 30 IN.	1189.00	LFT
0086	715-92253	SEWER SANITARY LATERAL RECONNECT	1.00	EACH
0087	716-09396	PIPE INSTALLATION, TRENCHLESS, 2 IN.	170.00	LFT
0088	720-01092	MANHOLE, TYPE J15, MODIFIED	1.00	EACH
0089	720-12660	MANHOLE, TYPE H15	1.00	EACH
0090	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	25.00	EACH
0091	720-44025	CASTING, TYPE 4, FURNISH AND ADJUST TO GRADE	1.00	EACH
0092	720-45030	INLET, TYPE E7	1.00	EACH
0093	720-45035	INLET, TYPE F7	3.00	EACH
0094	720-45410	MANHOLE, TYPE C4	1.00	EACH
0095	720-95422	MANHOLE, TYPE J4	10.00	EACH
0096	720-97008	FIRE HYDRANT ASSEMBLY, RELOCATE	3.00	EACH
0097	720-98174	INLET, TYPE B15	15.00	EACH
0098	720-98555	INLET, TYPE C15	5.00	EACH
0099	801-03291	CONSTRUCTION SIGN, TYPE D	2.00	EACH
0100	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00	EACH
0101	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	24000.00	LFT
0102	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	2.00	EACH
0103	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	120.00	LFT
0104	801-06625	DETOUR ROUTE MARKER ASSEMBLY	10.00	EACH
0105	801-06640	CONSTRUCTION SIGN, TYPE A	78.00	EACH

0106	801-06645	CONSTRUCTION SIGN, TYPE B	88.00 EACH
0107	801-06775	MAINTAINING TRAFFIC	1.00 LS
0108	801-07119	BARRICADE, TYPE III-B	144.00 LFT
0109	801-11990	TEMPORARY CURB RAMP	4.00 EACH
0110	801-12081	PORTABLE SIGNAL	1.00 LS
0111	801-12482	DRIVEWAY ASSISTANCE DEVICE	7.00 EACH
0112	801-12641	TEMPORARY ACCESSIBLE PEDESTRIAN PATH	287.00 SYS
0113	801-12862	TEMPORARY PEDESTRIAN CHANNELIZER	810.00 LFT
0114	802-04089	SIGN, SHEET, REMOVE	10.00 EACH
0115	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	254.00 LFT
0116	802-07057	SIGN, PANEL, WITH LEGEND	151.00 SFT
0117	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	9.00 EACH
0118	802-07060	SIGN, SHEET, RELOCATE	7.00 EACH
0119	805-09720	CONDUIT, STEEL, GALVANIZED, 0.75 IN. UNDERGROUND	850.00 LFT
0120	805-11375	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 25 FT	1.00 EACH
0121	805-11377	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 35 FT	3.00 EACH
0122	805-11383	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, TYPE A	4.00 EACH
0123	805-11744	HANDHOLE, SIGNAL, TYPE 2	4.00 EACH
0124	805-11814	CONDUIT, HDPE, 2 IN. SCHEDULE 40	965.00 LFT
0125	805-11817	PEDESTRIAN PUSH BUTTON, APS	4.00 EACH
0126	805-78205	TRAFFIC SIGNAL HEAD, NO. 3 SECTION, 12 IN.	8.00 EACH
0127	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GAUGE	200.00 LFT
0128	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	400.00 LFT
0129	805-78930	CONTROLLER CABINET FOUNDATION, TYPE M	2.00 EACH
0130	805-93555	CONTROLLER AND CABINET, TYPE M	2.00 EACH
0131	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	2330.00 LFT
0132	807-12202	LUMINAIRE, LOW LUMEN ROADWAY	22.00 EACH
0133	807-12791	LIGHTING FOUNDATION, CONVENTIONAL POLE, CONCRETE, WITH GROUNDING	21.00 EACH
0134	807-12822	LIGHT POLE, 38 FT E.M.H., 8 FT MAST ARM, ANCHOR BASE	22.00 EACH
0135	807-86805	SERVICE POINT, TYPE I	3.00 EACH
0136	807-95889	WIRE, NO. 10 COPPER, 1/C	2550.00 LFT
0137	807-97237	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, 4 1/C	965.00 LFT
0138	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	355.00 LFT
0139	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2320.00 LFT
0140	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	120.00 LFT
0141	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	70.00 LFT
0142	808-06716	LINE, REMOVE	2500.00 LFT

0143	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0144	808-12032	GROOVING FOR PAVEMENT MARKINGS	10880.00	LFT
0145	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	510.00	LFT
0146	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	3892.00	LFT
0147	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	363.00	LFT
0148	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	26.00	EACH
0149	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	2760.00	LFT
0150	808-96016	LINE, THERMOPLASTIC, SOLID, YELLOW, 12 IN.	680.00	LFT